

**A CATALOGUE OF ARCHAEOLOGICAL FEATURES
ON BIG MOOR AND RAMSLEY MOOR, BASLOW
AND HOLMESFIELD, DERBYSHIRE
(Scheduled Ancient Monument 136)**

by Stewart Ainsworth (RCHME) and John Barnatt (PDNPA)

**ROYAL COMMISSION ON THE
HISTORICAL MONUMENTS OF ENGLAND
&
PEAK DISTRICT NATIONAL PARK AUTHORITY**

**ROYAL COMMISSION ON THE
HISTORICAL MONUMENTS OF ENGLAND
&
PEAK DISTRICT NATIONAL PARK AUTHORITY**

**BIG MOOR AND RAMSLEY MOOR
NORTH EAST DERBYSHIRE/DERBYSHIRE DALES
DERBYSHIRE**

NMR No: SK 27 NE 1,13,18,19,28,35,41,53,54,78-98

NGR: SK 27300 75600

SCHEDULED ANCIENT MONUMENT No: Derbyshire 136

RSM No: -

Surveyed: 1991-96
Surveyed by S.Ainsworth, C.Tuck (RCHME); J.Barnatt, W.Bevan, P.Sidebottom (PDNPA)
Report by S.Ainsworth and J.Barnatt
Drawings by P.Sinton

**Copyright RCHME and PDNPA 1998
Applications for reproduction should be made to the RCHME and PDNPA**

**RCHME York office: RCHME, Shelley House, Acomb Road, York YO2 4HB
Tel: 01904 784411 Fax: 01904 795348 e-mail: york@rchme.gov.uk**

**Headquarters: RCHME, National Monuments Record Centre, Great Western Village, Kemble Drive, Swindon SN2 2GZ
Tel: 01793 414700 Fax: 01793 414707 e-mail: info@rchme.gov.uk World Wide Web: <http://www.rchme.gov.uk>**

**Peak District National Park Authority: Aldern House, Baslow Road, Bakewell, Derbyshire DE45 1AE
Tel: 01629 816200 Fax: 01629 816310 e-mail: Aldern@PeakDistrict.org**

CONTENTS

INTRODUCTION	2
FORMAT	3
INDEX	4
CATALOGUE	42
Sheet 1	42
Sheet 2	42
Sheet 3	47
Sheet 4	56
Sheet 5	90
Sheet 6	100
Sheet 7	103
Sheet 8	108
Sheet 9	121
Sheet 10	132
Sheet 11	132
Sheet 12	134
Sheet 13	135
Sheet 15	140
Sheet 16	141
Sheet 17	143
Sheet 18	143
CONCORDANCE	144
PREHISTORIC FEATURES	144
HISTORIC FEATURES	153
APPENDICES	

Appendix 1: Index Diagram for Sheet Numbers

INTRODUCTION

This Catalogue has been produced to complement the survey report '**An Archaeological Survey of the Landscape on Big Moor and Ramsley Moor, Baslow and Holmesfield, Derbyshire**'; the basis of the feature numbering system employed is described in the **Methodology** section of that report.

Overlays (for each sheet), which also provide a key between the features in the Catalogue and the survey drawings, are included in the site archive. There is no Sheet 14. National Monuments Record (NMR) numbers have been allocated to individual or groups of monuments in the above report.

FORMAT

In the Catalogue the format of each feature record is as follows;

Feature Number - Type of feature; Period; National Grid Reference*; Description

* in order to facilitate reference to drawn survey plans, all grid references within the Catalogue are given as twelve figure rectangular coordinates which correspond to distance in metres east and north respectively from the false origin of the Ordnance Survey National Grid (this facilitates direct correlation with the instrumental survey control data). To convert these numeric coordinates into the more familiar alpha-numeric notation of published OS maps, the first digit of both the easting and northing should be omitted, and the new ten figure grid reference prefaced by the 100km map square identifier SK. For example a grid reference given in the Catalogue as 427207,374966 is the equivalent of the alpha-numeric SK27207 74966. All grid references are to the nearest metre. Linear features are indicated by two grid references for the terminals.

INDEX

Feature number followed by sheet number (in bold).

2	3
4	3
14	3
15	4
16	4
17	4
25	4
26	4
29	4
31	4
32	4
33	4
34	4
35	4
36	4
37	4
38	4
40	4
41	4
42	4
46	4
93	4
94	4
104	4
105	4
106	4
107	4
108	4
109	4
110	4
111	4
112	4
113	4
114	4
115	4
116	4
117	4
118	4
119	4
120	4
121	4
122	4
123	4
125	4

126	4
127	4
128	4
129	4
130	4
132	4
133	4
134	4
135	4
136	4
137	4
138	4
139	4
142	4
143	4
144	4
145	4
147	4
148	4
149	4
150	4
151	4
153	4
154	4
155	4
160	4
161	4
164	4
165	4
166	4
168	4
169	4
172	4
173	4
174	4
175	4
176	4
177	4
178	4
179	4
180	4
181	4
182	4
198	4
199	4
200	4
201	4
202	4
203	4
204	4

205	4
206	4
207	4
208	4
209	4
210	4
211	4
212	4
213	4
214	4
215	4
216	4
217	4
218	4
219	4
220	4
221	4
222	4
223	4
224	4
225	4
226	4
227	4
229	4
230	4
231	4
232	4
234	4
235	4
236	4
237	4
239	4
240	4
241	4
242	4
243	4
244	4
245	4
246	4
247	4
248	4
249	4
251	4
252	4
253	4
255	4
256	4
257	4
259	4
260	4

261	4
265	4
266	4
267	4
268	4
270	4
274	4
275	4
276	4
277	4
278	4
280	4
281	4
282	4
283	4
284	4
285	4
286	4
287	4
288	4
289	4
290	4
292	4
293	4
294	4
295	4
296	4
297	4
298	4
299	4
300	4
301	4
302	4
303	4
304	4
305	4
306	4
308	4
309	4
310	4
312	4
314	4
315	4
316	4
317	4
318	4
321	4
322	4
323	4
324	4

325	4
326	4
327	4
330	4
331	4
332	4
333	4
334	4
335	4
336	4
337	4
338	4
342	4
343	4
344	4
345	4
347	4
349	4
350	4
351	4
352	4
354	4
355	4
356	4
357	4
358	4
359	4
360	4
361	4
362	4
363	4
365	4
366	4
367	4
368	4
369	4
370	4
371	4
372	4
373	4
374	4
375	4
376	4
378	4
380	4
381	4
382	4
383	4
384	4
385	4

386	4
387	4
388	4
389	4
390	4
392	4
393	4
394	4
395	4
396	4
397	4
398	4
399	4
400	4
401	4
402	4
403	4
404	4
405	4
410	4
411	4
412	8
413	8
414	8
415	8
416	8
417	8
418	8
419	8
420	8
421	8
422	4
423	4
424	4
425	4
427	4
428	4
429	8
430	8
431	8
432	8
433	8
434	8
435	4
435	4
436	4
437	4
438	4
439	4
466	4

467	4
468	4
469	4
470	4
471	4
472	5
473	5
474	8
475	8
476	8
477	8
478	8
479	8
480	8
481	8
482	8
483	8
484	8
485	8
486	8
488	8
489	8
490	8
491	8
492	8
493	8
494	8
495	8
496	8
497	8
498	8
499	8
500	8
501	8
502	8
503	8
504	8
505	8
506	8
507	8
508	8
509	8
510	8
511	8
512	8
513	8
514	8
515	8
516	8
517	8

518	8
519	8
520	8
521	8
522	8
523	8
524	8
526	8
527	8
528	8
529	8
530	8
531	8
532	8
533	8
534	8
535	8
536	8
537	8
538	8
539	8
541	8
542	8
543	8
544	8
545	8
546	8
548	8
549	8
550	8
552	8
553	8
554	8
555	8
557	8
558	8
559	8
560	8
562	8
563	8
564	8
565	13
566	3
567	4
568	8
570	8
573	8
574	5
576	4
580	4

582	4
583	4
586	5
587	4
588	4
593	4
594	4
595	4
596	4
597	4
598	4
599	4
600	4
601	4
602	4
603	5
603	5
604	5
605	4
606	4
610	4
611	4
612	4
613	4
614	4
615	4
616	4
617	4
618	4
619	4
620	4
621	8
622	4
623	4
624	5
625	8
626	4
627	4
630	8
631	4
1000	8
1001	8
1002	8
1003	8
1004	8
1005	8
1006	8
1007	8
1008	8
1009	8

1010	8
1011	8
1012	8
1014	8
1015	8
1016	8
1017	8
1018	8
1019	8
1020	8
1021	8
1022	8
1023	8
1024	8
1025	8
1026	8
1027	8
1028	8
1029	8
1030	8
1031	8
1032	8
1033	8
1034	8
1036	8
1037	8
1038	8
1039	8
1040	8
1041	8
1042	8
1043	8
1044	8
1045	8
1046	8
1047	8
1048	8
1049	8
1050	8
1051	8
1052	8
1053	8
1054	8
1055	8
1056	8
1057	8
1058	8
1059	8
1060	4
1061	4

1062	4
1063	4
1064	4
1065	4
1066	4
1067	4
1068	8
1069	4
1070	4
1071	4
1072	4
1073	4
1074	4
1075	4
1076	4
1077	4
1078	4
1079	4
1080	4
1081	4
1082	4
1083	4
1084	4
1085	4
1086	4
1087	4
1088	4
1089	4
1090	4
1091	4
1092	4
1093	4
1094	4
1095	4
1096	4
1097	4
1098	4
1099	4
1100	4
1101	4
1102	4
1103	4
1104	4
1105	4
1106	4
1107	4
1108	4
1109	4
1110	4
1111	4

1112	4
1113	4
1114	4
1115	4
1116	4
1117	4
1118	4
1119	4
1120	4
1121	4
1122	4
1123	4
1124	4
1125	4
1126	4
1127	4
1128	4
1129	4
1130	4
1131	4
1132	4
1133	4
1134	4
1135	4
1136	4
1137	4
1138	4
1139	4
1140	4
1141	4
1142	4
1143	4
1145	4
1147	4
1148	4
1149	4
1150	4
1151	4
1152	4
1153	4
1154	4
1156	4
1157	4
1158	4
1159	4
1160	4
1169	8
1170	8
1171	8
1172	8

1173	8
1174	8
1175	8
1176	8
1177	8
1178	8
1181	4
1184	4
1200	8
1201	8
1202	8
1203	8
1204	8
1205	8
1206	8
1207	8
1208	8
1210	8
1211	8
1212	8
1213	8
1214	8
1217	8
1218	8
1220	8
1221	8
1222	8
1223	8
1224	8
1225	4
1226	13
1227	4
1228	8
1229	8
1230	5
1231	5
1232	5
1233	4
1234	4
1235	4
1236	4
1237	4
1238	4
1239	4
1240	4
1241	4
1242	4
1243	4
1244	4
1245	4

1246	4
1247	4
1248	4
1249	4
1250	4
1251	4
1252	4
1253	4
1254	4
1255	4
1256	4
1257	4
1258	4
1259	4
1260	4
1261	4
1263	4
1264	4
1265	4
1266	4
1267	4
1268	4
1269	4
1270	4
1271	4
1272	4
1273	4
1274	4
1275	4
1276	4
1277	4
1278	4
1279	13
1280	4
1281	13
1282	13
1283	13
1284	13
1285	13
1287	13
1288	13
1289	13
1290	13
1291	13
1292	13
1293	13
1294	13
1295	4
1296	4
1297	4

1298	4
1299	4
1300	4
1301	4
1302	4
1303	4
1304	4
1305	4
1306	4
1307	4
1308	4
1309	4
1310	4
1311	4
1312	4
1313	4
1314	4
1315	4
1316	4
1317	4
1318	4
1319	4
1320	4
1321	4
1322	4
1323	4
1324	4
1325	4
1326	4
1327	4
1328	4
1329	2
1330	4
1331	4
1332	4
1333	4
1334	4
1335	4
1336	4
1337	4
1338	4
1339	4
1340	4
1341	4
1342	4
1343	4
1344	4
1345	4
1346	4
1347	4

1348	3
1349	4
1350	4
1351	4
1352	3
1353	3
1354	3
1355	3
1356	3
1357	3
1358	3
1359	3
1360	3
1361	3
1362	3
1363	3
1364	3
1365	3
1366	3
1367	3
1368	3
1369	3
1370	3
1371	3
1372	3
1373	3
1374	3
1375	3
1376	3
1377	3
1378	3
1379	3
1380	3
1381	3
1382	3
1383	3
1384	3
1385	3
1386	3
1387	3
1388	3
1389	3
1390	3
1391	3
1392	3
1393	3
1394	3
1395	3
1396	3
1397	3

1398	3
1399	3
1400	3
1401	3
1402	3
1403	3
1404	3
1405	3
1406	3
1407	3
1408	3
1409	3
1410	3
1411	3
1412	4
1413	4
1414	4
1415	4
1416	4
1417	4
1418	4
1419	4
1420	4
1421	4
1422	4
1423	9
1424	9
1425	9
1426	9
1427	9
1428	9
1429	9
1430	9
1431	9
1432	9
1433	9
1434	9
1435	9
1436	9
1437	9
1438	9
1439	9
1440	9
1441	9
1442	9
1443	9
1444	9
1445	9
1446	9
1447	9

1448	9
1449	9
1450	9
1451	9
1452	9
1453	9
1454	9
1455	5
1456	5
1457	5
1458	9
1459	9
1460	9
1461	15
1461	15
1462	9
1463	9
1464	9
1465	9
1466	9
1467	9
1468	9
1469	2
1470	4
1471	9
1474	5
1475	5
1476	16
1477	5
1478	5
1479	5
1480	5
1481	8
1482	8
1484	8
1485	8
1486	8
1487	8
1488	8
1489	8
1491	8
1492	8
1493	8
1494	8
1495	8
1496	8
1497	8
1498	8
1499	8
1500	8

1501	7
1502	7
1503	8
1504	8
1505	8
1506	8
1507	8
1508	8
1509	8
1510	8
1511	11
1512	11
1513	11
1514	11
1515	11
1516	11
1517	11
1518	11
1519	11
1520	11
1521	11
1523	11
1524	11
1525	11
1526	11
1527	11
1528	11
1529	11
1530	11
1531	11
1532	11
1533	11
1534	11
1535	11
1536	11
1537	8
1538	11
1539	11
1540	11
1541	6
1545	6
1546	6
1547	6
1548	6
1549	6
1550	6
1551	6
1552	6
1553	6
1554	6

1555 9
1556 9
1557 9
1558 9
1559 9
1560 9
1561 9
1562 9
1563 9
1564 9
1565 9
1566 9
1567 9
1568 9
1569 9
1570 9
1571 9
1572 9
1573 9
1574 9
1575 9
1576 9
1577 9
1578 9
1579 9
1580 9
1581 9
1582 9
1583 9
1584 9
1585 9
1586 9
1587 9
1588 9
1589 9
1590 9
1591 9
1592 9
1593 9
1594 9
1595 9
1596 9
1597 9
1598 9
1599 9
1600 9
1601 9
1602 9
1603 9
1604 9

1605	9
1606	9
1607	9
1608	9
1609	9
1610	9
1611	9
1612	9
1613	9
1614	9
1615	9
1616	9
1617	9
1618	9
1619	9
1620	9
1621	9
1622	9
1623	9
1624	9
1625	9
1626	9
1627	9
1628	9
1629	9
1630	9
1631	9
1632	9
1633	9
1634	9
1635	9
1636	9
1637	9
1638	9
1639	9
1640	9
1641	9
1642	9
1643	9
1644	9
1645	9
1646	9
1647	9
1648	9
1649	9
1650	9
1651	9
1652	9
1653	9
1654	9

1655	9
1656	9
1657	9
1658	9
1659	9
1660	9
1661	9
1662	13
1663	13
1664	13
1665	13
1666	13
1667	13
1668	13
1669	13
1670	13
1671	13
1672	13
1673	13
1674	13
1675	13
1676	13
1677	13
1678	13
1679	13
1680	13
1681	13
1682	13
1683	13
1684	13
1685	13
1686	13
1687	13
1688	13
1689	13
1690	13
1691	13
1692	13
1693	13
1694	13
1695	13
1696	13
1697	13
1698	13
1699	13
1700	13
1701	13
1702	4
1702	4
1703	13

1704	13
1705	13
1706	13
1707	13
1708	13
1709	13
1710	13
1711	13
1712	13
1713	13
1714	13
1715	13
1716	13
1717	13
1718	13
1719	13
1720	13
1721	13
1722	15
1722	15
1723	15
1723	15
1724	9
1725	4
1725	4
1726	3
1727	3
1728	3
1729	3
2000	5
2001	5
2002	5
2003	5
2004	5
2005	5
2006	5
2007	5
2008	5
2009	5
2010	5
2011	5
2012	5
2013	5
2014	5
2015	5
2016	5
2017	5
2018	5
2019	5
2020	5

2021	5
2022	5
2023	5
2024	5
2025	5
2026	5
2027	5
2028	5
2029	5
2030	5
2031	5
2032	5
2033	5
2034	5
2035	5
2036	5
2037	5
2038	5
2039	5
2040	5
2041	5
2042	5
2043	5
2044	5
2045	5
2046	5
2047	5
2048	5
2049	5
2051	5
2052	5
2053	5
2054	5
2055	5
2056	5
2057	5
2058	5
2059	5
2060	5
2061	5
2062	5
2063	5
2064	5
2065	5
2066	5
2067	5
2068	5
2069	5
2070	5
2071	5

2072	5
2073	5
2074	5
2075	5
2076	5
2077	5
2078	5
2079	5
2080	5
2081	5
2082	5
2083	5
2084	5
2085	5
2086	5
2087	5
2089	5
2090	5
2092	5
2093	5
2094	5
2095	9
2096	5
2097	5
2098	5
2100	5
2101	5
2103	5
2106	5
2107	5
2108	5
2109	5
2110	5
2111	5
2112	5
2113	5
2114	5
2115	9
2117	9
2118	9
2119	9
2120	9
2121	9
2122	9
2123	9
2125	9
2126	9
2127	9
2128	9
2129	9

2130	9
2132	9
2133	9
2134	9
2135	9
2136	9
2137	9
2138	9
2139	9
2141	9
2143	9
2144	9
2145	9
2146	9
2147	9
2148	9
2149	8
2150	8
2153	8
2154	8
2156	2
2157	2
2158	2
2159	2
2160	2
2161	2
2162	2
2163	2
2164	2
2165	2
2166	2
2167	2
2168	2
2169	2
2170	2
2171	2
2172	2
2173	2
2174	2
2175	2
2176	2
2177	2
2178	2
2179	2
2180	2
2181	2
2182	2
2183	2
2184	2
2185	2

2186	5
2187	2
2194	2
2196	2
2201	2
2204	2
2205	2
2206	2
2207	2
2208	2
2209	2
2210	2
2211	2
2212	8
2213	8
2214	8
2215	8
2216	8
2217	8
2218	8
2219	8
2220	8
2221	8
2222	8
2223	8
2224	8
2225	13
2226	13
2228	13
2229	12
2229	12
2230	12
2231	12
2232	13
2233	13
2235	13
2236	13
2237	9
2238	2
2239	8
2240	5
2242	5
2243	5
2245	5
2246	5
2247	5
2248	5
2249	5
2250	5
2251	5

2252	5
2253	5
2254	5
2255	5
2256	5
2257	5
2258	5
2259	5
2260	5
2261	5
2262	5
2263	5
2264	5
2265	5
2266	5
2267	5
2268	5
2269	5
2270	5
2271	5
2272	5
2273	5
2274	5
2275	5
2276	5
2277	5
2278	5
2279	5
2280	5
2281	5
2282	5
2283	4
2284	2
2285	2
2286	4
2287	4
2288	2
2289	2
2293	4
2294	4
2295	4
2296	4
2297	4
2298	4
2299	4
2300	4
2301	4
2302	4
2303	4
2304	4

2305	4
2306	4
2307	4
2308	2
2309	2
2310	2
2311	2
2312	2
2313	2
2314	2
2315	2
2316	2
2317	2
2318	2
2319	2
2320	2
2321	2
2322	2
2323	2
2324	2
2325	2
2326	2
2327	2
2328	2
2329	2
2330	2
2331	2
2332	2
2333	2
2334	2
2335	2
2336	2
2337	2
2338	2
2339	2
2340	2
2341	17
2342	17
2343	17
2344	17
2345	5
2345	5
2346	16
2347	16
2348	16
2349	16
2350	16
2351	16
2352	16
2353	16

2354	16
2355	16
2356	16
2357	16
2358	16
2359	16
2360	16
2361	16
2362	16
2363	16
2364	16
2365	16
2366	16
2367	16
2368	16
2369	16
2370	16
2371	16
2372	16
2373	16
2374	16
2375	16
2376	16
2377	16
2378	1
2379	1
2380	1
2381	1
2382	1
2383	1
2384	1
2385	1
2386	12
2387	12
2388	12
2389	12
2390	12
2391	12
2392	12
2393	12
2394	12
2395	12
2396	12
2397	12
2398	12
2399	12
2400	12
2401	12
2402	12
2403	12

2404	7
2405	7
2406	7
2407	7
2408	7
2409	7
2410	7
2411	7
2412	7
2413	7
2414	7
2415	7
2416	7
2417	3
2418	3
2419	7
2420	7
2421	7
2422	7
2423	7
2424	7
2425	7
2426	7
2427	7
2428	7
2429	7
2430	7
2431	7
2432	7
2433	7
2434	7
2435	7
2436	7
2437	7
2438	7
2439	7
2440	7
2441	7
2442	7
2443	7
2444	7
2445	7
2446	7
2447	7
2448	7
2449	7
2451	7
2452	7
2453	7
2454	7

2455	7
2456	7
2457	7
2458	7
2459	7
2460	7
2461	7
2462	7
2463	7
2464	7
2465	7
2467	7
2468	3
2469	7
2470	7
2471	7
2472	7
2473	7
2474	7
2475	7
2476	7
2477	7
2478	7
2479	7
2480	7
2481	7
2482	7
2483	7
2484	7
2485	7
2486	7
2487	7
2488	7
2489	7
2490	7
2491	7
2492	7
2493	7
2494	6
2495	7
2496	6
2497	6
2498	6
2499	6
2500	6
2501	6
2502	6
2503	6
2504	6
2505	6

2506	6
2507	6
2508	6
2509	6
2510	6
2511	6
2512	6
2513	6
2514	6
2515	6
2516	6
2517	6
2518	6
2519	6
2520	6
2521	6
2522	6
2523	6
2524	6
2525	6
2526	6
2527	6
2528	6
2529	6
2530	6
2531	18
2532	18
2533	3
2534	3
2535	4
2536	4
2537	4
2538	4
2539	4
2540	4
2541	4
2542	4
2543	4
2544	4
2545	4
2546	4
2547	4
2548	4
2549	4
2550	4
2551	4
2552	4
2553	4
2554	4
2555	4

2556	4
2557	4
2558	4
2559	4
2560	4
2561	4
2562	4
2563	4
2564	4
2565	4
2566	4
2567	4
2568	4
2569	4
2570	4
2571	4
2572	4
2573	4
2574	4
2575	4
2576	4
2577	4
2578	4
2579	4
2580	4
2581	4
2582	4
2583	4
2584	4
2585	4
2586	4
2587	4
2588	4
2589	3
2590	3
2591	3
2592	3
2593	3
2594	3
2595	3
2596	3
2597	3
2598	3
2599	3
2600	3
2601	3
2602	3
2604	3
2605	3
2606	3

2607	3
2608	3
2609	3
2610	3
2611	3
2612	3
2613	3
2614	3
2615	3
2616	3
2617	3
2618	3
2619	3
2620	3
2621	3
2622	3
2623	3
2624	3
2625	3
2626	3
2627	3
2628	3
2629	3
2630	3
2631	3
2632	3
2633	3
2634	3
2635	3
2636	3
2637	3
2638	3
2639	3
2640	3
2641	3
2642	3
2643	3
2644	3
2645	3
2646	3
2647	3
2648	3
2649	3
2650	3
2651	3
2652	3
2653	3
2654	3
2655	3
2656	3

2657	3
2658	3
2659	3
2660	3
2661	3
2662	3
2663	3
2664	3
2665	3
2666	3
2667	3
2668	3
2669	3
2670	3
2671	3
2672	3
2673	3
2674	3
2675	3
2676	3
2677	3
2678	3
2679	4
2680	4
2681	4
2682	7
2683	7
2684	7
2685	7
2686	3
2687	7
2688	7
2689	2
2689	4
2691	2
2692	2
2693	4
2694	4
2695	4
2696	4
2697	5
2698	5
2699	5
2700	9
2701	13
2702	4
2703	4
2704	4
2705	4
2706	9

2707	13
2710	1
2711	1
2712	1
2713	15
2713	15
2714	15
2714	15
2715	15
2715	15
2716	15
2717	5
2718	13
2719	13
2720	13
2721	13
2722	13
2723	13
2726	8
2727	8
2728	8
2729	7
2730	7
2731	3
2732	3
2733	3
2734	4
2735	3
2738	6
2739	6
2740	6
2741	6
2742	6
2743	11
2744	11
2745	11
2746	4
2747	4
2748	4
2749	4
2750	4
2751	4
2752	5
2753	5
2754	5
2755	5
2756	5
2757	5
2759	11
2760	10

2761	6
2762	3
2763	3
2764	3
2765	3
2766	8
2767	4
2768	4
2769	4
2770	4
2772	4
2773	5
2774	5
2775	8
2776	8
2777	8
2778	3
2779	3
2780	2
2781	2
2782	2
2783	4
2784	3
2785	4
2786	4
2787	4
2788	4
2789	4
2790	4
2791	4
2792	5
2793	5
2794	5
2795	16
2796	6
2797	8
2798	8
2799	12
2800	12
2801	13
2802	13
2803	4
2804	4
2805	13
2806	5

CATALOGUE

Sheet 1

2378 - Slit Trenches; Modern; 426848,374841; A close group of five slit trenches (average 2.1m x 0.6m and 0.4m in depth but enlarged at ground level by sheep-scrapes) and corresponding spoil banks. Associated with military activity c.1939-45.

2379 - Slit Trench; Modern; 426813,374958; 2.6m x 1.0m and 0.3m in depth. Associated with military activity c.1939-45.

2380 - Slit Trench; Modern; 426813,374954; 1.3m x 0.6m and 0.3m in depth. Associated with military activity c.1939-45.

2381 - Bullet Scars; Modern; 426797,374952; Single boulder with bullet scars on south face. Associated with military activity c.1939-45.

2382 - Bullet Scars; Modern; 426779,374960; Single boulder with bullet scars on south face. Associated with military activity c.1939-45.

2383 - Slit Trench; Modern; 426769,374971; 2.8m x 0.5m and 0.6m in depth, unusually long for this type of feature. Associated with military activity c.1939-45.

2384 - Slit Trench; Modern; 426760,374956; 2.6m x 0.7m with spoil bank to south, associated with military activity c.1939-45. Unusually long for this type of feature.

2385 - Pit; Modern; 426819,374992; Foxhole 0.6m square. Associated with military activity c.1939-45.

2710 - Hollow Way; Post Medieval; 426787,374905; 426776,374896; Short section of hollow way visible in slight natural gully.

2711 - Hollow Way; Post Medieval; 426854,374907; 426780,374879; Hollow way divides into two routes upslope.

2712 - Hollow Way; Post Medieval; 426967,374958; 426952,374949; Short section of hollow way cut into natural slope.

Sheet 2

1329 - Boulder Scarp; Bronze Age; 427153,374983; 427154,374999; Sinuous scarp 0.5m in height with break at centre.

1469 - Cairn; Bronze Age; 427210,374977; Low irregular cairn 3.0m x 2.0m and 0.2m in height, contains a few large stones.

2156 - Bullet Scars; Modern; 427156,374938; Large earthfast boulder with bullet scars on south-east face. Associated with military activity c.1939-45.

2157 - Possible Hollow Way; Post Medieval; 427168,374954; 427169,374948; Very slight feature 0.1m in depth, could be natural.

2158 - Pit; Modern; 427160,374941; Foxhole 0.7m x 1.0m and 0.1m in depth. Associated with military activity c.1939-45.

2159 - Pits; Modern; 427165,374968;Two foxholes 0.7m x 0.8m and 0.1m in depth. Associated with military activity c.1939-45.

2160 - Bullet Scars; Modern; 427170,374973;Single large bullet-scarred rock. Associated with military activity c.1939-45.

2161 - Probable Cairn; Bronze Age; 427175,374976;Large stone with some medium-sized stones stacked around it, maximum 1.1m in diameter and 0.3m in height. Partly turf-covered.

2162 - Linear Clearance; Bronze Age; 427179,374979;427188,374978;Low stony turf-covered bank of medium-sized stones 9.5m in length, 1.0m wide and 0.1m in height.

2163 - Linear Clearance; Bronze Age; 427172,374980;427178,374979;Low stony turf-covered bank of medium-sized stones 5.5m in length, 0.8m wide and 0.1m in height.

2164 - Linear Clearance; Bronze Age; 427163,374984;427164,374982;Low stony turf-covered bank of medium-sized stones 3.0m in length, 0.3m wide at the north end widening to 0.8m at the south end, 0.1m in height.

2165 - Linear Clearance; Bronze Age; 427161,374975;427163,374975;Area of medium-sized, turf-covered stones with a single large stone at the west end, 2.6m x 0.7m and 0.2m in height.

2166 - Probable Linear Clearance; Bronze Age; 427172,374994;427173,374991;Area of medium-sized turf covered stones 3.0m x 1.2m and 0.2m in height.

2167 - Pit; Modern; 427188,374994;Foxhole 0.3m square and <0.05m depth. Associated with military activity c.1939-45.

2168 - Spoil Mound; Post Medieval; 427195,374999;Spoil heap of large and medium-sized stones 5.5m x 2.5m and maximum height of c. 0.5m. Associated with 1960s-70s excavations by the Hunter Archaeological Society.

2169 - Stone Bank; Bronze Age; 427226,374995;427218,374998;Irregular stone bank 0.7m wide and 0.3m in height, probably a continuation of stone bank 1318. Cut by hollow way 2174, the stones which originally formed the bank here have been removed and placed by the side of the hollow (2692).

2170 - Spoil Mound; Modern; 427218,374992;Low doughnut-shaped feature 4.4m in diameter and 0.1m in height. Associated with the 1960s-70s excavations by the Hunter Archaeological Society.

2171 - Cairn; Bronze Age; 427228,374989;2.3m in diameter and 0.1m in height.

2172 - Linear Clearance; Bronze Age; 427224,374985;427229,374975;Discontinuous linear clearance 18.5m in length, maximum 2.5m wide and 0.2m in height. Defines boundary between areas of scattered stone to the north-west and stone-free ground to the south-east.

2173 - Lynchet; Bronze Age; 427215,374973;427219,374978;0.2m in height (downslope). There is an area of scattered stone above the lynchet and stone-free ground below it. The lynchet abuts linear clearance 2238 forming a small rectangular "enclosure".

2174 - Hollow Way; Post Medieval; 427207,374966;427216,374998;Depth 0.1m. Cuts stone bank 2169 and lynchet 2175.

2175 - Lynchet; Bronze Age; 427197,374982;427211,374988;Height 0.1m, cut by hollow-way

2174. There is scattered stone below the lynchet and stone-free ground above it.
- 2176 - Cairn; Bronze Age; 427192,374980; 2.0m in diameter and 0.1m in height.
- 2177 - Cairn; Bronze Age; 427132,374994; Small cairn 1.0m in diameter and 0.2m in height.
- 2178 - Possible Linear Clearance; Bronze Age; 427136,374991; 427144,374996; Turf-covered bank of large stones terminating to the west at an earthfast boulder, 9.2m in length, maximum 1.7m wide and 0.4m in height. May be fortuitous.
- 2179 - Lynchet; Bronze Age; 427147,374990; 427136,374982; Height 0.1m.
- 2180 - Pits; Modern; 427138,374982; Two foxholes 0.4m x 0.9m and 0.1m in depth. Associated with military activity c.1939-45.
- 2181 - Bullet Scars; Modern; 427140,375000; Single bullet-scarred boulder Associated with military activity c.1939-45.
- 2182 - Bullet Scars; Modern; 427133,374982; Single bullet-scarred boulder Associated with military activity c.1939-45.
- 2183 - Quarry; Modern; 427136,374980; Pit with depth 0.8m, with two crude banks of stone waste to the sides.
- 2184 - Quarries; Modern; 427121,374956; An area of quarrying with at least 9 small pits and 2 larger pits (2183, 2187). There is further quarrying to the North-West under the scarp (see 1334-6, 1338-9).
- 2185 - Bullet Scars; Modern; 427101,374920; Single bullet-scarred boulder Associated with military activity c.1939-45.
- 2187 - Quarry; Modern; 427105,374953; Sub-circular pit with stone waste around sides.
- 2194 - Bullet Scars; Modern; 427109,374950; Single large boulder with bullet-scars on south-east face. Associated with military activity c.1939-45.
- 2196 - Possible Cairn; Bronze Age; 427079,374991; Mound of medium-sized stones, maximum 3.0m in diameter, 0.2m in height (upslope) and 0.3m in height (downslope). Scoop in the top may represent robbing.
- 2201 - Bullet Scars; Modern; 427050,374998; Single large boulder with bullet scars on south-east face. Associated with military activity c.1939-45.
- 2204 - Slit Trench; Modern; 427065,374942; 0.4m x 1.6m and 0.1m in depth. Associated with military activity c.1939-45.
- 2205 - Pit; Modern; 427059,374936; Rectangular pit 1.0m x 1.7m and 0.1m in depth. Associated with military activity c.1939-45.
- 2206 - Bullet Scars; Modern; 427055,374929; Two large boulders with bullet scars on south-east face. Associated with military activity c.1939-45.
- 2207 - Bullet Scars; Modern; 427090,374951; Single large boulder with bullet scars on south-east face. Associated with military activity c.1939-45.

2208 - Pit; Modern; 427085,374943;1.2m square and 0.2m in depth. Associated with military activity c.1939-45.

2209 - Drainage Gully; Natural; 427058,374920;427056,374928;Narrow sinuous channel, 0.1m in depth, probably natural.

2210 - Bullet Scars; Modern; 427111,374908;Area of bullet scarred rocks. Associated with military activity c.1939-45.

2211 - Pit; Modern; 427059,374895;Foxhole 0.6m x 0.7m and 0.1m in depth. Associated with military activity c.1939-45.

2238 - Linear Clearance; Bronze Age; 427220,374972;427215,374972;Right angle of turf-covered stone 6.5m in length, 0.9m wide and 0.2m in height. May be clearance associated with lynchet 2173 forming a small enclosure.

2284 - Cairn/Bullet Scars; Bronze Age/Modern; 427252,374998;Of earth and large stones, 1.6m in diameter and 0.4m in height, built against the north side of a large earthfast boulder, the southern face of which is bullet scarred.

2285 - Cairn; Bronze Age; 427246,374996;Large bracken and heather-covered cairn, 0.1m in height.

2288 - Excavation Trench; Modern; 427228,374999;Crescential hollow, c.5.5m x 0.6m and 0.2-0.3m in depth, which is an excavation trench associated with the Hunter Society 1960s-70s excavations.

2289 - Lynchet; Bronze Age; 427226,374994;427228,374990;Short scarp 0.2m in height and c4.0m in length.

2308 - Cairn; Bronze Age; 427242,374974;Cairn 2.6m x 4.5m and 0.4m maximum height, heather and bracken-covered.

2309 - Paved Path; Post Medieval; 427196,374834;427241,374995;Raised paved path, 0.2m in height and 1m regular width.

2310 - Hollow Way; Post Medieval; 427238,374985;427235,374976;Short scarp 0.2m in height representing one side of a hollow way.

2311 - Hollow Way; Post Medieval; 427238,374963;427241,374974;Slight hollow way scarp 0.1-0.2m in height, cuts stony bank 2313.

2312 - Clearance Stone; Bronze Age; 427233,374963;Small area of scattered stone, possibly the disturbed remnants of linear clearance which is visible as a more comprehensive feature (2172) to the north.

2313 - Linear Clearance; Bronze Age; 427238,374962;427261,374970;Irregular stony bank of large and medium-sized stones, c.26m in length and maximum 2.3m in width, associated with cairn 2314 and cut by hollow way 2311.

2314 - Cairn; Bronze Age; 427263,374971;Small cairn 1.6m in diameter and 0.1m in height, part of stony bank 2313.

2315 - Cairn; Bronze Age; 427254,374978;Cairn of large and medium-sized stones maximum 4.2m in diameter. The south and east quadrants of the cairn are heather and bracken covered

and are relatively low in height (0.2-0.4m) compared to the north and west quadrants which are 0.5m in height.

2316 - Guidestone; Post Medieval; 427169,374777; 0.3m x 0.25m and 1.1m in height, standing upright but loose with some packing stones around the base.

2317 - Hollow Way; Post Medieval; 427164,374781,427061,374715; One principal and distinct route with a number of small braided channels either side crossing the steep slope diagonally.

2318 - Cairn or Burial Cairn; Bronze Age; 427129,374782; Irregular cairn of medium-sized stone, maximum 4.0m in diameter and 0.3m in height, possibly disturbed. If the nearby possible cairns are fortuitous, this 'isolated' cairn may be a funerary structure.

2319 - Possible Cairn; Bronze Age; 427134,374778; Turf-covered possible cairn with some medium-sized stone visible, 1.2m x 3.7m and 0.2m in height. This could easily be a natural feature.

2320 - Possible Cairn; Bronze Age; 427084,374790; Small possible cairn 0.9m in diameter and 0.1m in height comprising a few stones visible through the turf. This could easily be a natural feature.

2321 - Possible Paired Pits; Modern; 427074,374757; Two slight depressions 0.4m square, possibly associated with military activity c.1939-45.

2322 - Pit; Modern; 427121,374744; Shallow pit 1.8m x 0.8m associated with military activity c.1939-45, post-dates hollow way 2317.

2323 - Possible Hollow Way; Post Medieval; 427075,374770,427056,374752; May be natural.

2324 - Possible Cairn; Bronze Age; 427092,374797; Small grass and bracken-covered possible cairn, 1.0m in diameter and 0.1m in height. This could easily be a natural feature.

2325 - Possible Cairn; Bronze Age; 427027,374794; Low possible cairn of medium-sized stone, 1.9m x 3.9m. This could easily be a natural feature.

2326 - Possible Pit; Modern; 427058,374792; Possible infilled pit 0.9m x 1.7m and 0.1m in depth, may be associated with military activity c.1939-45.

2327 - Possible Pit; Modern; 427062,374813; Possible infilled pit, 0.7m square and 0.1m in depth, may be associated with military activity c.1939-45.

2328 - Possible Pit; Modern; 427058,374810; Possible infilled pit 0.6 x 0.8m and 0.1m in depth, may be associated with military activity c.1939-45.

2329 - Bullet Scars; Modern; 427060,374873; Large earthfast boulder with bullet scars on south face.

2330 - Bullet Scars; Modern; 427038,374965; Area of large earthfast boulders with bullet scars on south faces.

2331 - Possible Clearance Stone; Bronze Age; 427014,374998; Area of possibly chucked medium-sized stones, 1.7m x 3.6m, around three to four larger stones, possibly associated with a cleared, cultivated area to the south.

2332 - Pit; Modern; 427243,374825; 0.9m square. Associated with military activity c.1939-45.

- 2333 - Pit; Modern; 427297,374802;0.4m square. Associated with military activity c.1939-45.
- 2334 - Pit; Modern; 427315,374955;1.3m x 1.0m. Associated with military activity c.1939-45.
- 2335 - Pit; Modern; 427351,374873;0.9m x 0.7m. Associated with military activity c.1939-45.
- 2336 - Pit; Modern; 427467,374869;0.7m x 0.9m. Associated with military activity c.1939-45.
- 2337 - Pit; Modern; 427474,374871;0.7m square. Associated with military activity c.1939-45.
- 2338 - Pit; Modern; 427479,374896;0.7m square. Associated with military activity c.1939-45.
- 2339 - Pit; Modern; 427478,374879;0.6m square. Associated with military activity c.1939-45.
- 2340 - Pit; Modern; 427460,374902;0.6m square. Associated with military activity c.1939-45.
- 2689 - Linear Clearance; Bronze Age; 427231,374968;427229,374971;1.7 x 4.1m and 0.2m in height. Medium-sized stones showing through turf.
- 2691 - Stone Bank; Bronze Age; 427213,374999;427215,374998;1.0 x 3.0m and 0.2m in height. Part of bank 1318/2169 which has been lowered and probably robbed (see 2692) where hollow way 570 crosses it.
- 2692 - Pile of Stones; Post Medieval; 427217,374996;427217,374999;1.3 x 3.2m. Excavation by the Hunter Archaeological Society in the 1960s-70s demonstrated this results from the removal of stone bank material to allow passage of hollow way and stacking of stones alongside.
- 2780 - Cairn; Bronze Age; 427263,374988;4.0 x 3.8m and 0.4m high. Mostly grass covered with some medium-sized stone visible.
- 2781 - Lynchet; Bronze Age; 427226,374995;short section (less than 2m in length), 0.2m high.
- 2782 - Cairn; Bronze Age; 427075,374963;3.0 x 2.0m and 0.3m high. Medium stone, with some larger stones around edge (2 with bullet scars).

Sheet 3

- 2 - Cairn; Bronze Age; 426973,375137;Heather-covered cairn 1.2m in diameter and 0.5m in height.
- 4 - Cairn; Bronze Age; 426970,375042;Height 0.5m. Turf covered.
- 14 - Linear Clearance; Bronze Age; 426992,375068;426981,375055;Area of medium-sized clearance stone 0.8m in height. Incorporates a number of earthfast boulders including one at its west termination point.
- 566 - Cairn/Possible site of Guidestone; Bronze Age/Post Medieval; 426974,375197;3.0m in diameter and 0.4m in height 0.4m. Turf covered. Loose stones on top possibly mark the remnants of packing for a guidestone now removed.
- 1348 - Hollow Way; Post Medieval; 426964,375092;427006,375086;Shallow hollow way.
- 1352 - Linear Clearance; Bronze Age; 426980,375052;426983,375054;Area of medium and small clearance stone 1.0m x 3.0m and 0.3m in height.

1353 - Boulder Scarp/Possible Platform; Bronze Age; 426981,375069;426989,375065;Height 0.3m. Platform-like appearance upslope.

1354 - Lynchet; Bronze Age; 426994,375013;427001,375013;Sinuous lynchet 0.3m in height with some deposited stone.

1355 - Cairn; Bronze Age; 426989,375012;Sub-circular turf-covered cairn c.3.0m in diameter and 0.3m in height.

1356 - Lynchet; Bronze Age; 426957,375035;426985,375013;Height 0.3m. Some deposited stone.

1357 - Linear Clearance; Bronze Age; 426936,375062;426937,375058;4.0m x 1.4, 0.3m in height 0.3m. Medium-sized stone visible through turf.

1358 - Lynchet; Bronze Age; 426980,375077;426984,375075;Height 0.3m. Sharpening of base of natural slope.

1359 - Pit; Modern; 426994,375085;Sub-square pit 2.2m x 2.2m and 0.4m in depth. Associated with military activity c.1939-45.

1360 - Pit; Modern; 426968,375123;Rectangular pit 1.3m x 2.0m and 0.3m in depth. Associated with military activity c.1939-45.

1361 - Slit Trench; Modern; 426967,375131;0.4m x 1.2m and 0.2m in depth. Associated with military activity c.1939-45.

1362 - Slit Trench; Modern; 426977,375130;0.4m x 1.9m and 0.3m in depth. Associated with military activity c.1939-45.

1363 - Slit Trench; Modern; 426972,375121;0.2m x 1.5m and 0.3m in depth. Associated with military activity c.1939-45.

1364 - Cairn/Possible Pit; Bronze Age/Modern; 426972,375128;Turf covered cairn 6.0m in diameter and 0.6m in height, bound by earthfast boulders. Scoop in south-west side/centre may be a military pit.

1365 - Pit; Modern; 426894,375091;Small square pit 0.5m x 0.5m. Associated with military activity c.1939-45.

1366 - Slit Trench; Modern; 426880,375085;0.4m x 1.4m and 0.3m in depth.

1367 - Pit; Modern; 426880,375100;Rectangular pit 1.0m x 1.5m and 0.2m in depth. Associated with military activity c.1939-45.

1368 - Pit; Modern; 426872,375102;0.6m x 0.7m and 0.1m in depth. Associated with military activity c.1939-45.

1369 - Cairn or Pile of Stones; Bronze Age or Post Medieval; 426874,375104;Small cairn of medium-sized stone representing prehistoric or hollow way clearance, 1.0m in diameter and 0.2m in height.

1370 - Shooting Butt; Post Medieval; 426901,375152;Crescent-shaped earthen shooting butt, 7.8m in diameter and 0.5m in height.

1371 - Cairn; Bronze Age; 426910,375143;2.0m-3.0m in diameter and 0.3m in height, of

medium-sized stone with two large boulders added and several earthfast stones nearby.

1372 - Cairn; Bronze Age; 426862,375117;Small cairn of medium-sized stone 1.8m in diameter and 0.3m in height, with a robbed interior.

1373 - Pile of Stones; Post Medieval; 426845,375102;Small heap of stones 1.0m in diameter with no soil in interstices.

1374 - Slit Trench; Modern; 426840,375105;0.5m x 1.4m and 0.3m in depth. Associated with military activity c.1939-45.

1375 - Pit; Modern; 426839,375109;0.9m x 2.5m and 0.3m in depth, cut into natural slope. Associated with military activity c.1939-45.

1376 - Ditch; Post Medieval; 426808,375110;426808,375110;Sub-square trench, 0.6m wide and 0.2m in depth, with an irregular stony natural interior and slight upcast downslope. Function unknown.

1377 - Bullet Scars; Modern; 426809,375127;Area of heavily bullet scarred rocks. Associated with military activity c.1939-45.

1378 - Paved Path; Post Medieval; 426804,375090;426773,375082;Short stretch of worn slabs with robber trench to west.

1379 - Cairn/Bullet Scars; Bronze Age/Modern; 426786,375096;Small cairn of medium-sized stone 1.8m in diameter and 0.3m in height, appears to have a large earthfast stone under the centre. Some component stones are bullet scarred.

1380 - Foundation Trench; Post Medieval; 426611,375258;426755,375127;Cut into steep slope for wall.

1381 - Burial Cairn or Linear Clearance; Bronze Age; 426804,375153;Arc of stone 7.5m x 1.4m representing a complete linear clearance feature or a robbed barrow as suggested by sharp inner edge.

1382 - Possible Quarry or Robber Trench; Post Medieval; 426797,375161;Depth 0.3m maximum, may be associated with the robbing of possible cairn 1381.

1383 - Cairn; Bronze Age; 426816,375148;Medium-sized stone 1.2m-1.8m in diameter and 0.3m in height.

1384 - Possible Shooting Butt; Post Medieval; 426867,375167;5.5m in diameter, low mound which may be the ruined remains of a shooting butt or it is a rabbit warren.

1385 - Lynchet; Bronze Age; 426880,375208;426884,375151;Height 0.5m.

1386 - Probable Cairn; Bronze Age; 426907,375186;Masked cairn 2.0m-3.0m in diameter and 0.3m in height.

1387 - Cairn; Bronze Age; 426925,375189;Cairn of medium-sized stone visible through turf, c.4.0m in diameter and 0.4m in height. Built with a small area of uncultivable ground.

1388 - Boulder Scarp; Bronze Age; 426931,375190;426927,375183;Height 0.4m. Some stone deposited on upper edge.

- 1389 - Cairn; Bronze Age; 426927,375182; Cairn of medium-sized stone visible through turf, 1.0m-3.0m in diameter and 0.3m in height.
- 1390 - Boulder Scarp; Bronze Age; 426932,375182;426928,375175; Height 0.4m. Some loose stone on upper edge.
- 1391 - Hollow Way; Post Medieval; 426919,375160;426925,375148; Predates braided hollow way 565.
- 1392 - Ring Cairn; Bronze Age; 426955,375152; Comprising stone bank 18.5m in diameter with kerb stones visible in places but no obvious entrance. However the bank has been heavily disturbed by braided hollow way 565 in places.
- 1393 - Cairn; Bronze Age; 426938,375172; 3.5m-4.5m in diameter and 0.5m in height. Military pits dug into its perimeter (1394, 1396). Turf and heather covered.
- 1394 - Pit; Modern; 426939,375170; 0.8m square dug against cairn 1393. Associated with military activity c.1939-45.
- 1395 - Pit; Modern; 426935,375167; 0.5m square. Associated with military activity c.1939-45.
- 1396 - Pit; Modern; 426937,375172; 0.4m square. Associated with military activity c.1939-45. Dug against cairn 1393.
- 1397 - Pit; Modern; 426941,375172; 0.8m x 0.9m. Associated with military activity c.1939-45.
- 1398 - Boulder Scarp; Bronze Age; 426939,375170;426936,375168; Height 0.5m. Military pit dug into side (1395).
- 1399 - Pit; Modern; 426986,375153; 1.0m square. Associated with military activity c.1939-45.
- 1400 - Pit; Modern; 426988,375147; 1.0m square. Associated with military activity c.1939-45.
- 1401 - Pit; Modern; 426985,375150; 1.0m square. Associated with military activity c.1939-45.
- 1402 - Boulder Scarp; Bronze Age; 426969,375141;426979,375132; Height 0.4m.
- 1403 - Pit; Modern; 426984,375135; 0.8m square. Associated with military activity c.1939-45.
- 1404 - Pit; Modern; 426987,375130; 1.0m square. Associated with military activity c.1939-45.
- 1405 - Pit; Modern; 426982,375128; 1.0m square. Associated with military activity c.1939-45.
- 1406 - Pit; Modern; 426983,375131; 0.5m square. Associated with military activity c.1939-45.
- 1407 - Cairn; Bronze Age; 426953,375202; Heather-covered cairn, 1.0m-1.8m in diameter and 0.3m in height.
- 1408 - Lynchet; Bronze Age; 426941,375203;426953,375196; Indistinct lynchet 0.3m in height.
- 1409 - Cairn; Bronze Age; 426930,375226; Cairn of medium-sized stone visible through heather, 1.5m in diameter and 0.4m in height.
- 1410 - Cairn; Bronze Age; 426903,375223; Sub-square cairn 1.8m x 1.9m and 0.3m in height. Heather-covered.

1411 - Cairn; Bronze Age; 426881,375225;Comprising a few heather-obscured stones against an earthfast boulder, c.4.0m in diameter and 0.3m in height.

1726 - Linear Clearance; Bronze Age; 426596,375348;426594,375347;1.0m x 1.9m and 0.2m in height of medium-sized stone. Together with linear clearance 1727 this defines the margin between stony ground to the west and cleared ground to the east.

1727 - Linear Clearance; Bronze Age; 426604,375354;426600,375351;1.9m x 5.8m and 0.4m in height (downslope) of medium-sized stone. Together with linear clearance 1726 this defines the margin between stony ground to the west and cleared ground to the east.

1728 - Cairn; Bronze Age; 426674,375338;Maximum 4.6m in diameter and 0.3m in height of large and medium-sized stone, built around several earthfast boulders. A single stone slab to one side of the cairn is probably natural.

1729 - Linear Clearance; Bronze Age; 426693,375326;2.9m x 6.3m and 0.4m in height of medium-sized stone.

2417 - Hollow Way; Post Medieval; 426927,375281;426827,375556;Shallow, poorly defined hollow way.

2418 - Stone Bank; Bronze Age; 426662,375473;426702,375512;Well-formed stone bank, c.60m in length, 2.0m wide and 0.3m in height, masked.

2468 - Earthen Bank; Bronze Age; 426517,375437;426650,375535;c.170m in length, 2.8-3.0m wide and 0.1m in height, less well-formed below cairn 2467.

2533 - Quarry; Post Medieval; 426524,375416;Stone quarry of more than one phase. Date 1876 carved on one exposed face.

2534 - Linear Clearance; Bronze Age; 426995,375119;426998,375114;Area of cleared stone around an earthfast boulder, maximum 0.4m in height. Masked.

2589 - Mounds/Stone Bank; Post Medieval; 426542,375417;426530,375412;Two mounds joined by a length of stony bank, possibly post dates hollow ways and may be associated with nearby quarrying.

2590 - Cultivation Edge; Bronze Age; 426597,375448;426609,375446;At edge of stony ground.

2591 - Lynchet; Bronze Age; 426580,375446;426594,375448;0.3m in height, cut by hollow ways.

2592 - Lynchet; Bronze Age; 426609,375445;426597,375433;0.3m in height.

2593 - Cultivation Edge; Bronze Age; 426597,375432;426605,375394;Margin between stony and cleared ground, with outcropping boulders.

2594 - Hollow Way; Post Medieval; 426594,375451;426609,375447;Shallow.

2595 - Cairn; Bronze Age; 426603,375458;Maximum 3.0m in diameter and 0.3m in height, heather covered.

2596 - Lynchet; Bronze Age; 426599,375471;426603,375460;0.4m in height.

2597 - Lynchet; Bronze Age; 426600,375501;426597,375483;0.4m in height.

2598 - Earthen Bank; Bronze Age; 426612,375448;426638,375462;2.0 x 29.5m and 0.3m in height.

2599 - Linear Clearance; Bronze Age; 426638,375462;426650,375468;2.9 x 12.8m and 0.4m in height, of medium-sized stone.

2600 - Cairn; Bronze Age; 426650,375469;Maximum 1.9m in diameter, of medium-sized stone. On the edge of earthen bank (2601) and linear clearance (2599).

2601 - Earthen Bank; Bronze Age; 426662,375473;426650,375468;c.14m in length, 1.8m wide and 0.3m in height.

2602 - Cairn; Bronze Age; 426704,375474;4.4m in diameter and 0.5m in height. Large stones visible.

2604 - Slit Trench; Modern; 426661,375456;Shallow trench 2.0 x 0.4m, associated with military activity c.1939-45.

2605 - Lynchet; Bronze Age; 426619,375416;426601,375413;0.3m in height.

2606 - Stoney Lynchet; Bronze Age; 426605,375355;426609,375381;1.0m in height along edge of stone-covered ground. Lynchet changes direction at large natural boulders.

2607 - Clearance Stone; Bronze Age; 426607,375380;Area of dumped stone c.2 x 3m on top of, and behind stony lynchet.

2608 - Linear Clearance; Bronze Age; 426615,375372;426619,375375;2.0 x 6.2m and 0.5m in height. Large stones.

2609 - Cairn; Bronze Age; 426619,375378;Maximum 1.2m in diameter and 0.3m in height.

2610 - Earthen Bank; Bronze Age; 426614,375383;426609,375381;Short bank 5m in length, 2m wide and 0.3m in height.

2611 - Earthen Bank; Bronze Age; 426618,375385;426635,375381;2.0 x 18.0m and 0.3m in height.

2612 - Cairn; Bronze Age; 426637,375380;Maximum 3.5m in diameter and 0.5m in height, of large and medium-sized stones.

2613 - Linear Clearance; Bronze Age; 426640,375379;2.0 x 4.0m and 0.4m in height.

2614 - Earthen Bank; Bronze Age; 426669,375366;426643,375378;c.2 x 29m and 0.3m in height.

2615 - Stoney Lynchet; Bronze Age; 426605,375393;426612,375383;0.4m in height - at edge of stone-covered ground.

2616 - Cairn; Bronze Age; 426686,375386;1.4m in diameter and 0.3m in height, comprising a few small stones against an earthfast stone.

2617 - Slit Trench; Modern; 426695,375393;Silted-up trench 0.6 x 1.8m, associated with military activity c.1939-45.

2618 - Cairn or Burial Cairn; Bronze Age; 426691,375396;Maximum 6.5m in diameter and 0.8m in height, of mixed stones and earthfast rocks with a high earth content. Evidence of rabbit

disturbance. The cairn is noticeably larger than others in the vicinity and it may be a burial feature.

2619 - Slit Trenches; Modern; 426702,375404;Two trenches in chevron pattern, 0.5 x 1.7m and 0.5 x 2.1m respectively. Associated with military activity c.1939-45.

2620 - Cairn; Bronze Age; 426702,375408;Maximum 2.0m in diameter and 0.3m in height, of small stones.

2621 - Cairn; Bronze Age; 426710,375416;Maximum 1.8m in diameter and 0.1m in height, comprising a small group of small stones which would not be visible in deeper heather.

2622 - Pit; Modern; 426677,375428;0.5 x 0.5m, associated with military activity c.1939-45.

2623 - Slit Trench; Modern; 426687,375430;1.6 x 0.3m, associated with military activity c.1939-45.

2624 - Probable Cairn; Bronze Age; 426696,375423;2.2 x 4.7m and 0.3m in height, heather covered.

2625 - Probable Cairn; Bronze Age; 426723,375432;Maximum 2.0m in diameter and 0.2m in height, heather covered.

2626 - Linear Clearance; Bronze Age; 426725,375448;426723,375436;Medium stones, 1.9 x 12.8m and 0.3m in height.

2627 - Possible Cairn; Bronze Age; 426728,375403;2.6m in diameter and 0.3m in height, heather covered.

2628 - Pit; Modern; 426728,375401;0.5m square, associated with military activity c.1939-45.Cut into side of possible cairn 2627.

2629 - Cultivation Edge; Bronze Age; 426709,375334;426708,375342;0.5m in height - edge of natural rock outcrop.

2630 - Cairn; Bronze Age; 426715,375323;1.8 x 2.3m and 0.4m in height, heather covered.

2631 - Slit Trench; Modern; 426778,375398;Wedge-shaped trench, 1.4m x maximum 1.0m wide, associated with military activity c.1939-45.

2632 - Slit Trench; Modern; 426774,375387;Wedge-shaped trench, 1.2m x maximum 0.5m wide, associated with military activity c.1939-45.

2633 - STET; Modern; 426774,375421;Pit, 0.7 x 2.0m with pronounced lip to east, possible machine gun nest or mortar platform associated with military activity c.1939-45.

2634 - Slit Trench; Modern; 426781,375413;1.5 x 0.4m, associated with military activity c.1939-45.

2635 - Paired Pits; Modern; 426793,375431;0.5m square, associated with military activity c.1939-45.

2636 - Hollow Way; Post Medieval; 426877,375492;426904,375355;Braided, maximum 0.5m in depth.

- 2637 - Cairn; Bronze Age; 426814,375352;3.1 x 4.7m and 0.4m in height, masked.
- 2638 - Slit Trench; Modern; 426812,375348;0.6 x 2.5m and 0.3m in depth, associated with military activity c.1939-45.
- 2639 - Cairn; Bronze Age; 426790,375321;Maximum 3.1m in diameter and 0.3m in height, of medium-sized stone.
- 2640 - Probable House Site; Bronze Age; 426787,375333;Probable house platform c.6.5m in diameter, lip 0.3m high.
- 2641 - Cairn; Bronze Age; 426767,375328;Maximum 4.6m in diameter and 0.5m in height, of medium-sized stone.
- 2642 - Cairn; Bronze Age; 426754,375339;2.5m in diameter and 0.3m in height, masked.
- 2643 - Cairn; Bronze Age; 426771,375301;Sub-square cairn 4.3m square and 0.6m in height, masked.
- 2644 - Possible Kerb Cairn; Bronze Age; 426767,375304;Oval ring of small stones, 1.0 x 1.9m, in what may be a crude kerb. No interior fill. This may be a funerary feature.
- 2645 - Slit Trench; Modern; 426759,375311;0.6 x 2.0m and 0.3m in depth, associated with military activity c.1939-45.
- 2646 - Linear Clearance; Bronze Age; 426780,375281;426773,375273;2.5 x 11.0m and 0.3m in height, of medium-sized stone.
- 2647 - Platform/Linear Clearance; Bronze Age; 426746,375323;Rectangular platform c. 6 x 9m with pronounced stony lynchet, 0.6m high, flat area above. Downslope lynchet has clearance stone above in a stretch of linear clearance.
- 2648 - Probable Cairn; Bronze Age; 426730,375333;Maximum 2.3m in diameter and 0.3m in height, masked.
- 2649 - Possible Cairn; Bronze Age; 426729,375328;1.8 x 3.0m and 0.3m in height, masked.
- 2650 - Cairn; Bronze Age; 426759,375338;2.0m in diameter and 0.3m in height, masked.
- 2651 - Cairn; Bronze Age; 426815,375314;2.2m in diameter and 0.3m in height, masked.
- 2652 - Cairn; Bronze Age; 426828,375319;2.5 x 4.2m and 0.4m in height, masked.
- 2653 - Possible Cairn; Bronze Age; 426831,375337;Maximum 2.1m in diameter, built against earthfast slab to south-east, masked.
- 2654 - Slit Trench; Modern; 426829,375340;0.6 x 1.8m, associated with military activity c.1939-45.
- 2655 - Slit Trench; Modern; 426826,375364;0.7 x 1.9m, associated with military activity c.1939-45.
- 2656 - Slit Trench; Modern; 426842,375338;0.6 x 2.0m, associated with military activity c.1939-45.

2657 - Slit Trench; Modern; 426845,375343;0.6 x 1.9m, associated with military activity c.1939-45,

2658 - Cairn; Bronze Age; 426868,375302;3.1m in diameter and 0.5m in height, of medium-sized stone.

2659 - Cairn; Bronze Age; 426862,375329;2.2m in diameter and 0.3m in height, masked.

2660 - Slit Trench; Modern; 426865,375313;0.6 x 1.8m, associated with military activity c.1939-45.

2661 - Slit Trench; Modern; 426849,375309;0.6 x 2.0m, associated with military activity c.1939-45.

2662 - Cairn; Bronze Age; 426838,375303;2.3m in diameter and 0.3m in height, of medium stone.

2663 - Cairn; Bronze Age; 426833,375292;1.6m in diameter and 0.3m in height built against earthfast slab to east, masked.

2664 - Cairn; Bronze Age; 426847,375297;1.8 x 3.0m and 0.3m in height, of medium-sized stone.

2665 - Possible Cairn; Bronze Age; 426823,375302;2m in diameter and 0.3m in height, masked.

2666 - Slit Trench; Modern; 426829,375264;Shallow trench 2.0 x 0.4m, associated with military activity c.1939-45.

2667 - Cairn; Bronze Age; 426798,375254;2.7 x 4.3m and 0.5m in height, masked.

2668 - Linear Clearance; Bronze Age; 426808,375260;Linear clearance 1.9 x 8.6m and 0.4m in height, some medium-sized stones around possible earthfasts.

2669 - Possible Cairn; Bronze Age; 426802,375204;1.7 x 4.0m and 0.4m in height. Heavily masked.

2670 - Cairn; Bronze Age; 426899,375238;1.8 x 3.1m and 0.4m high. Hollow ways divert around the cairn.

2671 - Cairn; Bronze Age; 426885,375299;1.9m in diameter and 0.3m high, of medium-sized stone.

2672 - Cairn; Bronze Age; 426875,375300;Maximum 2.5m in diameter and 0.6m high, of medium-sized stone.

2673 - Cairn; Bronze Age; 426914,375262;1.9m in diameter, comprising a few stones on and against an earthfast boulder.

2674 - Slit Trench; Modern; 426963,375375;Shallow trench 1.8 x 0.4m and 0.1m in depth.

2675 - Slit Trench; Modern; 426981,375449;1.5 x 0.4m and 0.2m in depth, associated with military activity c.1939-45.

2676 - Pit; Modern; 426974,375451;0.5m square, associated with military activity c.1939-45.

2677 - Causeway; Post Medieval; 426917,375489;426919,375479Earthen, associated with hollow

way crossing wet ground.

2678 - Causeway; Post Medieval; 426912,375446;426914,375438;Earthen, 0.2m in height - links hollow way 2762.

2686 - Cairn; Bronze Age; 426737,375499;Maximum 3.2m in diameter and 0.3m in height, mostly masked.

2731 - Possible Cairn; Bronze Age; 426991,375146;Gathered stones 1.7 x 2.8m, possibly a clearance cairn.

2732 - Animal Disturbance; Natural; 426573,375488;Widespread area of disturbance caused by burrowing animals.

2733 - Hollow Way; Post Medieval; 426637,375280;426585,375288;Terraced route traversing the natural slope.

2735 - Hollow Way; Post Medieval; 426726,375207;426682,375202;Band of hollow way scarps traversing the natural slope.

2762 - Hollow Way; Post Medieval; 426901,375482;426931,375317;Part of band of roughly parallel hollow ways including 2417 and 2636.

2763 - Hollow Way; Post Medieval; 426949,375466;426947,375446;Short section of hollow way.

2764 - Hollow Way; Post Medieval; 426902,375300;426839,375231;Hollow way distinct from main swathe.

2765 - Hollow Way; Post Medieval; 426814,375213;426838,375198;Two adjacent routes crossing hollow way 565 at an angle.

2778 - Hollow Way; Post Medieval; 426920,375451;426918,375474;Leads to causeway 2677.

2779 - Hollow Way; Post Medieval; 426946,375106;426954,375124;Short c17m section leading to main hollow way route 565.

2784 - Stony Lynchet; Bronze Age; 426726,375447;426726,375451;Heather covered, 0.3m high.

Sheet 4

15 - Cairn; Bronze Age; 427001,375078;Circular cairn 3.2m in diameter and 0.3m in height. Bilberry and bracken covered, no stone visible on surface.

16 - Linear Clearance; Bronze Age; 427012,375098;427011,375092;Bank of medium-sized stone (where visible), 6.2m x 1.2m and 0.4m in height with a large earthfast boulder at the south end.

17 - Cairn; Bronze Age; 427011,375126;Substantial irregular cairn of medium and large sized stones visible through turf, c.8m in diameter and 0.7m in height. Cairn is disturbed at the north.

25 - Cairn; Bronze Age; 427073,375086;Sub-circular turf-covered cairn 3.4m in diameter and 0.4m in height. Some large stones are visible.

26 - Linear Clearance; Bronze Age; 427087,375036;427079,375035;Area of medium-sized to large clearance stone, 7.0m x 1.8m and 0.2m in height.

- 29 - Cairn; Bronze Age; 427109,375043;Cairn of medium-sized stone 2.9m in diameter and 0.4m in height.
- 31 - Tree Ring, Shieling or Cairn; Bronze Age; 427119,375048;Regular stony ring c.4.0m in diameter at a width of 1.1m.Possible shieling or tree ring or robbed cairn. Doubtful house site.
- 32 - Linear Clearance; Bronze Age; 427176,375073;427099,375039;Constructed along the crest of a natural scarp, 0.5m in height (downslope).
- 33 - Stony Lynchet; Bronze Age; 427099,375038;427177,375075;Constructed along the crest of a natural scarp, 0.5m in height (downslope), intermittent banking upslope.
- 34 - Possible Boulder Scarp; Bronze Age; 427154,375061;427129,375049;May be natural.
- 35 - Cairn; Bronze Age; 427162,375073;3.2m in diameter and 0.3m in height, turf covered.
- 36 - Stone Bank; Bronze Age; 427189,375121;427161,375067;Long sinuous bank c.75m in length 1.0-3.0m wide and 0.5m in height, of large and medium-sized stone with later modification (2564) at north-west end. Appears to post-date cairn 142 and overlie stone bank 143.
- 37 - Cairn; Bronze Age; 427182,375069;Circular cairn 3.2m in diameter and 0.3m in height.
- 38 - Linear Clearance; Bronze Age; 427182,375086;427173,375089;c.10.5m x maximum 2.7m and 0.3m in height, turf covered.
- 40 - Possible Cairn; Bronze Age; 427172,375093;1.8m in diameter and 0.2m in height.
- 41 - Lynchet; Bronze Age; 427170,375098;427175,375091;0.2m in height.
- 42 - Cairn; Bronze Age; 427112,375104;Small circular cairn 2.0m in diameter and 0.2m in height. Turf-covered.
- 46 - Cairn; Bronze Age; 427204,375119;Cairn situated on the edge of an area of stony ground, 2.6 x 5.0m and 0.4m in height, of medium-sized and large stones but disturbed at centre.
- 93 - Cairn; Bronze Age; 427205,375065;Stony sub-circular cairn situated on the crest of a natural scarp, c.2.7m in diameter and 0.3m in height (downslope).
- 94 - Lynchet; Bronze Age; 427210,375072;427215,375086;0.3m in height.
- 104 - Cairn; Bronze Age; 427025,375139;Sub-circular heather-covered cairn maximum 4.0m in diameter.
- 105 - Cairn; Bronze Age; 427032,375134;Turf-covered cairn 4.0m-5.0m in diameter and 0.4m in height. Some medium-sized stone visible, robbed in centre.
- 106 - Cairn; Bronze Age; 427065,375119;Substantial stony cairn, oval in plan with minimum and maximum diameters of 4.8m and 11.0m and standing 0.5m in height. The centre of the cairn has been disturbed.
- 107 - Cairn; Bronze Age; 427059,375138;Heather-covered cairn 1.8-3.2m in diameter and 0.4m in height. Two medium-sized stones are visible.
- 108 - Cairn; Bronze Age; 427060,375151;Well-formed cairn 3.1 x 6.2m and 0.5m in height, some medium-sized and 3-4 large stones visible.

109 - Linear Clearance; Bronze Age; 427061,375163;Low linear cairn 1.7 x 6.0m and 0.3m in height, some medium-sized stone visible.

110 - Cairn; Bronze Age; 427079,375155;2.9m in diameter and 0.6m in height.

111 - Cairn; Bronze Age; 427092,375162;Small cairn maximum 2.7m in diameter and 0.2m in height.

112 - Cairn; Bronze Age; 427087,375132;Turf-covered cairn 1.0-2.5m in diameter, 0.3m in height.

113 - Cairn; Bronze Age; 427099,375129;Sub-oval in plan with minimum and maximum diameters of 5.0m and 8.0m, and 0.5m in height. Large stones are visible around edge of the cairn, and it appears to have been robbed from north. There is a large earthfast boulder at west.

114 - Cairn; Bronze Age; 427106,375131;2.2 x 4.0m and 0.3m in height, mostly turf covered.

115 - Lynchet; Bronze Age; 427108,375139;427107,375133;0.3m in height.

116 - Cairn; Bronze Age; 427108,375141;Maximum 4.0m in diameter and 0.4m in height - mostly turf covered and built against an earthfast slab.

117 - Linear Clearance; Bronze Age; 427120,375164;2.0 x 6.0m and 0.5m in height. Some medium-sized stone visible.

118 - Cairn; Bronze Age; 427125,375163;3.9m in diameter and maximum 0.4m in height. Some medium-sized stone visible.

119 - Linear Clearance; Bronze Age; 427132,375163;Small, low cairn, 1.7 x 3.6m and 0.2m in height.

120 - Cairn; Bronze Age; 427134,375158;Maximum 3.8m in diameter and 0.4m in height.

121 - Cairn; Bronze Age; 427118,375175;1.9 x 3.5m and 0.3m in height.

122 - Earthen Bank; Bronze Age; 427166,375118;427145,375146;33m long, 2m wide and max 0.3m high. Overlain by shooting butt 588.

123 - Possible Cairn; Bronze Age; 427115,375218;2.0m in diameter and 0.1m in height, masked by turf and soil. May be a fortuitous natural feature.

125 - Cairn; Bronze Age; 427136,375196;Small heather-covered cairn 3.0m in diameter and maximum 0.4m in height.

126 - Earthen Mound; Bronze Age or Modern; 427132,375230;Low mound 1.5 x 2.5m. Probably a prehistoric feature but could be associated with military activity c.1939-45.

127 - Cairn; Bronze Age; 427143,375224;1.0 x 1.0m and 0.2m in height, masked by turf and soil.

128 - Linear Clearance; Bronze Age; 427154,375231;427152,375225;6.0 x 2.0m and 0.2m in height, masked by turf and soil.

129 - Earthen Mound; Bronze Age or Modern; 427163,375218;2.0m in diameter and 0.3m in height. Probably a prehistoric feature but could be associated with military activity c.1939-45.

- 130 - Cairn; Bronze Age; 427164,375208;2.0 x 3.4m and 0.2m in height.
- 132 - Linear Clearance; Bronze Age; 427145,375161;427144,375157;Low L-shaped bank c.4m in length, 2m wide and maximum 0.2m in height, masked, extends from north-east side of cairn 133.
- 133 - Cairn; Bronze Age; 427142,375156;4.0m in diameter and 0.7m in height, of large and medium-sized stone. Low bank (132) extends from north-east side of cairn.
- 134 - Cairn; Bronze Age; 427137,375153;Grass-covered cairn of large and medium-sized stone, c.4.8 x 2.0m, with a pit (610) dug into the south side.
- 135 - Cairn; Bronze Age; 427133,375137;2.8 x 4.3m and 0.4m in height. Large stones visible through turf.
- 136 - Cairn; Bronze Age; 427150,375125;3.7 x 5.2m and 0.4m in height, of large stones.
- 137 - Linear Clearance; Bronze Age; 427155,375118;427154,375121;1.6 x 3.5m and 0.3m in height, mostly turf covered but with some large stones visible.
- 138 - Cairn; Bronze Age; 427167,375150;Maximum 3.4m wide and 0.3m in height.
- 139 - Cairn; Bronze Age; 427160,375169;3.8m in diameter and 0.8m in height.
- 142 - Cairn; Bronze Age; 427200,375087;Disturbed cairn 5.0m in diameter and 0.3m in height upslope, 1.0m downslope. Appears to pre-date bank to either side.
- 143 - Stone Bank; Bronze Age; 427224,375090;427210,375104;2.20m in length, 1.7m wide and 0.3m in height. Feature is not well-formed and appears to be overlain by stone bank 36.
- 144 - Cairn; Bronze Age; 427218,375112;2.7 x 5.8m and 0.6m in height. Some large stones visible through the turf.
- 145 - Lynchet; Bronze Age; 427224,375120;427218,375115;0.3m in height.
- 147 - Linear Clearance; Bronze Age; 427186,375125;427189,375121;2.5 x 5.0m and 0.3m in height, turf covered.
- 148 - Lynchet; Bronze Age; 427185,375128;427186,375125;0.2m in height.
- 149 - Linear Clearance; Bronze Age; 427184,375130;2.0 x 4.0m and 0.3m in height, turf covered.
- 150 - Cairn; Bronze Age; 427196,375125;3.8 x 7.7m and 1.0m in height, of large and medium-sized stone Small shelter or military feature cut into south side (2788).
- 151 - Stone Bank; Bronze Age; 427204,375138;427199,375128;S-shaped bank c.12m in length and 1.5m wide may indicate possible house site (2569) to north west.
- 153 - Possible Stone Bank; Bronze Age; 427205,375141;427204,375138;1.2 x 3.8m, this feature is not well-formed but may a continuation of stone banks 151 and 154.
- 154 - Stone Bank; Bronze Age; 427220,375146;427205,375142;Irregular stone bank c.17m in length, maximum 3m wide and 0.8m in height, of medium-sized stones.
- 155 - Possible Cairn; Bronze Age; 427214,375141;Irregular group of earthfast stones 3.5 x 6.0m

with dumped stones around. Disturbance at south reveals a sub-surface void but there is insufficient evidence to indicate that this is a cist.

160 - Cairn; Bronze Age; 427225,375127;Maximum 3.5m in diameter and 0.8m in height, mostly heather covered. Defines western limit of possible house site 161.

161 - Possible House Site; Bronze Age; 427228,375128;Level area c.3m in diameter, defined by stone bank (178) lynchet (2681) and cairn (160) may be a house site.

164 - Linear Clearance; Bronze Age; 427227,375144;427235,375147;c.12m in length, 2m wide and 0.3m in height, of medium-sized stone.

165 - Lynchet; Bronze Age; 427232,375150;427250,375132;0.3m in height. Defines possible trackway 2573.

166 - Linear Clearance; Bronze Age; 427240,375161;427247,375150;c.13m in length, 3.5m wide and 0.8m in height, of large and medium-sized stone.

168 - Lynchet; Bronze Age; 427244,375173;427253,375180;0.3m in height.

169 - Earthen Bank; Bronze Age; 427160,375202;427189,375151;c.59m in length, 2m wide and 0.1-0.2m in height.

172 - Cairn; Bronze Age; 427220,375192;3.5m in diameter and 0.5m in height.

173 - Linear Clearance; Bronze Age; 427217,375093;427212,375082;c.13m in length, 2.0m wide and 0.3m in height, mostly heather covered.

174 - Lynchet; Bronze Age; 427227,375098;427223,375095;0.4m in height.

175 - Cairn; Bronze Age; 427228,375102;3.8 x 7.5m and 1.0m in height. Mostly large stones visible through turf.

176 - Cairn; Bronze Age; 427233,375110;3.9m in diameter and 0.4m in height upslope, 0.6m downslope, heather covered.

177 - Cairn; Bronze Age; 427239,375106;Maximum 6.5m in diameter and 1.0m in height upslope, 1.3m downslope, medium-sized and large stones visible through turf.

178 - Stone Bank; Bronze Age; 427225,375133;427264,375116;Irregular stone bank c.44m in length, 2m wide and 0.5m in height, mostly of medium-sized stone.

179 - Stone Bank; Bronze Age; 427301,375104;427263,375118;Disturbed area of linear stone clearance c.2.5m in width and 0.3m in height. This feature is cut by a hollow-way 570 which causes the discontinuity.

180 - Lynchet; Bronze Age; 427253,375100;427260,375118;Earthen lynchet 0.4m in height.

181 - Linear Clearance; Bronze Age; 427256,375107;427259,375112;Area of medium-sized clearance stone 5.4m x 1.6m, 0.2m in height (upslope) and 0.6m in height (downslope).

182 - Linear Clearance; Bronze Age; 427254,375099;427251,375089;Curvilinear area of medium-sized to large clearance stones, 11.0m in length, 2.8m wide and 1.0m in height (downslope). Cut by a military foxhole (part of feature number 1270).

198 - Lynchet; Bronze Age; 427257,375133;427246,375150;0.3m in height. Defines possible trackway 2573.

199 - Boulder Scarp; Bronze Age; 427274,375140;427282,375152;Stony scarp 0.5m in height. Three boulders have been added to the eastern end and some may have been added to west.

200 - Boulder Scarp; Bronze Age; 427278,375165;427274,375160;0.4m in height.

201 - Cairn or Burial Cairn; Bronze Age; 427108,375286;Well-formed symmetrical cairn 6.0 x 7.0m and 0.5m in height. Partly turf-covered but some medium-sized stone visible. Possibly an overtly funerary structure.

202 - Earthen Mound; Bronze Age or Modern; 427123,375275;2.5 x 3.0m and 0.3m in height. Probably a prehistoric feature but could be associated with military activity c.1939-45.

203 - Earthen Bank; Bronze Age; 427174,375278;427172,375258;Lynchet-like feature 20.0m in length, 2.0m wide, and 0.3m in height (downslope) and 0.1m (upslope). Partly masked by peat.

204 - Cairn; Bronze Age; 427173,375285;2.0m in diameter and 0.2m in height, masked by turf and soil.

205 - Possible Cairn; Bronze Age; 427187,375263;2.0 x 2.5m and 0.2m in height, masked by turf and soil. May be a fortuitous natural feature.

206 - Cairn; Bronze Age; 427196,375267;3.5 x 4.0m and 0.4m in height, of medium-sized stone.

207 - Earthen Bank; Bronze Age; 427190,375273;427217,375280;Low feature 29.0m in length and 2.0m wide. Conjoins with linear clearance 231 to the east, and to the west is obscured by peat.

208 - Linear Clearance; Bronze Age; 427215,375297;427215,375302;5.5 x 2.0m and 0.4m in height. Conjoins cairn 209.

209 - Cairn; Bronze Age; 427214,375304;4.5 x 5.0m and 0.4m in height, masked by turf and soil. Conjoins linear clearance 208.

210 - Cairn; Bronze Age; 427196,375303;2.5 x 3.0m and 0.2m in height, masked by turf and soil.

211 - Earthen Bank; Bronze Age; 427156,375299;427210,375314;6.0m in length, 2.0m wide and up to 0.2m in height. To the west this feature is obscured by peat.

212 - Possible Cairn; Bronze Age; 427211,375315;2.0 x 3.0m. Could be a low cairn or some clearance stones on the crest of a bank.

213 - Lynchet; Bronze Age; 427206,375330;427212,375316;0.3m in height.

214 - Cairn; Bronze Age; 427217,375329;3.0 x 3.5m and 0.3m in height, masked by turf and soil.

215 - Cairn; Bronze Age; 427213,375338;1.5 x 2.0m and 0.2m in height, masked by turf and soil.

216 - Cairn; Bronze Age; 427203,375343;2.0 x 2.5m and 0.3m in height, masked by turf and soil.

217 - Cairn; Bronze Age; 427223,375344;2.0 x 3.0m and 0.2m in height, masked by turf and soil.

218 - Probable Lynchet; Bronze Age; 427223,375344;427241,375356;32.0m in total length but

the south-western part may well be entirely natural. The eastern c.10.0m is sharper and is probably an enhanced lynchet.

219 - Cairn; Bronze Age; 427240,375352;2.0 x 2.5m and 0.2m in height, masked by turf and soil. Placed above feature 218.

220 - Earthen Bank; Bronze Age; 427249,375366;427169,375352;82.0m in length, 1.5m wide and is up to 0.2m in height. It conjoins cairn 1113 and is breached by gap 1114.

221 - Cairn; Bronze Age; 427177,375385;2.0m in diameter and 0.2m in height, masked by turf and soil.

222 - Cairn; Bronze Age; 427186,375244;2.5m x 3.0m and 0.2m in height, masked by turf and soil.

223 - Cairn; Bronze Age; 427191,375232;2.0 x 2.5m and 0.3m in height, masked by turf and soil.

224 - Shooting Butt; Post Medieval; 427193,375239;0.4m in height, largely earthen.

225 - Lynchet; Bronze Age; 427197,375241;427204,375242;11.0m in length and 0.3m in height.

226 - Linear Clearance; Bronze Age; 427204,375242;427209,375248;8.5 x 3.5m and 0.5m in height, masked by turf and soil.

227 - Cairn; Bronze Age; 427217,375253;4.0 x 4.5m and 0.4m in height, masked by turf and soil.

229 - Linear Clearance; Bronze Age; 427215,375295;427216,375287;8.0 x 2.0m and 0.4m in height. Conjoins earthen bank 1156.

230 - Possible Gate; Bronze Age; 427217,375282;This gap between earthen bank 1156 and linear clearance 231 is 1.5m wide and may be an original gateway.

231 - Linear Clearance; Bronze Age; 427218,375281;427226,375267;17.5 x 2.0m and 0.4m in height, masked by turf and soil. This feature is regular and bank-like, and is conjoined by earthen bank 207 and lynchet 1157.

232 - Possible Gate; Bronze Age; 427227,375266;This gap between linear clearance 231 and 234 is 1.5m wide and may be an original gateway.

234 - Linear Clearance; Bronze Age; 427244,375275;427226,375263;Sinuous feature c.23m in length, 2.0m-4.5m wide, and 0.2m in height (upslope) and 0.5m (downslope).

235 - Linear Clearance; Bronze Age; 427243,375277;427245,375283;6.5 x 2.5m.

236 - Probable House Site; Bronze Age; 427249,375287;Well-defined rubble ring 4.0 x 4.5m (internally) and 8.0m in diameter (externally), and 0.3m in height. There is a gap to the south-east 4.5m wide where the feature is continued by low earth scarps.

237 - Linear Clearance; Bronze Age; 427250,375295;427248,375291;7.0 x 2.5m and 0.1m in height, masked by turf and soil.

239 - Lynchet; Bronze Age; 427236,375262;427230,375263;6.0m in length and 0.3m in height. Western end conjoins linear clearance 234.

240 - Possible Linear Clearance; Bronze Age; 427235,375275;427239,375273;5.0 x 1.5m,

comprising three stone slabs. It is not clear whether they have been placed here or are fortuitous.

241 - Cairn; Bronze Age; 427230,375279; 2.5 x 3.5m and 0.2m in height. Masked by turf and soil and conjoined by cairn 242.

242 - Cairn; Bronze Age; 427229,375276; 2.0 x 3.5m and 0.2m in height, masked by turf and soil.

243 - Cairn; Bronze Age; 427232,375308; 2.5 x 3.0m and 0.3m in height, masked by turf and soil.

244 - Linear Clearance; Bronze Age; 427214,375249; 4.5 x 2.0m and 0.3m in height, masked by turf and soil. Conjoins lynchet 1197.

245 - Linear Clearance; Bronze Age; 427219,375237; 1.9 x 11.0m and 0.5m in height.

246 - Cairn; Bronze Age; 427214,375229; Maximum 4.6m in diameter and 0.6m in height.

247 - Cairn; Bronze Age; 427211,375220; 2.6 x 4.4m and 0.5m in height.

248 - Cairn; Bronze Age; 427211,375208; Maximum 4.0m in diameter and 0.7m in height. Some medium-sized stone is visible but cairn is mostly masked.

249 - Linear Clearance; Bronze Age; 427213,375208; 18.5m in length, 1.8-3.7m wide and 0.6m in height, grass-covered. Bank is significantly lower where it is worn by animal traffic.

251 - Earthen Bank; Bronze Age; 427231,375205; 0.3m in height.

252 - Cairn; Bronze Age; 427227,375220; Sub-square cairn 5.0 x 6.2m and 1.4m in height. A slight scoop on the north side may be disturbance.

253 - Cairn; Bronze Age; 427242,375255; 3.0 x 4.5m and 0.5m in height, masked by turf and soil.

255 - Cairn; Bronze Age; 427260,375257; 4.5 x 5.0m and 0.6m in height, masked by turf and soil.

256 - Cairn; Bronze Age; 427270,375258; 3.0 x 3.5m and 0.4m in height, masked by turf and soil.

257 - Cairn; Bronze Age; 427271,375242; 6.5 x 8.0m and 0.6m in height, masked by turf and soil. There is a small disturbance at the western edge.

259 - Cairn; Bronze Age; 427258,375232; Maximum 4.4m in diameter and 0.8m in height.

260 - Lynchet; Bronze Age; 427249,375217; 0.3m in height.

261 - Cairn; Bronze Age; 427253,375223; 3.6 x 7.0m and 1.2m in height.

265 - Stone Bank; Bronze Age; 427240,375205; Curvilinear stone bank c.20m in length, 2m wide and 0.3m in height, defines house site 266. Stones visible on the straight section have a structured rather than dumped appearance.

266 - Probable House Site; Bronze Age; 427246,375205; Level area c.7.5m in diameter defined by stone bank 265.

267 - Lynchet; Bronze Age; 427253,375199; 3m in length and 0.2m in height,

where later routeway breaches stonebank 265/268.

268 - Stone Bank; Bronze Age; 427254,375196;427242,375173;Irregular L-shaped stone bank c.34m in length, 1.5-3.0m wide and 0.4-0.7m in height, of medium-sized stone.

270 - Linear Clearance; Bronze Age; 427265,375177;2.3 x 6.0m and 0.5m in height.

274 - Possible Cairn; Bronze Age; 427259,375210;1.9 x 4.6m and 0.3m in height.

275 - Linear Clearance; Bronze Age; 427294,375259;427303,375262;10.0 x 3.0m and 0.5m in height.

276 - Possible House Site; Bronze Age; 427292,375255;The strongly curving layout of linear clearance 1142 and 275 define a level area c.9.0m in diameter, and is suggestive of a former house site.

277 - Lynchet; Bronze Age; 427303,375261;427310,375262;8.0m in length and 0.3m in height.

278 - Linear Clearance; Bronze Age; 427310,375262;427317,375264;7.5 x 3.5m.

280 - Linear Clearance; Bronze Age; 427263,375292;427279,375271;Regular bank-like feature 26.0 x 2.5m and 0.3m in height, masked by turf and soil.

281 - Cairn; Bronze Age; 427259,375298;3.0m in diameter and 0.3m in height.

282 - Earthen Bank; Bronze Age; 427266,375291;427267,375298;9.0m in length, 2.0m wide and 0.3m in height.

283 - Cairn; Bronze Age; 427269,375298;2.5 x 4.0m and 0.3m in height. There is a small amount of robbing to the west.

284 - Cairn; Bronze Age; 427276,375286;2.0 x 3.0m and 0.3m in height, masked by turf and soil.

285 - Cairn; Bronze Age; 427271,375307;3.0 x 5.0m and 0.3m in height, masked by turf and soil.

286 - Possible Linear Clearance; Bronze Age; 427283,375272;427279,375271;4.5m in length and 0.2m in height. This lies within hollow way 570 and may well be a vestige of linear clearance 287, linking this with feature 280.

287 - Linear Clearance; Bronze Age; 427285,375274;427286,375275;Low feature 1.5 x 1.5m conjoins linear clearance 288 at one end.

288 - Linear Clearance; Bronze Age; 427290,375279;427287,375275;6.0 x 2.5m and 0.6m in height.

289 - Cairn; Bronze Age; 427295,375283;3.5 x 4.0m and 0.5m in height. May have conjoined linear clearance 287 but the junction has been disturbed by a narrow hollow way.

290 - Linear Clearance; Bronze Age; 427289,375268;427289,375275;8.0 x 2.5m and 0.5m in height. Conjoins linear clearance 288.

292 - Linear Clearance; Bronze Age; 427299,375289;427280,375310;c.29.0m in length, 2.0m wide and 0.3m in height, masked by turf and soil. The south-east part of this feature has a high stone content whilst to the north-west it is more earthen.

- 293 - Cairn; Bronze Age; 427279,375312;2.0 x 2.5m and 0.2m in height, masked by turf and soil.
- 294 - Linear Clearance; Bronze Age; 427282,375312;427288,375313;2.5 x 5.5m and 0.3m in height, masked by turf and soil. Conjoins possible lynchet 1126, and may be truncated by hollow way.
- 295 - Cairn; Bronze Age; 427272,375327;3.5 x 5.0m and 0.5m in height, masked by turf and soil. Conjoined by earthen bank 296.
- 296 - Earthen Bank; Bronze Age; 427270,375328;427241,375356;39.0m in length, 2.0m wide and 0.3m in height.
- 297 - Cairn; Bronze Age; 427302,375316;4.5 x 5.0m and 0.6m in height, of medium-sized stone. Disturbed at centre by a small pit.
- 298 - Cairn; Bronze Age; 427314,375286;2.0 x 3.0m. A discrete stone heap placed on top of feature 1184, with a maximum combined height of 0.4m.
- 299 - Cairn; Bronze Age; 427309,375284;Amorphous heap of stones 5.5 x 8.0m and maximum 0.4m in height, masked by turf and soil, measuring c. 5.5x8.0m, with a maximum height 0.4m. The south-west part of this feature is overlain by cairn 300.
- 300 - Cairn; Bronze Age; 427308,375281;A discrete heap of stones at the south-west end of cairn 299, 4.0 x 5.0m and 0.5m in height. Masked by turf and soil.
- 301 - Linear Clearance; Bronze Age; 427311,375279;427313,375271;8.0 x 3.5m and 0.4m in height. Conjoins lynchet 302.
- 302 - Lynchet; Bronze Age; 427317,375268;427310,375280;14.0m in length and 0.2m in height. Conjoins linear clearance 301.
- 303 - Cairn; Bronze Age; 427324,375299;5.0 x 7.0m and 0.4m in height (upslope) and 1.2m (downslope) 1.2m, masked by turf and soil.
- 304 - Lynchet; Bronze Age; 427325,375296;427329,375281;15.0m in length and 0.2m in height.
- 305 - Linear Clearance; Bronze Age; 427325,375291;427325,375287;4.0 x 1.5m and 0.3m in height, area of stones piled on lynchet.
- 306 - Cairn; Bronze Age; 427301,375169;Stone and earth cairn with maximum diameters of 4.5m and 1.2m, 0.3m in height.
- 308 - Clearance Stone; Bronze Age; 427321,375209;9.4m in length and 4.0m wide.
- 309 - Hollow Way; Post Medieval; 427338,375223;427329,375214;0.4m in depth, probably a continuation of hollow way 321.
- 310 - Possible House Site; Bronze Age; 427328,375203;Level area downslope of a cairn 308 through which a hollow-way 321 passes.
- 312 - Cairn; Bronze Age; 427321,375252;2.5 x 4.0m and 0.6m in height, masked by turf and soil.
- 314 - Linear Clearance; Bronze Age; 427317,375266;427324,375269;10.0 x 3.5m and 1.2m in height downslope.

315 - Cairn; Bronze Age; 427326,375268;c.5.0 x 7.0m and 1.3m in height downslope. This feature is cut into by shooting butt 597 at the north-east side.

316 - Cairns; Bronze Age; 427329,375278;East: c.5.5x 6.0m and 1.0m in height downslope, west: 3.0 x 3.5m, superimposed on the side of the eastern cairn. Cut into by shooting butt 597 at the south end.

317 - Cairn/Bullet Scars; Bronze Age/Modern; 427337,375257;4.0 x 5.0m and 0.3m in height (upslope), and 0.5m (downslope). Two boulders within the cairn are bullet scarred. Conjoined with lynchet 318.

318 - Lynchet; Bronze Age; 427333,375255;427335,375255;2.0m in length and 0.2m high.

321 - Hollow Way; Post Medieval; 427366,375245;427341,375224;Discontinuous feature 0.2m in depth, roughly parallel to but set back from the top of the natural slope.

322 - Cairn; Bronze Age; 427388,375240;Oval cairn of medium-sized stones, with maximum diameters of 4.1m and 5.6m and 0.3m in height.

323 - Linear Clearance; Bronze Age; 427396,375245;427406,375230;c.20m in length and 2.5m wide with a maximum height of 0.3m. Traces of a possible dry-walled face (one course of five or six stones) are visible on the east side.

324 - Possible Lynchet; Bronze Age; 427403,375229;427393,375230;0.5m in height with significant stony content. May be natural.

325 - Linear Clearance/Lynchets; Bronze Age; 427409,375250;427419,375256;c.6.0m x 1.5m and 0.5m high. There are short stretches of lynchet to either side of the linear clearance, giving a total length of c.13m.

326 - Burial Cairn; Bronze Age; 427134,375436;12.0 x 13.5m and 0.6m in height. Overlain by feature 567 and disturbed by three small robber pits dug into its top.

327 - Cairn; Bronze Age; 427186,375397;1.5 x 3.5m and 0.2m in height, masked by turf and soil.

330 - Cairn; Bronze Age; 427183,375411;3.0 x 3.5m and 0.4m in height, masked by turf and soil.

331 - Earthen Bank; Bronze Age; 427185,375412;427238,375430;57.0m in length, 2.0m wide and up to 0.3m high.

332 - Earthen Bank; Bronze Age; 427225,375446;427163,375429;69.0m in length, maximum 2.5m wide and 0.3m high.

333 - Cairn; Bronze Age; 427202,375478;3.0m in diameter and 0.3m in height, masked by turf and soil.

334 - Cairn; Bronze Age; 427202,375484;1.5m in diameter and 0.2m in height, of medium-sized stone. Conjoins bank 335.

335 - Earthen Bank; Bronze Age; 427190,375478;427221,375491;34.0m in length, 1.5m wide and up to 0.3m high. Conjoins cairn 334.

336 - Earthen Bank; Bronze Age; 427242,375414;427244,375454;42.0m in length, 2.0m-3.5m wide and 0.3m high on the downslope side.

337 - Earthen Bank; Bronze Age; 427246,375455;427286,375469;45.0m in length, 1.5-2.0m wide and 0.3m high.

338 - Earthen Bank; Bronze Age; 427244,375455;427264,375537;4.90m in length, 1.5-2.5m wide and 0.2m high. At the south end it curves strongly to define a probable house site (627).

342 - Possible Cairn; Bronze Age; 427242,375404;2.0 x 3.0m. This turf and soil covered feature is either a prehistoric cairn or comprises natural stone.

343 - Earthen Bank; Bronze Age; 427243,375414;427244,375403;Lynchet-like feature 9.0m in length, 2.5m wide and 0.3m high.

344 - Earthen Bank; Bronze Age; 427251,375367;427243,375402;Lynchet-like feature 37.0m in length, 2.0m wide and 0.3m high on the downslope side.

345 - Possible Gate; Bronze Age; 427250,375367;This gap is 2.5m wide and may well be an original gateway.

347 - Earthen Bank; Bronze Age; 427244,375403;427272,375405;0.2m in height.

349 - Cairn; Bronze Age; 427273,375409;1.5 x 2.0m and 0.2m in height, masked by turf and soil.

350 - Cairn; Bronze Age; 427276,375405;2.5 x 3.0m and 0.2m in height, masked by turf and soil.

351 - Linear Clearance; Bronze Age; 427281,375395;427279,375401;Low feature 7.0 x 1.0-2.0m, masked by turf and soil.

352 - Possible Animal Pen; Bronze Age; 427280,375398;Roughly rectangular area, 2.0 x 4.0m internally, defined by linear clearance 351 and 354. The south-eastern end is open and the interior is slightly dishd.

354 - Linear Clearance; Bronze Age; 427280,375401;427301,375374;4.34.0 x 2.0-3.0m and 0.3m high, masked by turf and soil.

355 - Cairn; Bronze Age; 427290,375389;2.5 x 4.5m and 0.4m in height. Conjoined with linear clearance 354.

356 - Cairn; Bronze Age; 427295,375382;3.0 x 5.0m and 0.6m in height. Conjoined with linear clearance 354.

357 - Cairn; Bronze Age; 427301,375376;2.5 x 4.0m and 0.3m in height, masked by turf and soil. Overlies earthen bank 358.

358 - Earthen Bank; Bronze Age; 427306,375367;427303,375375;9.0m in length, 2.0m wide and 0.3m high, overlain by cairn 357.

359 - Possible Cairn; Bronze Age; 427309,375367;Low area of stone 1.5 x 2.0m, could be clearance or a fortuitous natural feature.

360 - Cairn; Bronze Age; 427277,375345;3.5 x 4.5m and 0.6m in height, comprising stones of various sizes. Disturbed by a small military pit dug into the southern side (1125).

361 - Cairn; Bronze Age; 427281,375342;2.0 x 2.5m and 0.4m in height, masked by turf and soil.

362 - Cairn; Bronze Age; 427291,375353;3.0 x 4.0m and 0.5m in height, some medium-sized

stone exposed in small disturbance at south.

363 - Earthen Bank; Bronze Age; 427302,375378,427313,375536; 1.75m in length, 1.5-2.0m wide and 0.3m high. The bank is breached by possible gateways 626 and 1194. A small section of bank was excavated in 1983 (619).

365 - Cairn; Bronze Age; 427333,375410; 4.5m in diameter and 0.4m in height, of medium-sized stone.

366 - Cairn; Bronze Age; 427318,375313; 4.0m in diameter, masked by turf and stone.

367 - Cairn; Bronze Age; 427315,375341; 2.5 x 3.0m and 0.5m in height, masked by turf and soil.

368 - Possible Cairn; Bronze Age; 427323,375337; 1.0 x 1.5m and 0.1m in height, masked by turf and soil. May be a fortuitous natural feature.

369 - Burial Cairn/Platform; Bronze Age; 427322,375354; 8.0 x 8.5m and 0.6m in height, of medium-sized stone. Disturbed at centre by possible old excavation trench c.1.0 x 3.0m. There is a sub-rectangular stony platform at the south edge of the cairn, c.2.0 x 3.0m.

370 - Cairn; Bronze Age; 427324,375372; 1.5 x 2.5m and 0.3m in height, masked by turf and soil.

371 - Cairn; Bronze Age; 427330,375342; 2.5 x 5.0m and 0.3m in height, masked by turf and soil.

372 - Cairn; Bronze Age; 427334,375348; 2.5 x 3.0m and 0.3m in height, masked by turf and soil.

373 - Cairn; Bronze Age; 427342,375346; 2.0 x 4.0m and 0.4m in height. There are two large orthostats at the mound edge, one set vertically, the other appears to be a natural earthfast.

374 - Cairn; Bronze Age; 427338,375367; 5.0 x 6.0m and 0.8m in height, masked by turf and soil and placed at the edge of naturally stony ground.

375 - Clearance Stone/Bullet and Mortar Scars; Bronze Age/Modern; 427338,375378; 427338,375378; Irregular feature c.4.9 x 9.5m and maximum 0.3m height, comprises at least three conjoined heaps of stone placed at the edge of an area of naturally stony ground. One stone slab has been damaged by mortars and bullets.

376 - Linear Clearance; Bronze Age; 427336,375384,427335,375380; 4.5 x 1.5m and 0.3m high, masked by turf and soil.

378 - Cairn; Bronze Age; 427341,375373; 2.5 x 3.5m and 0.3m in height, masked by turf and soil. Built at the edge of naturally stony ground.

380 - Mound; Bronze Age or Modern; 427348,375370; Low earthen feature 2.0 x 2.5m, conjoins cairn 381, of uncertain date and interpretation, either prehistoric or possibly associated with military activity c1939-45.

381 - Cairn; Bronze Age; 427351,375370; 4.0 x 4.5m and 0.5m in height, masked by turf and soil.

382 - Cairn; Bronze Age; 427354,375361; 1.0 x 1.5m and 0.3m in height.

383 - Lynchet; Bronze Age; 427347,375364,427360,375365; 6.5m in length and terminates to the south-east at cairn 382.

384 - Cairn; Bronze Age; 427361,375367; 2.5 x 5.0m and 0.4m in height, masked by turf and soil.

385 - Lynchet; Bronze Age; 427381,375390;427363,375368;28.0m in length and 0.2-0.3m high overlain by possible linear clearance 386 trackway 582.

386 - Possible Linear Clearance or Pile of Stones; Bronze Age or Post Medieval; 427368,375369; 427366,375380;12.0 x 1.5m and 0.3m in height with a break at the centre. This feature flanks trackway 582 and as such may be associated with this rather than being prehistoric.

387 - Burial Cairn; Bronze Age; 427359,375347;8.5 x 10.0m and 0.8m in height, of various stone sizes. The east edge has been robbed with adjacent heap of discarded material. The north-west edge may also have been be robbed.

388 - Cairn; Bronze Age; 427360,375382;3.5 x 4.5m and 0.6m in height, masked by turf and soil.

389 - Cairn; Bronze Age; 427355,375396;2.0m in diameter and 0.3m in height. There is a small upright slab at north-west side.

390 - Cairn; Bronze Age; 427367,375398;3.0 x 4.5m and 0.4m in height.

392 - Lynchet; Bronze Age; 427384,375382;427375,375376;10.0m in length and 0.3m high.

393 - Lynchets; Bronze Age; 427396,375372;427382,375360;c.19.0m in length and 0.3m high. Short section curves to north to join linear clearance 395.

394 - Cairn; Bronze Age; 427384,375368;1.0 x 2.0m and 0.2m in height, masked by turf and soil.

395 - Linear Clearance; Bronze Age; 427387,375373;427389,375367;7.0 x 2.5m and 0.4m high.

396 - Boulder Scarp; Bronze Age; 427395,375382;427392,375377;5.5m in length and 0.3m high. This may be a fortuitous natural feature.

397 - Cairn; Bronze Age; 427396,375369;2.5 x 3.0m and 0.2m in height (upslope), 0.5m (downslope), masked by turf and soil.

398 - Linear Clearance; Bronze Age; 427396,375365;427394,375366;2.5 x 1.0m and 0.2m high, masked by turf and soil.

399 - Possible Mound; Bronze Age or Modern; 427389,375344;1.5 x 3.0m. It is not clear if this low feature is prehistoric, or a modern military feature associated with activity c.1939-45, or is just a fortuitous natural feature associated with a vegetation change.

400 - Cairn; Bronze Age; 427396,375341;2.5 x 3.0m and 0.4m in height, masked by turf and soil

401 - Cairn; Bronze Age; 427374,375319;2.5 x 4.0m and 0.4m in height, some medium-sized stone visible at west where heaping is slightly higher.

402 - Mound; Bronze Age or Modern; 427383,375320;2.0 x 4.0m and 0.3m in height. It is not clear if this is prehistoric, or a military feature associated with activity c.1939-45 war.

403 - Cairn; Bronze Age; 427398,375313;6.5 x 7.0m and 1.0m in height (downslope), and 0.4m (upslope). Disturbed by sheep scrapes to the east.

404 - Lynchet; Bronze Age; 427407,375290;427397,375281;14.0m in length and 0.3m high.

405 - Cairn; Bronze Age; 427410,375272;Amorphous pile of stones 3.0 x 6.0m and 0.2m in height (upslope) and 0.6m (downslope). There is a heap of stones to the north, and a lower

plinth to the south.

410 - Earthen Bank; Bronze Age; 427372,375462;427290,375481;87m in length, 2.0m wide and 0.3m high. The junction of this feature with earthen bank 363 was excavated in 1983. To the east it may continue as a reduced feature (possible earthen bank 1070).

411 - Earthen Bank; Bronze Age; 427304,375510;427364,375498;61.0m in length, 2.0-2.5m wide and 0.3m high. This bank is interrupted by possible gateways (412 and 1068), and is cut by hollow way 570. May continue to the east as a reduced feature (earthen bank 428).

422 - Cairn; Bronze Age; 427306,375435;5.0 x 6.0m and 0.5m in height. The centre is disturbed and a lobe at south may be upcast from this.

423 - Mound; Bronze Age or Modern; 427309,375454;1.5m in diameter and 0.2m in height. It is not clear if this is prehistoric, or if it is a military feature associated with activity c.1939-45.

424 - Cairn; Bronze Age; 427327,375419;2.5 x 3.0m and 0.3m in height. Guidepost 2791 stands at the centre, but the cairn is likely to be prehistoric.

425 - Cairn; Bronze Age; 427384,375404;2.0 x 4.0m and 0.3m in height. Placed on the crest of lynchet 1081.

427 - Cairn; Bronze Age; 427406,375495;3.0 x 4.0m and 0.3m in height, masked by turf and soil.

428 - Earthen Bank; Bronze Age; 427364,375498;427418,375506;57.0m in length, 2.0-2.5m wide and 0.2m high. To the west it continues in abruptly higher form as earthen bank 411.

435 - Lynchet; Bronze Age; 427435,375490;427417,375446;50.0m in length and 0.3m high.

436 - Lynchet; Bronze Age; 427455,375481;427444,375452;33.0m in length and 0.3m high. It is disturbed at the centre by animal disturbance 623.

437 - Cairn; Bronze Age; 427427,375418;3.0 x 4.0m and 0.3m in height

438 - Cairn; Bronze Age; 427454,375432;2.5 x 3.0m and 0.2m in height (upslope), and 0.4m (downslope), masked by turf and soil.

439 - Possible Platform; Bronze Age; 427459,375412;Rectangular platform, 3.0 x 4.0m defined by a stony scarp 0.4m in height (downslope).

466 - Cairn; Bronze Age; 427443,375489;3.0 x 3.5m and 0.3m in height (upslope), and 0.5m (downslope), masked by turf and soil.

467 - Cairn; Bronze Age; 427464,375460;3.0m in diameter and 0.3m in height, masked by turf and soil.

468 - Probable House Site; Bronze Age; 427474,375456;Level platform measuring c.5.5x 8.0m, with a well-defined eyelip scarp on the downslope side 0.6m high. It is probably the site of a former circular timber building. Conjoins lynchet 1072.

469 - Cairn; Bronze Age; 427498,375498;3.5 x 5.5m and 0.2m in height (upslope), and 0.5m (downslope), masked by turf and soil. Conjoined with lynchet 470.

470 - Lynchet; Bronze Age; 427492,375491;427498,375495;7.5m in length and 0.3m high. One end is conjoined with cairn 469.

471 - Linear Clearance; Bronze Age; 427497,375462;427501,375469;3.0 x 8.0m and 0.1m in height (upslope), and 0.4m (downslope), masked by turf and soil.

567 - Possible Pile of Stones; Post Medieval; 427134,375437;Small stone (1063) erected on the summit of disturbed cairn 326, adjacent to hollow way 565, possibly set within its own cairn.

576 - Possible excavation; Modern; 427199,375115;Area of disturbance within stone bank 36, 1.5 x 3.0m, possibly illicit excavation.

580 - Possible Hollow Way; Bronze Age; 427314,375398;427241,375358;Broad feature different in appearance to nearby Post Medieval hollow ways. South-west end appears to respect prehistoric features - may be a prehistoric droveway.

582 - Track; Post Medieval; 427363,375395;427366,375366;Short, slight stretch of terraced track with a small rubble heap along its downslope side (386). It runs parallel to hollow way 570 and may be a little-used alternate route to this.

583 - Hollow Way; Post Medieval; 427415,375231;427399,375247;0.3m in depth.

587 - Shooting Butt; Post Medieval; 427063,375223;Earthen, horseshoe-shaped bank, that faces north-west, that externally measures c.6.0 x 7.0m and is 0.3m high.

588 - Shooting Butt; Post Medieval; 427146,375168;8.0m in diameter and maximum 1.0m in height with a slight external ditch around the north side.

593 - Shooting Butt; Post Medieval; 427234,375231;Earthen horseshoe-shaped banks 7.4m in diameter and 0.7m in height.

594 - Shooting Butt; Post Medieval; 427298,375278;Largely earthen horseshoe-shaped bank, that faces north-west and externally measures c.6.0 x 8.0m and is 0.4m high. It overlies hollow way 570.

595 - Shooting Butt/Possible Cairn; Post Medieval/Bronze Age; 427318,375293;Circular bank that externally measures c.7.5 x 9.0m. The internal edge is retained on three sides by a rectangular drystone revetment. This may be a converted prehistoric cairn.

596 - Shooting Butt; Post Medieval; 427279,375209;Horseshoe-shaped structure 6.5m in diameter and maximum 1.0m in height. Mostly turf-covered but some medium-sized stone visible.

597 - Shooting Butt/Possible Cairn or Linear Clearance; Post Medieval/Bronze Age; 427328,375273;Stony horseshoe-shaped bank that externally measures c.5.0 x 7.0m. Cuts into cairns 315 and 316 suggesting that this may have utilised a pre-existing feature.

598 - Shooting Butt; Post Medieval; 427349,375317;Earthen horseshoe-shaped bank, that externally measures c.5.0 x 6.5m and is 0.3m high.

599 - Shooting Butt; Post Medieval; 427404,375357;Earthen horseshoe-shaped bank, that externally measures c.7.0 x 7.5m and is 0.4m high. The western part of the interior has been cut by a small military pit (2767).

600 - Shooting Butt; Post Medieval; 427470,375355;Earthen, roughly square bank, that externally measures c.6.0 x 6.0m and is 0.4m high.

601 - Shooting Butt; Post Medieval; 427454,375394;Earthen horseshoe-shaped bank, that

externally measures c.5.0x 7.0m and is 0.4m high.

602 - Shooting Butt; Post Medieval; 427480,375413;Earthen, horseshoe-shaped bank, that externally measures c.6.0x 7.0m and is 0.4m high.

605 - Pit; Modern; 427104,375085;Sub-rectangular hollow 1.9m x 2.3m and 1.0m in depth. Associated with military activity c.1939-45.

606 - Pit; Modern; 427121,375095;Sub-rectangular hollow 1.7m x 2.5m and 0.5m in depth. Associated with military activity c.1939-45.

610 - Pit; Modern; 427139,375152;1.4m square and 0.5m in depth, probably associated with military activity c.1939-45,cut into cairn 134.

611 - Possible Water Tank; Post Medieval; 427381,375268;A rectangular hollow, 2.5 x 5.5m, with upcast on two sides. Aligned with the downslope end of drain 612.

612 - Drain; Post Medieval; 427312,375326;427376,375273;Shallow drain 0.5 x 1.5m wide and can be traced for c.85m. It aligns with possible water tank 611 and is cut by pit 1130.

613 - Pit; Modern; 427299,375414;Small oval pit with some upcast, is probably a military feature associated with military activity c.1939-45.

614 - Paired Pits; Modern; 427300,375431;Two small oval pits, 2.5 x 4.0m, with upcast mound are probably associated with military activity c.1939-45.

615 - Pit; Modern; 427331,375339;Small, deep oval pit with upcast on the downslope side is probably associated with military activity c.1939-45.

616 - Pit; Modern; 427343,375404;Small oval pit 1.0m in depth with upcast to one side is probably associated with military activity c.1939-45.

617 - Pit; Modern; 427405,375364;Small oval pit with some upcast is probably associated with military activity c.1939-45.

618 - Mound; Natural; 427418,375307;1.5x 3.0m and 0.3m high. Probably created by burrowing animals.

619 - Excavation Trench; Modern; 427288,375481;Backfilled excavation trench dug in 1983.

620 - Possible Mound; Modern; 427400,375447;2.0 x 1.5 and 0.3m high, of earth and a few stones. It is not clear if this is upcast from animal burrowing, or is a military feature.

622 - Possible House Site; Bronze Age; 427434,375395;A platform c.4.5m across is defined on the downslope side by a lynchet 0.3m high. It is possibly the site of a timber building, but it is not well defined and may be a fortuitous knoll.

623 - Animal Disturbance; Natural; 427450,375467;Area of uneven ground, the result of previous rabbit activity. It disturbs the centre of lynchet 436.

626 - Possible Gate; Bronze Age; 427289,375462;A gap 2.5m wide may be an original gateway.

627 - Probable House Site; Bronze Age; 427241,375475;Platform c.6.0m in diameter defined to the west by boundary bank 338 and to the east by a very slight lynchet.

631 - Possible House Site; Bronze Age; 427321,375265;Possible house site defined by linear clearance 314 and cairn 315 and measuring c. 7.0m across. May be fortuitous.

1060 - Paired Pits; Modern; 427172,375434;Two small oval pits probably associated with military activity c.1939-45.

1061 - Paired Pits; Modern; 427164,375426;Two small oval pits probably associated with military activity c.1939-45.

1062 - Lynchet; Bronze Age; 427160,375428;427154,375425;6.0m in length and 0.2m high, defines the edge of an area of uneven ground.

1063 - Possible Guidestone; Post Medieval; 427135,375439;Loosely-set stone, possibly associated with hollow ways but lack of bullet scarring suggests that it may be a Modern erection.

1064 - Slit Trench; Modern; 427127,375426;Slit trench associated with military activity c.1939-45.

1065 - Slit Trench; Modern; 427123,375430;Slit trench associated with military activity c.1939-45.

1066 - Paired Pits; Modern; 427224,375465;Two small sharp-sided pits probably associated with military activity c.1939-45.

1067 - Probable House Site; Bronze Age; 427228,375471;Low platform c.5.5m in diameter, defined on the downslope side by a lynchet 0.2m high. It is probably the site of a circular timber building.

1069 - Slit Trench; Modern; 427372,375465;Slit trench associated with military activity c.1939-45.

1070 - Possible Earthen Bank; Bronze Age; 427390,375461;427372,375462;Slight feature 18.0m in length, 2.0m wide and 0.1m high. May be fortuitous.

1071 - Hollow Way; Post Medieval; 427489,375475;427506,375472;Narrow hollow way can only be traced for a short distance.

1072 - Lynchet; Bronze Age; 427485,375464;427478,375459;9.0m in length and 0.3m high.

1073 - Track; Post Medieval; 427486,375447;427470,375444;Slight track can only be traced for a short distance.

1074 - Pile of Stones; Natural; 427499,375425;A doubtful cairn that is probably a natural grouping.

1075 - Lynchet; Bronze Age; 427438,375412;427436,375397;15.0m in length and 0.3m high.

1076 - Lynchet; Bronze Age; 427434,375387;427416,375375;22.0m in length and 0.3m high.

1077 - Cairn; Bronze Age; 427402,375362;1.5 x 2.5m and 0.3m in height, masked by turf and soil.

1078 - Possible House Site; Bronze Age; 427392,375369;Terraced area c.7.0m in diameter which could be the site of a timber building although there is no conclusive evidence for this.

1079 - Cairn; Bronze Age; 427372,375397;2.0 x 3.0m and 0.2m in height, masked by turf and soil.

- 1080 - Cairn; Bronze Age; 427377,375398; 2.0 x 2.5m and 0.3m in height.
- 1081 - Lynchet; Bronze Age; 427385,375397,427368,375399; Strongly curved feature c.26.0m in length 0.3m high.
- 1082 - Possible House Site; Bronze Age; 427382,375401; Platformed area, measuring c. 7-10m across, defined by lynchet 1081 may be a house site although there is no conclusive evidence for this.
- 1083 - Slit Trench; Modern; 427366,375438; Slit trench associated with military activity c.1939-45.
- 1084 - Hollow Way; Post Medieval; 427364,375420,427332,375425; Slight hollow way.
- 1085 - Paired Pits; Modern; 427333,375451; Two small pits 1.0m deep, probably associated with military activity c.1939-45.
- 1086 - Slit Trench; Modern; 427311,375436; Slit trench associated with military activity c.1939-45.
- 1087 - Linear Clearance; Bronze Age; 427376,375358,427382,375360; 7.5 x 2.5m and 0.5m high.
- 1088 - Linear Clearance; Bronze Age; 427383,375362,427386,375363; 3.5 x 2.0m and 0.5m high, and masked by turf and soil.
- 1089 - Possible Gate; Bronze Age; 427292,375386; This gap is 2.0m wide and if hollow way 580 is a prehistoric feature then this may be an original gateway.
- 1090 - Pit; Modern; 427274,375405; Small oval pit probably associated with military activity c.1939-45.
- 1091 - Cairn; Bronze Age; 427272,375404; 1.0 x 2.0m and 0.2m in height, masked by turf and soil.
- 1092 - Pit; Modern; 427312,375400; Small oval pit probably associated with military activity c.1939-45.
- 1093 - Pit; Modern; 427275,375434; Small oval pit probably associated with military activity c.1939-45.
- 1094 - Paired Pits; Modern; 427260,375399; Two small oval pits probably associated with military activity c.1939-45.
- 1095 - Pit; Modern; 427253,375400; Small oval pit probably associated with military activity c.1939-45.
- 1096 - Pit; Modern; 427250,375406; Small oval pit probably associated with military activity c.1939-45.
- 1097 - Pit; Modern; 427254,375393; Small oval pit probably associated with military activity c.1939-45.
- 1098 - Mound; Modern; 427258,375394; 1.0 x 3.5m, probably associated with military activity c.1939-45.
- 1099 - Slit Trench; Modern; 427300,375349; Slit trench associated with military activity c.1939-45.

1100 - Pit; Modern; 427232,375374;Small oval pit probably associated with military activity c.1939-45.

1101 - Cairn; Bronze Age; 427231,375391;0.4m in height, masked.

1102 - Pit; Modern; 427214,375394;Small oval pit probably associated with military activity c.1939-45.

1103 - Pit; Modern; 427222,375395;Small oval pit probably associated with military activity c.1939-45.

1104 - Possible Cairn; Bronze Age; 427215,375393;Stony mound 0.3m in height, may be just upcast from adjacent pit.

1105 - Pit; Modern; 427181,375414;Small oval pit probably associated with military activity c.1939-45.

1106 - Pit; Modern; 427179,375415;Small oval pit probably associated with military activity c.1939-45.

1107 - Paired Pits; Modern; 427182,375405;Two small oval pits probably associated with military activity c.1939-45.

1108 - Slit Trench; Modern; 427173,375388;Slit trench associated with military activity c.1939-45.

1109 - Pit; Modern; 427186,375388;Small oval pit probably associated with military activity c.1939-45.

1110 - Slit Trench; Modern; 427114,375418;Slit trench associated with military activity c.1939-45.

1111 - Slit Trench; Modern; 427099,375399;Slit trench associated with military activity c.1939-45.

1112 - Slit Trench; Modern; 427118,375388;Slit trench associated with military activity c.1939-45.

1113 - Cairn; Bronze Age; 427174,375352;1.0 x 2.0m and 0.1m in height, masked by turf and soil.

1114 - Possible Gate; Bronze Age; 427209,375353;This gap is c.5.0m wide and may be an original gateway.

1115 - Paired Pits; Modern; 427253,375357;Two pits probably associated with military activity c.1939-45.

1116 - Possible Cairn; Bronze Age; 427231,375327;2.0m in diameter and 0.1m in height, comprising only a few stones. May be a fortuitous feature.

1117 - Slit Trench; Modern; 427234,375333;Slit trench associated with military activity c.1939-45.

1118 - Slit Trench; Modern; 427236,375333;Slit trench associated with military activity c.1939-45.

1119 - Slit Trench; Modern; 427240,375331;Slit trench associated with military activity c.1939-45.

1120 - Slit Trench; Modern; 427244,375331;Slit trench associated with military activity c.1939-45.

1121 - Slit Trench; Modern; 427248,375329;Slit trench associated with military activity c.1939-45.

- 1122 - Slit Trench; Modern; 427259,375335;Slit trench associated with military activity c.1939-45.
- 1123 - Slit Trench; Modern; 427275,375328;Slit trench associated with military activity c.1939-45.
- 1124 - Slit Trenches; Modern; 427277,375325;Two Slit trenches overlapping each other at different angles, are associated with military activity c.1939-45.
- 1125 - Pit; Modern; 427277,375344;Small oval pit probably associated with military activity c.1939-45.It is dug into the side of cairn 360.
- 1126 - Possible Lynchet; Bronze Age; 427285,375321;427288,375314;7.8m in length and 0.3m high. It is not clear if this is a prehistoric feature, or one side of hollow way 570.
- 1127 - Pit; Modern; 427348,375341;Small, deep oval pit with upcast to one side, probably associated with military activity c.1939-45.
- 1128 - Lynchet; Bronze Age; 427365,375323;427352,375310;17.0m in length and 0.3m high.
- 1129 - Slit Trench; Modern; 427354,375310;Slit trench associated with military activity c.1939-45.
- 1130 - Pit; Modern; 427344,375302;Small oval pit probably associated with military activity c.1939-45.It cuts, and therefore post-dates, drain 612.
- 1131 - Pit; Modern; 427384,375322;Small oval pit probably associated with military activity c.1939-45.
- 1132 - Slit Trench; Modern; 427391,375318;Slit trench associated with military activity c.1939-45.
- 1133 - Pit; Modern; 427402,375316;Small oval pit probably associated with military activity c.1939-45.
- 1134 - Possible Cairn; Bronze Age; 427441,375349;2.5 x 3.5m and 0.2m in height. Situated at the crest of a part-stony slope, may be fortuitous.
- 1135 - Cist/Bullet Scars; Bronze Age/Modern; 427456,375324;Free-standing cist, comprising 3 upright stones and a displaced capstone, abutts a large natural boulder. East face of boulder and capstone are bullet-scarred.
- 1136 - Possible Stony Lynchet; Bronze Age; 427475,375371;427472,375366;7.0m in length and 0.3m high. It is not clear if this is prehistoric or natural.
- 1137 - Cairns; Bronze Age; 427421,375258;Two amorphous cairns piled against an earthfast boulder, westernmost: 2.0 x 2.5m, easternmost: 2.0m in diameter.
- 1138 - Slit Trench; Modern; 427364,375299;Slit trench associated with military activity c.1939-45.
- 1139 - Possible Lynchet; Bronze Age; 427317,375260;427323,375265;8.0m in length and 0.2m high. This slight feature marks a change in the angle of the natural slope and may be fortuitous.
- 1140 - Cairn; Bronze Age; 427333,375256;1.5 x 2.0m and 0.1m in height, masked by turf and soil.
- 1141 - Cairn; Bronze-Age; 427295,375232;0.7m in height, some bullet scars on stones.
- 1142 - Linear Clearance; Bronze Age; 427294,375247;427294,375259;2.25m in length, 2.5-3.5m

wide, and an average of 1.5m in height. This feature is discontinuous, being interrupted by hollow way 570 in three places where its line is perpetuated by sections of lynchet.

1143 - Possible House Site; Bronze Age; 427297,375264;Platform c.8.0m in diameter defined by linear clearance 275 and 1142 and a lynchet on the downslope side (2768). This may be the site of a timber building.

1145 - Lynchet; Bronze Age; 427272,375246;427285,375258;18.0m in length and 0.3m high.

1147 - Possible House Site; Bronze Age; 427234,375268;Semi-circular area c.5.0m in diameter defined on the downslope side by linear clearance 234. This may be the site of a circular timber building within a small yard.

1148 - Possible Earthen Bank; Bronze Age; 427264,375276;427265,375285;Slight feature 10.0m in length and 2.0m wide, may be fortuitous.

1149 - Lynchet; Bronze Age; 427250,375295;427257,375298;7.0m in length and 0.2m high.

1150 - Slit Trench; Modern; 427274,375319;Unusually large slit trench associated with military activity c.1939-45.

1151 - Slit Trench; Modern; 427271,375319;Slit trench associated with military activity c.1939-45.

1152 - Lynchet; Bronze Age; 427275,375316;427279,375313;5.5m in length and 0.2m high.

1153 - Lynchet; Bronze Age; 427259,375296;427263,375291;8.0m in length and 0.2m high.

1154 - Possible Gate; Bronze Age; 427215,375296;Gap that could be an original gateway.

1156 - Earthen Bank; Bronze Age; 427216,375286;427217,375283;3.0m in length, 1.5m wide and 0.3m high.

1157 - Lynchet; Bronze Age; 427209,375249;427213,375254;6.5m in length and 0.2m high.

1158 - Slit Trench; Modern; 427109,375280;Slit trench associated with military activity c.1939-45.

1159 - Lynchet; Bronze Age; 427146,375222;427154,375214;12.0m in length and 0.2m high.

1160 - Lynchet; Bronze Age; 427162,375230;427170,375222;12.0m in length and 0.3m high.

1181 - Lynchet; Bronze Age; 427356,375367;427353,375370;Slight feature.

1184 - Clearance Stone; Bronze Age; 427315,375289;427315,375289;Area of cleared stone c.3.0 x 6.0m, underlies cairn 298 with a combined height of 0.4m.

1225 - Stony Lynchet; Bronze Age; 427323,375109;427309,375090;Lyncheted section of natural slope 0.8m in height, with moderate sized stones.

1227 - Boulder Scarp; Bronze Age; 427114,375046;427107,375043;Residual stone behind.

1233 - Slit Trenches; Modern; 427430,375193;Two slit trenches of average dimensions 0.4m x 1.4m and 0.1m-0.2m in depth. Associated with military activity c.1939-45.

1234 - Slit Trench; Modern; 427452,375238;Single slit trench distinct from a group some 20m to the south 1233, 0.5m x 1.4m and 0.2m in depth. Associated with military activity c.1939-45.

1235 - Lynchet; Bronze Age; 427472,375259,427447,375233;A sharp lynchet maximum 1.0m in height defines the southern extent of a stone-free area some 20m wide, the northern limit of which corresponds with another, roughly parallel lynchet 1236.

1236 - Lynchet; Bronze Age; 427459,375269,427429,375254;0.5m in height and discernable as being sharper than the natural slope above. This lynchet defines the northern extent of a stone-free area some 20m wide 1235.

1237 - Hollow Way; Post Medieval; 427442,375226,427452,375227;0.5m in depth, visible only where it cuts a localised steepening of the natural slope for a length of c.10m.

1238 - Pit; Modern; 427453,375229;Foxhole 0.6m x 0.7m and 0.5m in depth. Associated with military activity c.1939-45.

1239 - Slit Trench; Modern; 427444,375229;1.1m x 0.3m and 0.3m in depth. Associated with military activity c.1939-45.

1240 - Possible Cairn; Bronze Age; 427431,375252;Sub-rectangular possible cairn 3.3m x 2.5m and 0.5m in height (downslope).

1241 - Pit; Modern; 427443,375259;Rectangular pit 0.8m x 0.4m and 0.1m in depth, probably a foxhole associated with military activity c.1939-45.

1242 - Lynchet or Cultivation Edge; Bronze Age; 427425,375227,427436,375253;0.4m in height and situated immediately below possible cairn 1240. Together with another lynchet 1236 this feature defines the northern extent of a cultivated area.

1243 - Possible House Site; Bronze Age; 427426,375258;Oval terraced platform with maximum diameters c.8m x 4m, the front edge of which is defined by a stony lip 0.5m in height.

1244 - Slit Trenches; Modern; 427384,375215;Group of seven trenches with average dimensions of 1.2m x 0.5m and 0.1m-0.2m in depth. Associated with military activity c.1939-45.

1245 - Bullet Scars; Modern; 427373,375227;Two large bullet scarred boulders associated with military activity c.1939-45.

1246 - Pit; Modern; 427435,375199;Foxhole 0.5m x 0.9m and 0.1m in depth. Associated with military activity c.1939-49.

1247 - Pits; Modern; 427412,375182;Group of three foxholes with average dimensions of 0.7m x 0.7m and 0.1m in depth. Associated with military activity c.1939-45.

1248 - Bullet Scars; Modern; 427433,375172;Single large bullet scarred boulder associated with military activity c.1939-45.

1249 - Hollow Way; Post Medieval; 427314,375203,427318,375205;0.4m in depth, continuation of hollow-ways 309 and 321 dividing around cairn 1250.

1250 - Cairn; Bronze Age; 427319,375202;Stone cairn 0.8m x 2.4m and 0.2m in height. Hollow-way 1249 divides around it.

1251 - Possible Clearance Stone; Bronze Age; 427325,375199;Single stone leant against another - could represent Bronze Age clearance or later disturbance.

1252 - Boulder Scarp; Bronze Age; 427351,375182,427351,375176;0.3m in height, aligned on-

and adjacent to linear clearance 1253. Ground to south-east is covered in scattered boulders in contrast to ground to north-west which is stone-free.

1253 - Linear Clearance; Bronze Age; 427353,375170;427351,375176;6.6m x 1.2m and 0.2m in height with both stone and earth content, cut by two slit trenches 1254. Ground to south-east is covered in scattered boulders in contrast to ground to north-west which is stone-free.

1254 - Paired Pits; Modern; 427352,375176;Two adjacent foxholes with average dimensions of 0.5m x 0.7m and 0.2m in depth. Both pits cut linear clearance 1253.

1255 - Cairn; Bronze Age; 427314,375132;Substantial stone and earth mound with maximum diameters of 3.2m and 2.0m, 0.4m in height.

1256 - Pits; Modern; 427321,375129;Three foxholes with average dimensions of 0.7m x 0.6m and 0.1m in depth. Associated with military activity c.1939-45.

1257 - Linear Clearance; Bronze Age; 427285,375157;427282,375152;5.0m in length, 0.9m wide and 0.1m in height 0.1m, both stone and earth content. This feature is aligned on an adjacent boulder scarp 199.

1258 - Hollow Way; Post Medieval; 427309,375104;427271,375070;0.2m in depth.

1259 - Cairn; Bronze Age; 427310,375117;Stone and earth cairn 0.2m in height.

1260 - Lynchet; Bronze Age; 427280,375060;427302,375092;Stony lynchet 0.5m in height.

1261 - Lynchet; Bronze Age; 427281,375104;427250,375065;Earthen lynchet 0.5m in height.

1263 - Cairn; Bronze Age; 427285,375084;Stony mound 5.5m x 4.1m.

1264 - Cairn; Bronze Age; 427284,375048;Sub-circular cairn of medium-sized stone 3.9m-4.7m in diameter, 0.1m in height (upslope) and 1.0m in height (downslope).

1265 - Cultivation Edge; Bronze Age; 427293,375046;427287,375052;An edge is discernable defining an area of flat ground to the south-west.

1266 - Possible Cairn; Bronze Age; 427282,375038;Consisting of a few buried stones, 1.4m in diameter and 0.2m in height.

1267 - Linear Clearance; Bronze Age; 427262,375049;427272,375035;A prominent area of medium-sized to large clearance stones, c.19m in length, 1.7m-4.0m in width and 0.6m in height.

1268 - Possible Clearance Stone; Bronze Age; 427289,375025;A few medium-sized to large stones 1.6m x 4.1m. May be natural.

1269 - Cairn; Bronze Age; 427261,375050;Cairn of medium-sized to large stone, 3.2m x 5.0m and 0.5m in height.

1270 - Pits; Modern; 427255,375095;Two shallow foxholes with average dimensions of 0.7m x 0.8m and <0.1m in depth, associated with military activity c.1939-45. Both foxholes cut adjacent features, namely linear clearance 182 and a hollow way 570.

1271 - Linear Clearance; Bronze Age; 427248,375085;427250,375087;Low strip of medium-sized clearance stones, 3.1m in length and 0.9m wide.

1272 - Probable Lynchet; Bronze Age; 427251,375089;427235,375071;Southernmost half of feature is a well-defined stony lynchet, beyond which the feature is less distinct. On the same alignment as earthen lynchet 180.

1273 - Linear Clearance; Bronze Age; 427259,375077;427281,375061;Maximum 0.5m in height, of medium-sized stone, broken by hollow ways.

1274 - Cairn; Bronze Age; 427235,375023;Stony crescent-shaped cairn 6.9m in length, c.1.0m wide and 0.2m in height (downslope), underlies linear clearance 1275.

1275 - Linear Clearance; Bronze Age; 427240,375029;427238,375026;Low area of stone clearance 0.8m wide and 0.15m in height, overlies cairn 1274 and lynchet 1280.

1276 - Cairn; Bronze Age; 427225,375013;Clearance stones, c.2.0m in width and 0.4m in height.

1277 - Excavation; Modern; 427229,375024;Sub-rectangular excavation trench c.12.0m x 12.5m and 0.2m in depth. Associated with 1960s-70s excavations by the Hunter Archaeological Society.

1278 - Cairn/Spoil Mound; Bronze Age/Modern; 427221,375020;Earth and stone mound 4.5m-5.0m in diameter and 1.0m in height. Spoil heap associated with 1960s-70s excavations by the Hunter Archaeological Society. Prior to excavation there was a small cairn here.

1280 - Bank; Bronze Age/Modern; 427233,375021;427227,375013;Earthen bank 1.5m wide, c.10m in length and 0.6m in height (downslope), appears to be a reinstated or modified feature associated with 1960s excavations by the Hunter Archaeological Society. It appears to originally have been a stoney feature and has either been replaced or was buried under a spoil heap and the stoney components have become masked.

1295 - Lynchet; Bronze Age; 427259,375049;427250,375042;0.3m in height, disturbed by hollow way 570.

1296 - Cairn; Bronze Age; 427222,375039;Sub-circular cairn 5.3m in diameter and 0.6m in height. Some small stone is visible on the surface of the cairn and there is a small pit at east.

1297 - Lynchet; Bronze Age; 427213,375044;427231,375055;1.0m in height. The lynchet is cut into the base of an escarpment with some stone stacked behind.

1298 - Spoil Mound; Modern; 427216,375020;Vestigial spoil heap from 1960's-70s excavations by Hunter Archaeological Society.

1299 - Excavation; Modern; 427203,375040;Associated with 1960s-70s excavations by the Hunter Archaeological Society.

1300 - Lynchet; Bronze Age; 427198,375039;427211,375043;Stony lynchet 0.3m in height. A small section at south east has evidently been removed during excavation.

1301 - Lynchet; Bronze Age; 427205,375035;427213,375044;0.6m in height, distinct from lynchet 1300.

1302 - Excavation; Modern; 427203,375021;1.8m x 2.4m. Overlain by a levelled spoil mound 1303. Associated with the 1960s-70s excavations by the Hunter Archaeological Society.

1303 - Spoil Mound; Modern; 427202,375018;Levelled spoil mound 4.5m in diameter and 0.2m in height. Overlies trench 1302. Associated with 1960s-70s excavations by the Hunter Archaeological Society.

- 1304 - Excavation; Modern; 427198,375013;One edge of an excavation trench, which includes 1320 and 1321. Associated with 1960s-70s excavations by the Hunter Archaeological Society.
- 1305 - House Site; Bronze Age; 427194,375016;Stone-built feature with an entrance at the west side. Excavated by the Hunter Archaeological Society in the 1960s-70s.
- 1306 - Lynchet; Bronze Age; 427197,375043;427194,375044;Height 0.4m.
- 1307 - Lynchet; Bronze Age; 427185,375042;427177,375035;Height 0.4m.
- 1308 - Stony Lynchet; Bronze Age; 427186,375044;427180,375040;Stony lynchet 0.3m in height, distinct from lynchet 1307.
- 1309 - Cairn; Bronze Age; 427170,375044;Small crescent-shaped cairn of medium-sized stone, some loose stone, 1.8m in length, 0.6m wide and 0.3m in height.
- 1310 - Lynchet; Bronze Age; 427098,375043;427105,375041;May denote cultivation avoiding boulder behind.
- 1311 - Cairn; Bronze Age; 427163,375040;Sub-circular cairn of medium-sized stone, 0.7m in height (downslope).
- 1312 - Stony Lynchet; Bronze Age; 427168,375042;427164,375038;Lynchet of medium-sized stone, 0.3m in height.
- 1313 - Excavations; Modern; 427181,375016;Two trenches associated with the 1960s-70s excavations by the Hunter Archaeological Society. The west trench has dimensions 2.5m x 6.5m, the east trench measures 2.0m x 5.7 and both are 0.1-0.2m in depth.
- 1314 - Spoil Mound; Modern; 427178,375020;Residual spoil from adjacent excavation trenches, 2.0m in diameter and 0.2m in height with a flat top. Associated with the 1960s-70s excavations by the Hunter Archaeological Society.
- 1315 - Stone Bank; Bronze Age; 427176,375035;427172,375012;Irregular and discontinuous stone bank c.2.0m in width, <0.6m in height with an overall length of 23m. Two breaks in the bank may be due to later paths crossing the feature.
- 1316 - Possible House Site; Bronze Age; 427176,375014;Level stone-free site, c. 5m across, defined by arc in stone bank 1315.
- 1317 - Linear Clearance; Bronze Age; 427174,375012;427180,375010;Area of medium-sized clearance stone 6.1m x 2.0m and 0.6m in height. Overlies stone bank 1318.
- 1318 - Stone Bank; Bronze Age; 427174,375011;427213,374999;Irregular bank of medium-large sized stones, c.2.8m in width and 0.3m-0.7m in height. Overlain by linear clearance 1317 and cairn 1319.
- 1319 - Cairn; Bronze Age; 427183,375010;Sub-circular cairn of medium-large sized stone, 3.5m in diameter and 0.5m in height. Overlies stone bank (feature number 1318).
- 1320 - Excavation; Modern; 427184,375012;427191,375017;Height 0.3m maximum. The edge of an excavation trench, which includes 1304 and 1321, associated with the 1960s-70s excavations by the Hunter Archaeological Society.
- 1321 - Possible Boulder Scarp or Excavation; Bronze Age/Modern; 427199,375008;

427192,375006;Height 0.3m. Although this looks like a boulder scarp it mirrors the edge of an excavation trench, which includes 1304 and 1320, dug by the Hunter Archaeological Society in the 1960s-70s.

1322 - Possible House Site; Bronze Age; 427195,375012;Arc in stone bank 1318 defines one edge of a possible excavated feature with 3-4 postholes and a diameter of c. 6.0m.

1323 - Spoil Mound; Modern; 427191,375005;Distinct mound 2.0m in diameter and 0.3m in height may be a cairn but no stone is visible. It lies at the edge of excavations carried out by the Hunter Archaeological Society in the 1960s-70s and may be a spoil heap or associated with casual backfilling.

1324 - Linear Clearance; Bronze Age; 427157,375026;427165,375020;9.5m x 1.0m and maximum 0.3m in height.

1325 - Cairn; Bronze Age; 427168,375016;Cairn of medium-sized stone 1.5m-2.0m in diameter and 0.3m in height.

1326 - Boulder Scarp; Bronze Age; 427166,375007;427167,375017;0.3m in height 0.3m, may contain some intermittent clearance stone.

1327 - Lynchet; Bronze Age; 427169,375005;427166,375003;Short lynchet maximum 0.3m in height, underlies linear clearance 1328.

1328 - Linear Clearance; Bronze Age; 427166,375008;427164,374988;Irregular bank of medium-sized stone c.20m in length, 1.8m wide and 0.6m in height (downslope). At its mid-point, the fabric of the bank appears to have pushed to the east.

1330 - Cairn; Bronze Age; 427155,375001;Oval in plan with minimum and maximum diameters of 1.5m and 2.7m, 0.4m in height. No visible stone.

1331 - Boulder Scarp; Bronze Age; 427152,375008;427150,375002;Height 0.3m.

1332 - Linear Clearance; Bronze Age; 427145,375009;427129,375007;L-shaped linear clearance c.16m in length, 1.0m wide, 0.3m in height (downslope) and 0.1m (upslope) with little visible stone. This feature defines a stone-free area to the north.

1333 - Boulder Scarp; Bronze Age; 427130,375021;427121,375017;Height 0.3m.

1334 - Building/Bullet Scars; Post Medieval/Modern; 427076,375016;Ruined quarry workers's shed c.3.0m x 3.0m. Two walls of dressed stone are upstanding to a height of c.1.0m, with bullet scars. One side was originally built over a split boulder but this is now collapsed.

1335 - Dressed Stone; Post Medieval; 427069,375017;Three gate post rough-outs placed together.

1336 - Dressed Stone; Post Medieval; 427071,375029;Gate post rough-out in small quarry pit.

1337 - Shelter; Post Medieval; 427049,375039;Small shelter constructed between three boulders, 0.7m in depth. There is one upstanding wall of dressed stone, and a second wall flanking a former entrance (now blocked).

1338 - Quarry or Shelter Wall; Post Medieval; 427047,375008;Two contiguous pits with a low wall (possibly a windbreak or stacked waste) to the west.

- 1339 - Pile of Stones; Post Medieval; 427033,375023;Line of stones associated with quarry pits nearby.
- 1340 - Cairn; Bronze Age; 427004,375018;Sub-circular turf-covered cairn 3.8m in diameter and 0.4m in height.
- 1341 - Cairn; Bronze Age; 427009,375026;Cairn of medium-sized stone, sub-oval in plan with minimum and maximum diameters of 2.2m and 4.0m, 0.4m in height.
- 1342 - Cairn; Bronze Age; 427009,375031;Small cairn 0.9m in diameter and 0.4m in height.
- 1343 - Stony Lynchet; Bronze Age; 427006,375043;427008,375028;Height 0.3m maximum height, some stone visible on and behind slope.
- 1344 - Boulder Scarp; Bronze Age; 427073,375041;427058,375048;Height 0.3m, some deposited stone on edge.
- 1345 - Cairn/Military Fieldwork/Bullet Scars; Bronze Age/Modern; 427056,375049;3.1m in diameter and 0.4m in height. A casual setting of stone at the west side of the cairn with some bullet scars appears to be military, associated with military activity c.1939-45.
- 1346 - Linear Clearance; Bronze Age; 427038,375058;427047,375054;Height 0.3m.
- 1347 - Lynchet; Bronze Age; 427010,375092;426999,375092;Height 0.3m.
- 1349 - Cairn; Bronze Age; 427039,375109;Small cairn 0.9m in diameter and 0.3m in height, comprising three or four small stones.
- 1350 - Cairn; Bronze Age; 427036,375093;Small cairn 1.1m in diameter and 0.3m in height, comprising a few turf-covered stones against an earthfast boulder.
- 1351 - Earthen Bank; Bronze Age; 427128,375075;427120,375092;Low earthen bank c.20m in length and 0.2m in height.
- 1412 - Cairn; Bronze Age; 427214,375070;Stony sub-circular cairn situated on the crest of a natural scarp, 2.2m-3.3m in diameter and 0.2m in height (downslope).
- 1413 - Possible Lynchet; Bronze Age; 427246,375073;427237,375065;Earthen lynchet c.12m in length and 0.3m in height. west end abuts a stony bank 1415.
- 1414 - Lynchet; Bronze Age; 427231,375053;427236,375058;Earthen lynchet containing occasional stones, 0.2m in height.
- 1415 - Linear Clearance; Bronze Age; 427233,375069;427237,375065;Stony bank 0.25m in height.
- 1416 - Stony Lynchet; Bronze Age; 427245,375065;427237,375056;Stony lynchet 0.4m in height.
- 1417 - Linear Clearance; Bronze Age; 427232,375051;427248,375040;Stony bank 0.6m in height, overlies an adjacent lynchet 1418.
- 1418 - Stony Lynchet; Bronze Age; 427237,375025;427246,375037;Stony lynchet 0.5m in height (downslope), overlain by a linear clearance 1417. Also overlain by 1275.
- 1419 - Burial Cairn or Cairn; Bronze Age; 427260,375034;Stony sub-circular cairn 2.0m-3.0m

in diameter and 0.8m in height (downslope). Three kerb stones define the downslope edge - there is a possibility that this is a burial site rather than a clearance cairn.

1420 - Slit Trench; Modern; 427265,375024;0.5m x 0.9m and 0.1m in depth 0.1m. Associated with military activity c.1939-45.Cuts clearance cairn 1421.

1421 - Cairn; Bronze Age; 427266,375023;Stony cairn 2.0, in diameter and 0.6m in height (downslope). Cut by military slit trench 1420.

1422 - Linear Clearance; Bronze Age; 427276,375030;427273,375028;Area of stone clearance 3.5m in length, 1.2m wide and 0.3m in height (downslope).

1470 - Stony Lynchet; Bronze Age; 427005,375044;427000,375046;0.5m in height.

1702 - Slit Trench; Modern; 427322,375121;Single trench 0.3m x 1.1m and 0.1m in depth, associated with military activity c.1939-45.

1725 - Slit Trench; Modern; 427381,375240;Single trench c.1.2m x 0.5m and 0.1m in depth. Associated with military activity c.1939-45.

2283 - Pit; Modern; 427305,375001;Trapezoidal pit 0.2m in depth, probably associated with military activity c.1939-45.

2286 - Cairn; Bronze Age; 427268,375004;Small bracken-covered cairn 2.6m in diameter and 0.3m in height.

2287 - Cairn; Bronze Age; 427258,375010;Of medium-sized stones, 2.5m in diameter and 0.3m in height.

2293 - Pit; Modern; 427458,375170;Shallow pit 0.5m square, associated with military activity c.1939-45.

2294 - Slit Trench; Modern; 427374,375150;0.4m x 1.7m, associated with military activity c.1939-45.

2295 - Pit; Modern; 427384,375143;Shallow pit 0.9m square. Associated with military activity c.1939-45.

2296 - Pit; Modern; 427384,375148;Shallow pit 0.9m square. Associated with military activity c.1939-45.

2297 - Slit Trench; Modern; 427365,375160;0.4m x 2.1m. Associated with military activity c.1939-45.

2298 - Pit; Modern; 427362,375156;1.0m square. Associated with military activity c.1939-45.

2299 - Slit Trench; Modern; 427371,375133;1.5m x 0.4m. Associated with military activity c.1939-45.

2300 - Slit Trench; Modern; 427363,375132;1.5m x 0.5m. Associated with military activity c.1939-45.

2301 - Pit; Modern; 427386,375159;Shallow L-shaped pit. Associated with military activity c.1939-45.

2302 - Slit Trench; Modern; 427395,375156;1.7m x 0.5m. Associated with military activity c.1939-45.

2303 - Pit; Modern; 427344,375133;1.4m x 0.8m. Associated with military activity c.1939-45.

2304 - Slit Trench; Modern; 427327,375094;1.8m x 0.4m. Associated with military activity c.1939-45.

2305 - Pit; Modern; 427441,375104;1.0m square. Associated with military activity c.1939-45,

2306 - Pit; Modern; 427434,375103;0.8m square. Associated with military activity c.1939-45,

2307 - Paired Pits; Modern; 427428,375093;Two adjacent pits each c.1.0msquare and c.1.0m in depth Associated with military activity c.1939-45.

2535 - Lynchet; Bronze Age; 427005,375106;427008,375124;0.1-0.2m in height.

2536 - Pit; Modern; 427039,375231;1.2 x 1.4m and 0.3m in depth, associated with military activity c.1939-45.

2537 - Pit; Modern; 427036,375247;1.1 x 1.8m and 0.3m in depth, associated with military activity c.1939-45.

2538 - Pit; Modern; 427037,375244;0.6 x 1.3m and 0.2m in depth, associated with military activity c.1939-45.

2539 - Pit; Modern; 427036,375242;0.5 x 0.8m and 0.3m in depth, associated with military activity c.1939-45.

2540 - Pit; Modern; 427039,375243;0.8 x 1.4m and 0.1m in depth, associated with military activity c.1939-45.

2541 - Probable Pit; Modern; 427053,375253;0.8 x 1.9m and 0.3m in depth, associated with military activity c.1939-45.

2542 - Possible Pit; Modern; 427057,375255;0.9 x 1.6m and 0.3m in depth, associated with military activity c.1939-45.

2543 - Pit; Modern; 427061,375248;Foxhole 0.5m square and 0.2m in depth, associated with military activity c.1939-45.

2544 - Pit; Modern; 427051,375222;0.8 x 1.3m and 0.2m in depth, associated with military activity c.1939-45.

2545 - Cairn; Bronze Age; 427067,375263;1.1 x 1.7m, of small stones around an earthfast boulder.

2546 - Pit; Modern; 427070,375244;0.6 x 1.2m and 0.2m in depth, associated with military activity c.1939-45.

2547 - Pit; Modern; 427068,375243;0.5m square and 0.1m in depth, associated with military activity c.1939-45.

2548 - Pit; Modern; 427067,375241;0.5 x 1.2m and 0.2m in depth, associated with military activity c.1939-45.

2549 - Pit; Modern; 427065,375268;0.7 x 1.2m and 0.3m in depth, associated with military activity c.1939-45.

2550 - Pit; Modern; 427099,375278;Foxhole 0.5m square and 0.2m in depth, associated with military activity c.1939-45.

2551 - Slit Trench; Modern; 427042,375381;0.5 x 2.1m and 0.2m in depth, associated with military activity c.1939-45.

2552 - Slit Trench; Modern; 427064,375399;0.5 x 1.9m and 0.4m in depth, associated with military activity c.1939-45.

2553 - Slit Trench; Modern; 427077,375397;0.6 x 1.6m and 0.4m in depth, associated with military activity c.1939-45.

2554 - Pit; Modern; 427099,375413;One pit 0.5 x 1.3m and 0.5m in depth, with a second, smaller pit 0.3 x 0.7m and 0.2m in depth immediately to the south. Associated with military activity c.1939-45.

2555 - Military Fieldwork; Modern; 427094,375494;Platform in the natural slope 2.0 x 4.0m, associated with military activity c.1939-45.

2556 - Bell Pit; Post Medieval; 427086,375476;Maximum 5.0m in diameter and maximum 0.8m in depth. Feature has possibly been modified with military pit (2679) dug into the bottom and drystone walled structure (2680) to south.

2557 - Pit; Modern; 427072,375458;1.1 x 1.3m and 0.1m in depth, associated with military activity c.1939-45.

2558 - Pit; Modern; 427074,375461;1.2m square and 0.3m in depth, associated with military activity c.1939-45.

2559 - Pit; Modern; 427076,375471;0.9 x 2.0m and 0.4m in depth, associated with military activity c.1939-45.

2560 - Pit; Modern; 427078,375475;0.9 x 2.0m and 0.5m in depth, associated with military activity c.1939-45.

2561 - Pit; Modern; 427085,375459;1.0 x 2.0m and 0.5m in depth, associated with military activity c.1939-45.

2562 - Pit; Modern; 427022,375406;Chevron-shaped pit overall length 1.9m,0.5m wide and 0.2m in depth, associated with military activity c.1939-45.

2563 - Slit Trench; Modern; 427010,375386;Irregular trench 0.6 x 1.9m and 0.2m in depth, associated with military activity c.1939-45.

2564 - Possible Animal Pen; Bronze Age; 427190,375118;Low rectangular structure c.2.5x4.0m, possibly an animal pen.

2565 - Lynchet; Bronze Age; 427214,375115;427210,375106;0.3m in height.

2566 - Possible Gate; Bronze Age; 427177,375075;Gap in bank 1.3m wide.

2567 - Slit Trench; Modern; 427135,375134;1.3 x 0.6m and 0.2m in depth, associated with

military activity c.1939-45.

2568 - Pit; Modern; 427152,375122;0.6m square and 0.2m in depth, associated with military activity c.1939-45.

2569 - Possible House Site; Bronze Age; 427200,375131;Level area defined by curvilinear bank 151, may be a house site of 7m or more diameter.

2570 - Stoney Lynchet/Linear Clearance; Bronze Age; 427209,375132; 427225,375132; Pronounced lynchet with stone dumped on, and behind it.

2571 - Cairn; Bronze Age; 427224,375137;Maximum 4.9m in diameter and 0.5m in height, of large and medium-sized stone. Disturbed by construction of casual shelter or military feature (2770).

2572 - Probable House Site; Bronze Age; 427246,375130;Well-defined platform 4.4m diameter.

2573 - Possible Track; Bronze Age; 427253,375132;427237,375153;Defined at a width of c.6m by lynchets 198, 165 and linear clearance 166.

2574 - Cairn; Bronze Age; 427203,375181;3.0m in diameter and 0.7m in height. Some medium-sized stone is visible.

2575 - Lynchet; Bronze Age; 427260,375186;427264,375180;0.2m in height.

2576 - Clearance Stone; Bronze Age; 427266,375160;Small area of dumped stone on edge of stony ground.

2577 - Cairn; Bronze Age; 427241,375214;Triangular cairn maximum 1.6 x 2.1m and 0.3m in height.

2578 - Lynchet; Bronze Age; 427239,375224;427241,375212;0.5m in height with some stone visible at the corner.

2579 - Probable Cairn; Bronze Age; 427186,375207;2.4 x 3.1m and 0.4m in height.

2580 - Pit; Modern; 427161,375167;0.6 x 0.4m and 0.2m in depth, associated with military activity c.1939-45.

2581 - Pit; Modern; 427151,375160;0.6m square and 0.2m in depth, associated with military activity c.1939-45.

2582 - Pit; Modern; 427148,375166;0.7m square and 0.1m in depth, cut into shooting butt 588, associated with military activity c.1939-45.

2583 - Pit; Modern; 427141,375146;0.8 x 1.0m and 0.3m in depth, associated with military activity c.1939-45.

2584 - Possible Pit or Quarry; Modern or Post Medieval; 427116,375156;1.8 x 2.0m and 0.5m in depth, with some spoil to south-east side. Could be a quarry or more likely a pit associated with military activity c.1939-45.

2585 - Pit; Modern; 427127,375212;0.7m square and 0.2m in depth, associated with military activity c.1939-45.

- 2586 - Pit; Modern; 427127,375216;0.6 x 0.9m and 0.2m in depth, associated with military activity c.1939-45.
- 2587 - Slit Trench; Modern; 427091,375222;1.3 x 0.7m and 0.2m in depth cut into the bottom of a quarry, associated with military activity c.1939-45.
- 2588 - Possible Cairn; Bronze Age; 427089,375171;Maximum 1.5 x 2.6m and 0.4m in height.
- 2679 - Possible Pit; Modern; 427086,375475;0.8 x 1.3m, dug into the bottom of bell pit 2556. Appears to be associated with drystone walling (2680) immediately to south. Both features are possibly associated with military activity c.1939-45.
- 2680 - Shelter or Military Fieldwork; Post Medieval or Modern; 427086,375470;427088,375471; Low drystone walled structure 2.2m in length, either a shelter associated with pit 2679 or with bell pit 2556.
- 2681 - Lynchet; Bronze Age; 427225,375128;427228,375130;Defines northern limit of possible house site 161.
- 2689 - Cairn; Bronze Age; 427189,375079;Maximum 3.5m in diameter and 0.3m in height, of mostly large stones.
- 2693 - Cairn; Bronze Age; 427241,375035;Irregularly shaped mound maximum 4.5 x 3.5m and 0.4m high of medium-sized stone disturbed in northern part.
- 2694 - Linear Clearance; Bronze Age; 427252,375016;427245,375033;1.8m in length, 2.5-4.4m wide and 0.5m in height. Of medium-sized stone, and cut by hollow ways.
- 2695 - Lynchet; Bronze Age; 427272,375034;427270,375030;0.3m in height.
- 2696 - Excavation; Modern; 427245,375043;Excavation trench 0.1m in depth. Associated with 1960s-70s excavations by the Hunter Archaeology Society.
- 2702 - Pit; Modern; 427450,375250;Rectangular pit 0.8m x 0.4m and 0.1m in depth, probably a foxhole associated with military activity c.1939-45.
- 2703 - Slit Trenches; Modern; 427440,375205;Two slit trenches of average dimensions 0.4m x 1.4m and 0.1m-0.2m in depth. Associated with military activity c.1939-45.
- 2704 - Slit Trench; Modern; 427455,375223;Single trench c.0.4m x 1.4m and 0.1m in depth. Associated with military activity c.1939-45.
- 2705 - Slit Trenches; Modern; 427453,375206;Close group of five slit trenches of average dimensions 0.4m x 1.4m and 0.1m-0.2m in depth. Associated with military activity c.1939-45.
- 2734 - Hollow Way; Post Medieval; 427050,375380;426700,375175;Band of multiple hollow ways. Joins with hollow way route 565.
- 2746 - Hollow Way; Post Medieval; 427228,375158;427213,375151;Two short sections of parallel hollow ways.
- 2747 - Cairn; Bronze Age; 427191,375104;Sub-circular cairn maximum 3.0m in diameter.
- 2748 - Cairn; Bronze Age; 427194,375092;Small sub-circular cairn maximum 2.0m in diameter.

- 2749 - Cairn; Bronze Age; 427171,375088;2.5 x 4.7m.
- 2750 - Possible Lynchet or Hollow Way; Bronze Age or Post Medieval; 427225,375010; 427223,374999; c.12m in length, alternatively may be downslope scarp of terraced hollow way 570.
- 2751 - Pit; Modern; 427302,375286;Rectangular pit 1.5 x 1.8m,probably associated with military activity c.1939-45
- 2767 - Pit; Modern; 427403,375356;Rectilinear pit 1.9m x 1.5m associated with military activity c. 1939-45. Cuts shooting butt 599.
- 2768 - Lynchet; Bronze Age; 427297,375267;427300,375263;0.3m high and 7m in length. May define limit of possible house site 1143.
- 2769 - Lynchet; Bronze Age; 427047,375054;0.3m high.
- 2770 - Shelter or Military Fieldwork; Post Medieval or Modern; 427224,375136;Shelter or military structure, c.3m x 2m built into cairn 2571.
- 2772 - Lynchet; Bronze Age; 427225,375271;427230,375275;Height 0.3m.
- 2783 - Stone Bank; Bronze Age; 427226,374995;427226,375008;c. 16m long, height 0.2m upslope and 0.5m downslope.
- 2785 - Spoil Mound; Modern; 427234,375018;Residual spoil defined by grassy area. Related to 1960s-70s Hunter Archaeological Society excavations.
- 2786 - Bullet and Mortar Scars; Modern; 427065,375026;An extensive area of outcropping rocks peppered with bullet and mortar scars. Associated with military activity 1939-45.
- 2787 - Possible Lynchet; Bronze Age; 427200,375083;427199,375067; c. 14m in length and 0.3m high. Possibly a lynchet, but may also be natural. Cultivated ground to east.
- 2788 - Shelter or Military Fieldwork; Post Medieval or Modern; 427196,375123;Small shelter or military structure cut into pre-existing cairn (150). North side built of 3/4 courses of drystone walling construction probably taken from cairn material.
- 2789 - Lynchet; Bronze Age; 427218,375254;427226,375262;12m long and 0.2m high.
- 2790 - Possible Lynchet; Bronze Age; 427438,375294;427432, 375285; c. 14m long and 0.3m high. Possibility that it may be natural.
- 2791 - Guidestone/Bullet Scars; Post Medieval/Modern; 427327,375419;Roughly rectangular pillar 2.05m high and 0.20 x 0.35m in plan, inserted into cairn 424 and situated on a false crest when approached from the north. East face is inscribed "SI",also bullet scarred.
- 2803 - Quarries; Post Medieval; 427150,375416;Discrete area of quarrying comprising many small hollows within an area of stoney ground.
- 2804 - Quarries; Post Medieval; 427070,375245;Discrete area of quarrying comprising many small hollows.

Sheet 5

472 - Cairn; Bronze Age; 427537,375457; Stone and earth, 2.6m x 4.0m and 0.3m in height.

473 - Burial Cairn/Possible Platform; Bronze Age; 427557,375476; Large irregular cairn of predominantly large stone, c. 12.5m x 9.0m in plan dimension. There is a possible platform on the south side 0.3m in height, and a disturbance in the centre of cairn with slighter indications of disturbance continuing to the North-West. Disturbed by shooting butt 604 at south-east side.

574 - Hollow Way/Track; Post Medieval; 427593,375377,427500,375315; Deeply incised where crossing escarpment. At the North-Eastern end it is terraced into the slope.

586 - Hollow Way; Post Medieval; 427579,375431,427516,375468; Height 0.3m. Aligned on guidestone.

603 - Shooting Butt; Post Medieval; 427507,375433; Earthen shooting butt probably of collapsed turf construction, c.6m in diameter and upstanding to a height of 0.4m.

604 - Shooting Butt; Post Medieval; 427561,375474; Rectangular butt with internal retaining of large stones, 0.4m in depth cut into a burial cairn 473.

624 - Pit; Post Medieval; 427511,375464; Sub-rectangular pit 2.3m x 0.8m with spoil to south-east.

1230 - Possible Boulder Scarp; Bronze Age; 427511,375291,427505,375285; Break in slope that may be natural.

1231 - Possible Boulder Scarp; Bronze Age; 427509,375282,427498,375274; Break in slope that may be natural.

1232 - Possible Lynchet; Bronze Age; 427511,375278,427504,375270; Ground surface is significantly flatter downslope of this possible lynchet.

1455 - Possible Hollow Way; Post Medieval; 427740,375233,427740,375227; 3.0m wide and 0.2m in depth, leads in the direction of Barbrook.

1456 - Drain; Post Medieval; 427869,375115,427963,375144; 0.5-1.0m wide and 0.2m in depth.

1457 - Possible Cultivation Edge; Bronze Age; 427968,375159,427961,375170; A scarp 0.2m in height and c.14m in length may represent a cultivation edge along the base of the natural slope. Ground above the scarp is covered in scattered boulders in contrast to ground below the scarp which is clear of stones. This may well be a natural feature reflecting geological changes.

1474 - Pit; Modern; 427999,375190; 1.7m x 1.9m and 0.5m in depth. Associated with military activity c.1939-45.

1475 - Pit; Modern; 427988,375127; 2.1 x 1.2m and 0.3m in depth with upcast to south. Associated with military activity c.1939-45.

1477 - Pit; Modern; 427988,375181; Foxhole built on slope out of loose quarried stone.

1478 - Possible Hollow Way; Post Medieval; 427890,375079,427885,375065; Possible route through rocks on natural slope defined at a width of c.2m and 0.5m in depth.

1479 - Hollow Way; Post Medieval; 427837,375075,427831,375049; 0.5m in depth.

1480 - Possible Pit; Modern; 427835,375052;1.8 x 1.0m and 0.6m in depth. Possible tree hole, though more likely a pit associated with military activity c.1939-45.

2000 - Cairn; Bronze Age; 427538,375482;Small cairn of large stones, 1.3m x 0.7m and 0.3m in height.

2001 - Linear Clearance; Bronze Age; 427535,375483,427529,375483Regular curvilinear feature 6.5m x 0.9m and 0.2m in height, some large stone is visible through the turf.

2002 - Cairn; Bronze Age; 427538,375479;Small, low cairn of large stones, 2.0m x 0.9m.

2003 - Cairn; Bronze Age; 427558,375465Small sub-circular cairn of large stones, 1.3m x 0.8m.

2004 - Bullet Scars; Modern; 427577,375448Single bullet scarred rock. Associated with military activity c. 1939-45.

2005 - Pit; Modern; 427604,375394;Small rectangular pit of uncertain depth, 0.6m x 0.5m. Associated with military activity c.1939-45.Probably associated with an adjacent pit 2006.

2006 - Pit; Modern; 427603,375390Shallow circular hollow 1.6m in diameter and 0.2m in depth, with a slight lip to the S. Associated with military activity c.1939-45.Probably associated with an adjacent pit (feature number 2005).

2007 - Lynchet; Bronze Age; 427576,375411,427570,375397Earthen feature, 0.4m in height, cut into the natural slope.

2008 - Pit; Modern; 427541,375435;Small rectangular pit of unknown depth, 1.3m x 0.5m. Associated with military activity c.1939-45.

2009 - Possible Cairn; Bronze Age; 427527,375386;Cairn of large stones, 3.2m x 1.0m. Dense bracken cover makes definite identification of the feature difficult.

2010 - Lynchet; Bronze Age; 427544,375373;427539,375367;Height 1.0m, defines a level platform upslope. There is no evidence to suggest that this represents a house site.

2011 - Cairn; Bronze Age; 427552,375365;Substantial stony cairn 3.8m in diameter, 0.3m in height (upslope) and 1.0m in height (downslope). There is no observable relationship with the adjacent boulder scarp (feature number 2012).

2012 - Boulder Scarp; Bronze Age; 427562,375377,427549,375360Height 0.4m.No observable relationship with the adjacent cairn 2011.

2013 - Boulder Scarp; Bronze Age; 427574,375395,427564,375382;Height 0.4m.

2014 - Quarry; Post Medieval; 427575,375355;Feature defined by a curvilinear scarp cut into the natural slope, could be interpreted as a house site but quarried appearance suggests this is not the case.

2015 - Possible Linear Clearance; Bronze Age; 427530,375330;Irregular feature of large and medium-sized stones, 0.3m in height (upslope) and 1.3m in height (downslope) with plan dimensions of c.6m x 3m. Partly turf covered. The north-west side of this feature is cut by hollow way 574, indeed the feature could well represent no more than upcast from the hollow way where it crosses the natural stony outcrop.

2016 - Bullet Scars; Modern; 427507,375343Single large bullet scarred boulder associated with

military activity c.1939-45.

2017 - Lynchet; Bronze Age; 427537,375331;427542,375344;Height 0.4m, some stone is visible through a cover of turf and bracken. Hollow way 574 terraced into natural slope above this lynchet.

2018 - Lynchet; Bronze Age; 427551,375319;427564,375359;Height 0.5m, some stone is visible through a cover of turf and bracken. The south-western section is either part of 2018 or could be part of hollow way 2035.

2019 - Linear Clearance; Bronze Age; 427562,375333;Crescent-shaped feature of predominantly medium-sized stone (determinable only where visible through dense bracken cover), 5.0m in length, 1.1m wide, 0.3m in height (upslope) and 1.0m in height (downslope). A single large stone is visible on the surface of the clearance. Overlies upper edge of lynchet 2020.

2020 - Lynchet; Bronze Age; 427559,375325;427567,375334;Underlies cairn 2019.

2021 - Lynchet; Bronze Age; 427591,375360;427585,375340;Height 1.0m. Some stone is visible through dense the bracken cover. An offset near the centre may represent the position of a ramp-like entrance.

2022 - Possible Lynchet; Bronze Age; 427586,375358;427585,375356;Height 0.2m. May be fortuitous.

2023 - Stone Bank; Bronze Age; 427630,375336;427592,375359;Irregular bank loosely formed of large and medium-sized stones, c. 47m in length and between 0.8m and 3.0m in width. Height varies between 0.1m at the north end and maximum 0.5m near the centre.

2024 - Possible Lynchet; Bronze Age; 427594,375352;427600,375356;Height 0.2m. May be fortuitous.

2025 - Cairn; Bronze Age; 427632,375334;1.5m-2.0m in diameter and 0.3m in height. Large stones visible through turf cover.

2026 - Possible Cairn; Bronze Age; 427618,375337;2.0m in diameter and 0.1m in height. May be no more than three or four stones. Turf and heather covered.

2027 - Cairn; Bronze Age; 427617,375328;Small, irregular group of large stones, 1.5m x 3.8m and 0.3m in height.

2028 - Stone Bank; Bronze Age; 427586,375337;427601,375316;Irregular bank loosely formed of large and medium-sized stones, c.28m in length and 2m in width. Height varies between 0.2m (at the south-east end) and 0.5m (at the north-west end). There is a cairn 2029 near centre and a cairn or bulbous terminal to the north-west end (2030).

2029 - Cairn; Bronze Age; 427593,375324;Sub-circular cairn of medium-sized and large stones piled along stone bank 2028, 2.5m in diameter and 0.3m in height.

2030 - Possible Cairn; Bronze Age; 427584,375338;Substantial stony feature 4.4m in diameter and 1.3m in height, with dense bracken cover. May be a cairn or a bulbous terminal to stone bank 2028.

2031 - Cairn; Bronze Age; 427520,375259;Substantial sub-circular cairn of medium-sized stone 2.4m- 3.0m in diameter and 0.3m in height. Partly turf covered.

2032 - Bullet Scars; Modern; 427528,375270;Single bullet scarred rock. Associated with military activity c.1939-45.

2033 - Bullet Scars; Modern; 427536,375265;Single bullet scarred rock. Associated with military activity c.1939-45.

2034 - Bullet Scars; Modern; 427537,375227;Single bullet scarred rock. Associated with military activity c.1939-45.

2035 - Hollow Way; Post Medieval; 427517,375270,427555,375322;Poorly defined way, slightly terraced into the natural slope.

2036 - Quarry; Post Medieval; 427503,375253;Sub-rectangular pit 2.0m x 2.9m and 0.4m in depth. There is an area of spoil immediately to the south-east.

2037 - Cairn; Bronze Age; 427506,375255;1.5m in diameter and 0.3m in height. A large upright slab to the east of the cairn may have been levered up for working by quarry men although erosion in the top suggests it has been in an upright position for some time.

2038 - Cairn; Bronze Age; 427587,375295;Large cairn of predominantly large stones, 3.5m-5.0m in diameter and 0.3m in height. Partly turf covered.

2039 - Cairn/Bullet Scars; Bronze Age/Modern; 427575,375297;Some stones on and around a large flat boulder. Some bullet scars visible.

2040 - Cairn; Bronze Age; 427575,375313;Substantial cairn of predominantly large stones 3.5m-5.0m in diameter 0.8m and in height. There is a large stone slab at the west of the cairn. Turf and bracken covered.

2041 - Linear Clearance; Bronze Age; 427569,375319;427572,375314;Curvilinear stone bank 1.5m in width and 0.4m in height. The bank forms a sub-circular feature 6.9m in diameter (see 2042). Densely bracken covered.

2042 - Probable House Site; Bronze Age; 427569,375317;Sub-circular level platform of c. 4.0m diameter cut in the natural slope, defined by stone bank 2041 upslope and slight lynchet downslope.

2043 - Lynchet; Bronze Age; 427577,375331;427574,375325;Height 0.4m.

2044 - Cairn; Bronze Age; 427543,375285;Small group of moderate-sized stones 0.9m in diameter and 0.2m in height.

2045 - Linear Clearance; Bronze Age; 427512,375315;427529,375310;Low, regular turf-covered bank 18m in length, 1.6m wide and 0.3m in height.

2046 - Stone Structure; Post Medieval; 427663,375482;Rectangular structure known as Robin Hood's Shooting Table made up of dressed slabs topped by two dressed stone slabs (one displaced). The name may suggest it was used as a table, probably associated with grouse shooting as the adjacent track was built to access the butts to the south west. Alternative possibilities are a seat or horse mounting step. Associated with bridge abutment 2047 and hollow way 2048. There are three further stone slabs on the ground immediately west of this feature. It lies adjacent to a small spring of clear water.

2047 - Bridge Abutment; Post Medieval; 427664,375489;Made up of coursed stonework, and associated with dressed stone structure 2046 and hollow way 2048.

2048 - Hollow Way/Track; Post Medieval; 427615,375404,427665,375485; Cut into steep natural slope. In parts a hollow way but lower is a track terraced into the slope which levels out at an artificial platform at the stream crossing-point. Associated with dressed stone structure 2046 and bridge abutment 2047.

2049 - Bullet Scars; Modern; 427620,375432; Single boulder with bullet scars on its south-east face. Associated with military activity c.1939-45.

2051 - Boulder Scarp; Bronze Age; 427528,375469,427532,375482; Discontinuous earthen scarp 0.5m in height with earthfast boulders.

2052 - Linear Clearance; Bronze Age; 427527,375480; Linear stone and earth cairn situated upslope of boulder scarp 2051. 5.4m x 1.9m and 0.4m in height.

2053 - Cairn; Bronze Age; 427524,375473; Small stone and earth cairn, 1.5m in diameter and 0.3m in height.

2054 - Cairn; Bronze Age; 427525,375450; Stone and earth cairn, 5.3m x 2.5m and 0.5m in height.

2055 - Possible Pile of Stones; Post Medieval; 427656,375381; Small stone and earth mound 1.4m-1.9m in diameter and 0.4m in height. Possibly natural.

2056 - Hollow Way; Post Medieval; 427662,375385,427665,375394; Braided hollow way, defined on the steep natural slope at a depth of 1.0m. Probably a continuation of hollow way 2060.

2057 - Hollow Way; Post Medieval; 427662,375399,427656,375392; Braided hollow way, defined on the steep natural slope at a depth of 1.0m. Probably a continuation of hollow way 2060.

2058 - Hollow Way; Post Medieval; 427670,375409,427649,375398; Braided hollow way, defined on the steep natural slope at a depth of 1.0m. Probably a continuation of hollow way 2060. Cut by pit 2059.

2059 - Pit; Modern; 427654,375402; Rectangular pit 1.2m x 1.6m and 0.2m in depth. Cut into hollow-way 2058. Associated with military activity c.1939-45.

2060 - Hollow Way; Post Medieval; 427686,375406,427679,375405; Depth 0.3m.

2061 - Linear Clearance; Bronze Age; 427636,375339,427643,375338; Earthen bank with significant stone content, 7.5m in length, 1.4m wide and 0.3m in height. Cut by foxhole 2062.

2062 - Pit; Modern; 427643,375337; Foxhole 0.6m x 0.9m and 0.5m in depth. Cuts linear clearance 2061. Associated with military activity c.1939-45.

2063 - Possible House Site; Bronze Age; 427639,375337; Defined by curving stone bank 2061 with a diameter of about 7-9m.

2064 - Cairn; Bronze Age; 427647,375332; Sub-circular stone cairn 3.0m in diameter and 0.2m in height.

2065 - Lynchet; Bronze Age; 427645,375338,427646,375335; Earthen lynchet 0.2m in height.

2066 - Cairn; Bronze Age; 427644,375335; Small cairn of stone and earth, 0.7m in diameter and 0.1m in height.

2067 - Pit; Modern; 427661,375356;Foxhole 0.5m square and 0.5m in depth. Associated with military activity c.1939-45.

2068 - Hollow Way; Post Medieval; 427662,375336;427680,375380;Series of braided hollow ways, truncated at edge of riverine erosion scarp.

2069 - Cairn; Bronze Age; 427660,375321;Irregular cairn maximum 5.5m in diameter, 0.3m in height (upslope) and 0.5m in height (downslope).

2070 - Linear Clearance; Bronze Age; 427647,375329;427646,375322;Bank of medium-sized stones, 0.3m in height, c.7m in length and 0.8m wide at the north end widening to 2.2m at the south end.

2071 - Cairn; Bronze Age; 427677,375303;Small cairn of medium-sized clearance stones, 1.3m-2.0m in diameter and 0.3m in height.

2072 - Possible Cairn; Bronze Age; 427670,375284;Small cairn of medium-sized stones maximum 0.9m in diameter and 0.2m in height.

2073 - Linear Clearance; Bronze Age; 427682,375293;427690,375272;Discontinuous area of stone along the crest of a steep riverine scarp comprising large earthfast boulders around which medium-sized stones have been piled, c.24m in length and 1m wide.

2074 - Hollow Way; Post Medieval; 427718,375181;427723,375214;Braided hollow way.

2075 - Hollow Way; Post Medieval; 427728,375155;427706,375157;Braided, heads toward natural declivity in valley slope.

2076 - Bullet Scars; Modern; 427804,375088;Group of boulders the south-east faces of which are bullet scarred. Associated with military activity c.1939-45.

2077 - Hollow Way; Post Medieval; 427861,375184;427847,375174;Depth 0.2m.

2078 - Slit Trench; Modern; 427914,375227;Chevron style foxhole 0.5m in depth, similar to foxhole (feature number 2079). Associated with military activity c.1939-45.

2079 - Slit Trench; Modern; 427932,375207;Chevron style foxhole 0.5m in depth, similar to foxhole (feature number 2078). Associated with military activity c.1939-45.

2080 - Pit; Modern; 427971,375223;D-shaped pit possibly a machine gun nest, on west-facing slope, built of large stones placed around boulders, with interior measurements of 1.2m x 2.2m.

2081 - Track; Post Medieval; 427964,375237;428069,375148;Terraced trackway cut into the natural slope at a width of 1.8m. Appears to be a continuation of trackway 2082.

2082 - Track; Post Medieval; 427894,375328;427667,375489;Terraced trackway cut into the natural slope at a width of 1.8m. Appears to be a continuation of trackway 2081. Cut by later quarry 2084.

2083 - Hollow Way; Post Medieval; 427845,375395;427839,375378;Series of braided routes, probably a continuation of hollow ways 2104 and 2105.

2084 - Quarry; Post Medieval; 427826,375431;1m in depth this feature appears to cut through and therefore post-dates the trackway immediately to the south-west 2082.

- 2085 - Drain; Post Medieval; 427793,375445;427764,375452;0.6m wide and 0.2m in depth.
- 2086 - Hollow Way; Post Medieval; 427829,375354;427832,375374;Braided and narrow, some may be heavy vehicle tracks.
- 2087 - Drain; Post Medieval; 427762,375468;427763,375450;Drainage sumps culverted under trackway 2082.
- 2089 - Drain/Possible Hollow Way; Post Medieval; 427764,375477;427732,375463;Possible hollow way, surface water in this culverted under trackway 2082 in a stone-lined drain.
- 2090 - Scarp; Modern; 427670,375494;427665,375501;Associated with construction of pumping compound to west.
- 2092 - Hollow Way; Post Medieval; 427774,375500;427775,375471;Depth 0.2m.
- 2093 - Possible Linear Clearance; Bronze Age; 427794,375478;427796,375472; Area of medium-sized stones with a large stone at either end, 0.3m in height, 6.0m in length and 0.9m wide at the centre widening to c.1.7m at either end. Alternatively a natural outcrop.
- 2094 - Possible Cairn; Bronze Age; 427792,375476;Slight consolidation of stones 1.4m x 2.5m, 0.1m in height (upslope) and 0.4m in height (downslope). Possibly natural.
- 2096 - Cairn or Pile of Stones; Bronze Age or Post Medieval; 427821,375496; Four-five large stones exposed, may be associated with clearance or alternatively with quarrying immediately downslope.
- 2097 - Boulder Scarp; Bronze Age; 427831,375495;427837,375489;Height 0.3m.
- 2098 - Possible Boulder Scarp; Bronze Age; 427841,375475;427844,375478;Height 0.3m with some large boulders and medium-sized stones. Alternatively a natural outcrop.
- 2100 - Boulder Scarp; Bronze Age; 427830,375487;427829,375494;Height 0.3m.
- 2101 - Hollow Way; Post Medieval; 427837,375484;427873,375500;Braided hollow way c.0.3m in depth.
- 2103 - Hollow Way; Post Medieval; 427814,375495;427807,375483;Depth 0.2m.
- 2106 - Hollow Way; Post Medieval; 427707,375411;427703,375409;Two narrow ways c.0.3m in depth cut across the natural riverine scarp.
- 2107 - Hollow Way; Post Medieval; 427705,375389;427701,375390;Braided hollow ways cut across the natural riverine scarp.
- 2108 - Hollow Way; Post Medieval; 427718,375312;427713,375300;Series of braided hollow ways, c.0.2m in depth, above the natural riverine scarp.
- 2109 - Hollow Way; Post Medieval; 427723,375259;427716,375267;Truncated by riverine erosion scarp.
- 2110 - Hollow Way; Post Medieval; 427736,375247;427718,375248;Truncated by riverine erosion scarp. Cuts through natural mound 2111.
- 2111 - Mound; Natural; 427734,375243;Earth mound 8.1m x 3.5m, some stone evident at west

end, probably natural.

2112 - Hollow Way; Post Medieval; 427748,375266;427739,375268;narrow braided paths.

2113 - Hollow Way; Post Medieval; 427740,375334;427731,375327;Braided where feature crosses a natural scarp.

2114 - Hollow Way; Post Medieval; 427774,375346;427750,375341;Depth 0.3m.

2186 - Mound; Natural; 427918,375220;Earthen mound 1.0m in height (downslope), probably natural. Cut by foxhole 2078.

2240 - STET; Post Medieval; 427998,375215;Single large flat stone with six shallow slits (feather holes), each measuring 0.06 x 0.01m, carved in an L-shape on the uppermost flat surface. Stone splitting.

2242 - Quarries; Post Medieval; 427983,375240;Area of small dayworking hollows, mostly small but including 2243.

2243 - Quarry; Post Medieval; 427974,375246;0.4m in depth.

2245 - Pit; Modern; 427990,375264;Foxhole 0.8m square and 0.1m in depth, associated with military activity c.1939-45.

2246 - Disturbance; Modern; 427993,375261;Shallow sub-circular depression 4.4m maximum diameter and 0.2m in depth, possibly a mortar crater associated with military activity c.1939-45.

2247 - Disturbance; Modern; 427995,375251;Shallow sub-circular depression 3.0m maximum diameter and 0.2m in depth, possibly a mortar crater associated with military activity c.1939-45.

2248 - Pit; Modern; 427945,375265;Rectangular dug-out 1.9 x 2.1m and 0.5m in depth (to upslope), associated with military activity c.1939-45.

2249 - Pit; Modern; 427924,375289;Rectangular dug-out 1.2 x 3.7m and 0.5m in depth (to upslope), associated with military activity c.1939-45.

2250 - Pits; Modern; 427906,375324;Four rectangular hollows terraced into the natural slope to form a series of platforms all 0.1-0.2m in depth (to upslope) and measuring 1.2 x 4.3m, 1.8 x 3.4m, 1.8 x 2.2m, and 1.2 x 2.5m respectively, probably associated with military activity c.1939-45.

2251 - Cairn; Bronze Age; 427942,375352;Mound of earth and medium-sized stone with a maximum diameter of 7.4m. South-west quadrant is 0.7m in height. The east half of feature is only 0.5m in height, which together with disturbed appearance of the north-west end suggest that the cairn has been robbed.

2252 - Possible Lynchet; Bronze Age; 427927,375344;427928,375336;Lynchet-type scarp 0.3m in height.

2253 - Possible Lynchet; Bronze Age; 427941,375327;427936,375332;Crescential scarp 0.2m in height and c.9m in length defines a circular level area in the natural slope. Despite its appearance it is doubtful whether this represents a house site.

2254 - Quarry; Post Medieval; 427966,375310;Steep sided stony quarry pit 1.5m in depth. There is an area of associated earthen spoil to the south 0.1-0.3m in height.

2255 - Linear Clearance; Bronze Age; 427968,375329,427960,375342; Bank of large stones 0.5m in height and c.16m in length, some stones are set on end at a bulbous south terminal. There are terrace-like areas above and below the bank.

2256 - Cairn; Bronze Age; 427989,375286; Cairn of large stones 5.1m in diameter and 0.7m in height, heather-covered.

2257 - Cairn; Bronze Age; 427945,375384; Disturbed cairn 1.5m in diameter and 0.2m in height, laid on natural slope.

2258 - Paired Pits; Modern; 427989,375376; 0.5m square, associated with military activity c.1939-45.

2259 - Slit Trench; Modern; 427980,375475; Chevron shaped trench 0.4m wide and largely infilled.

2260 - Pit; Modern; 427967,375491; 1.7m x 2.1m and 0.1-0.2m in depth, associated with military activity c.1939-45.

2261 - Slit Trench; Modern; 427978,375496; 0.3m x 1.8m and 0.1m in depth, associated with military activity c.1939-45.

2262 - Linear Clearance; Bronze Age; 427929,375431,427923,375432; U-shaped linear bank of earth and stones, 7.1m across the ends, 0.2m in height and artificial in appearance. Possibly represents clearance stone rather than an enclosure and may be associated with linear clearance 2263.

2263 - Linear Clearance; Bronze Age; 427930,375434,427928,375434; Small linear area of earth and medium-sized stone, 1.0m x 2.8m and 0.2m in height. Possibly associated with 2262.

2264 - Cairn; Bronze Age; 427915,375418; Cairn of large and medium-sized stones, maximum 3.2m in diameter and 0.4m in height. Southern half of the cairn has been robbed.

2265 - Drain; Post Medieval; 427867,375439,427861,375438; Stone-lined culvert under road.

2266 - Quarry; Post Medieval; 427876,375439; 1.0m in depth on east side, 0.4m in depth on west side, cut by drainage ditch 2267.

2267 - Drain; Post Medieval; 427869,375454,427872,375434; Drainage ditches 0.5m in depth, post-date and cut through quarry 2266.

2268 - Pit; Modern; 427903,375370; 0.7m in depth cut into quarry, with spoil to south-west 0.2m in height, associated with military activity c.1939-45.

2269 - Possible Cairn; Bronze Age; 427918,375373; Loose U-shaped pile of earth and medium-sized stones with small quarried hole 0.3m in depth in eastern quadrant, possibly the remains of a quarried cairn.

2270 - Possible Lynchet; Bronze Age; 427911,375388,427903,375413; Possible lynchet 0.3m in height and c.26m in length, could be a natural feature.

2271 - Cairn; Bronze Age; 427625,375325; Cairn of medium-sized stones, 0.2m in height, on edge of stony ground.

2272 - Cairn; Bronze Age; 427625,375303; Cairn of medium-sized stones, 0.3m in height, on

edge of stony ground.

2273 - Linear Clearance; Bronze Age; 427623,375315;427621,375317;Area of small stones, 0.3m in height, terminating at an earthfast boulder.

2274 - Linear Clearance; Bronze Age; 427619,375318;427615,375318;Area of medium-sized stones, 0.3m in height, on edge of stony ground.

2275 - Clearance Stone; Bronze Age; 427613,375315;Concentration of medium-sized stones on edge of stony ground.

2276 - Linear Clearance; Bronze Age; 427607,375306;427604,375310;Area of medium-sized clearance stone, 0.3m in height, on edge of stony ground.

2277 - Clearance Stone; Bronze Age; 427603,375313;Group of small stones.

2278 - Linear Clearance; Bronze Age; 427641,375311;427643,375319;Regular grass-covered bank of medium-sized stones, 0.2-0.3m in height.

2279 - Linear Clearance; Bronze Age; 427651,375296;427645,375304;Irregular bank of medium-sized stones, 0.2-0.3m in height, terminating at south end in two earthfast boulders.

2280 - Probable Cairn; Bronze Age; 427609,375292;Of large and medium-sized stones, 0.2-0.3m in height.

2281 - Cairn; Bronze Age; 427615,375287;Of large and medium-sized stones, 0.2-0.3m in height.

2282 - Boulder Scarp; Bronze Age; 427619,375294;427620,375300;Scarp with large stones, 0.3m in height, at cultivation edge.

2345 - Pit; Modern; 427674,375011;1.4m x 1.1m and 0.3m in depth. Associated with military activity c.1939-45.

2697 - Linear Clearance or Sheep Lea; Bronze Age or Post Medieval; 427992,375470;428004,375472;Low stone bank, well vegetated and looking much like linear clearance but given proximity with wall (2359 sheet 16) and hints of possible alignments or coursing, it may simply be the collapsed arm of a sheep lea.

2698 - Stone Bank; Post Medieval; 427877,375119;427871,375115;Loosely built stone retaining-bank alongside drain.

2699 - Lynchet; Bronze Age; 427523,375459;427524,375464;0.3m in height, cut by hollow way.

2717 - Clearance Stone; Bronze Age; 427965,375292;427963,375289;Area of clearance stone 2.5 x 4.0m.

2752 - Hollow Way; Post Medieval; 427705,375363;427702,375367;Short section of well-defined hollow way cuts into steep natural slope.

2753 - Hollow Way; Post Medieval; 427733,375341;427727,375344;Short section of well-defined hollow way cuts into steep natural slope.

2754 - Hollow Way; Post Medieval; 427738,375320;427731,375318;Short section of well-defined hollow way cuts into steep natural slope.

2755 - Hollow Way; Post Medieval; 427708,375214;427702,375201;Hollow way visible cut into the crest of the natural slope.

2756 - Hollow Way; Post Medieval; 427773,375156;427769,375154;Very short section of hollow way cut into crest of the natural slope.

2757 - Hollow Way; Post Medieval; 427819,375401;427815,375393;Short section of slight hollow way visible on the natural slope.

2773 - Hollow Way; Post Medieval; 427505,375450;427531,375460;~.30m length of hollow way. May continue as a track further west (1073).

2774 - Quarry; Post Medieval; 427845,375479;c.8m x 4m - possibly for stone extraction.

2792 - Possible Cairn; Bronze Age; 427998,375469;Well vegetated stone cairn, appearing to be overlain by sheep lea wall (2359 sheet 16), but the possibility that it is a collapsed structure associated with the lea cannot be discounted.

2793; Quarry; Post Medieval; 427650,375433;Small quarry cut into hillslope. Possibly associated with the construction of hollow way 2048.

2794; Quarry; Post Medieval; 427510,375353;Small quarry cut into hillslope, probably for stone.

2806; Pump; Modern; 427665,375496;Disused water pump surrounded by dilapidated wire fence.

Sheet 6

1541 - Dressed Stone; Post Medieval; 426394,375867;Gritstone slab 0.4 x 1.3m and 0.9m high, erected for working, tooling marks on north-west face.

1545 - Pile of Stones; STET; 426346,375945;Seven medium-sized stones grouped together and partially turf-covered, 1.0m in diameter and 0.2m in height. STET.

1546 - Slit Trench; Modern; 426345,375953;2.6 x 0.7m x 0.2m, associated with military activity c.1939-45.

1547 - Slit Trench; Modern; 426341,375956;2.2 x 0.6m x 0.2m, associated with military activity c.1939-45.

1548 - Pit; Modern; 426341,375951;1.4 x 1.0m x 0.2m, associated with military activity c.1939-45.

1549 - Pit; Modern; 426361,375931;Small pit or sump in bottom of hollow way with upcast material (possibly a dam) to north, blocking the hollow way, possibly associated with military activity c.1939-45.

1550 - Stone; Natural; 426422,375917;Large stone block 0.4 x 0.4m and 0.6m in height, erected perpendicular to bedding plain. May be fortuitous.

1551 - Pile of Stones; Post Medieval; 426436,375917;Heather-covered mound of medium-sized stone 3.2 x 1.4m and 0.4m in height, could just be residue from dayworking.

1553 - Probable Boulder Scarp; Bronze Age; 426407,375828;426422,375830;0.3m in height, defining edge of an area of cultivated ground.

1554 - Cairn; Bronze Age; 426381,375841;4.4 x 2.0m and 0.2m in height upslope and 0.6m in height downslope, of medium-sized stone piled on earthfast slab, on the edge of a cultivated area.

2494 - Boulder Scarp; Bronze Age; 426492,375759;426502,375761;0.3m in height.

2496 - Cairn; Bronze Age; 426346,375757;2.0 x 4.3m and 0.3m in height, of both large and small stones.

2497 - Clearance Stone; Bronze Age; 426346,375765;1.2 x 9.4m and 0.1m in height.

2498 - Cairn; Bronze Age; 426347,375767;1.9 x 3.5m and 0.4m in height. Masked.

2499 - Linear Clearance; Bronze Age; 426344,375782;426348,375773;1.6m x c.10.5m and 0.3m in height, of medium-sized stone.

2500 - Lynchet; Bronze Age; 426393,375829;426404,375826;0.2m in height.

2501 - Cairn; Bronze Age; 426405,375820;2.0m in diameter and 0.5m in height. Masked.

2502 - Cairn; Bronze Age; 426414,375809;3.4m in diameter and 0.5m in height, of small and medium-sized stones.

2503 - Cairn; Bronze Age; 426422,375801;1.0 x 3.4m and 0.2m in height. Masked.

2504 - Cairn; Bronze Age; 426436,375786;2.2 x 3.2m and 0.5m in height, of small and medium-sized stones piled next to an earthfast boulder. Partially masked.

2505 - Paired Pits; Modern; 426399,375746;Two small pits each 0.6m square and 0.2m in depth. Associated with military activity c.1939-45.

2506 - Paired Pits; Modern; 426408,375739;Two small pits each 0.6m square and 0.2m in depth. Associated with military activity c.1939-45.

2507 - Paired Pits; Modern; 426407,375739;Two small pits each 0.6m square and 0.3m in depth. Associated with military activity c.1939-45.

2508 - Pit; Modern; 426408,375734;0.6m square and 0.2m in depth. Associated with military activity c.1939-45.

2509 - Pit; Modern; 426410,375735;0.7m square and 0.2m in depth. Associated with military activity c.1939-45.

2510 - Pit; Modern; 426387,375718;0.6 x 1.8m and 0.3m in depth. Associated with military activity c.1939-45.

2511 - Pile of Stones; Post Medieval; 426407,375677;1.6 x 2.6m and 0.3m in height, comprising small and medium-sized stones piled around two earthfast boulders. Probable clearance from adjacent hollow way (2761).

2512 - Slit Trenches; Modern; 426490,375619;Shallow L-shaped trench maximum 1.5 x 0.7m cut into adjacent Bronze Age field bank 2526, associated with military activity c.1939-45.

2513 - Bullet Scars; Modern; 426421,375830;Single bullet scarred rock associated with military activity c.1939-45.

2514 - Cairn; Bronze Age; 426479,375867;3.5 x 2.6m and maximum 0.3m in height, of large and medium-sized stones. Constructed around west side of earthfast boulder.

2515 - Clearance Stone; Bronze Age; 426473,375864;6.8 x 3.3m and 0.1-0.2m in height.

2516 - Possible Cairn; Bronze Age; 426473,375876;Incipient feature 3.8 x 2.4m and 0.2-0.3m in height, comprising large and medium-sized stones piled to the west of an earthfast stone slab. Some evidence of an incomplete stone kerb.

2517 - Cultivation Edge; Bronze Age; 426489,375896;426474,375886;Margin defining the edge of an area of cleared ground.

2518 - Cairn; Bronze Age; 426481,375875;Grass and heather-covered cairn of medium-sized stone 2.7 x 5.1m and 0.3m in height.

2519 - Cultivation Edge; Bronze Age; 426479,375868;426474,375883;Margin defining the edge of an area of cleared ground.

2520 - Cairn; Bronze Age; 426488,375883;Large cairn of medium-sized stone, maximum 5.0m in diameter and 0.2-0.3m in height.

2521 - Boulder Scarp; Bronze Age; 426473,375757;426487,375757;0.3m in height.

2522 - Hollow Way; Post Medieval; 426471,375796;426440,375765;0.2m in depth.

2523 - Hollow Way; Post Medieval; 426456,375794;426447,375779;0.2m in depth.

2524 - Linear Clearance; Bronze Age; 426451,375767;2.2 x 7.3m and 0.5m in height, situated on edge of outcrop of natural boulders.

2525 - Linear Clearance; Bronze Age; 426456,375759;426463,375758;Area of clearance 1.1 x 7.6m on top of exposed natural boulders.

2526 - Earthen Bank; Bronze Age; 426490,375617;426498,375630;c.16m in length, maximum 3.7m wide and 0.3m in height, overlain by earthen bank (2452) to south east.

2527 - Lynchet; Bronze Age; 426462,375637;426470,375624;Pronounced lynchet maximum 0.5m in height with some dumped stone.

2528 - Slit Trenches; Modern; 426452,375637;Two adjacent trenches each measuring 1.7 x 0.6m and 0.2m in depth. Associated with military activity c.1939-45.

2529 - Lynchet; Bronze Age; 426435,375640;426447,375636;0.3m in height with a cluster of stone at the east end.

2530 - Quarry; Post Medieval; 426454,375588;Stone quarry, post-dates adjacent hollow ways.

2738 - Hollow Way; Post Medieval; 426484,375614;426459,375584;Well-defined route on a similar alignment to earthen bank 2526 to the north-east.

2739 - Probable Hollow Way; Post Medieval; 426307,375904;426308,375865;Slight feature parallel to modern footpath, out-lier to main group of hollow ways.

2740 - Boulder Scarp; Bronze Age; 426452,375763;426449,375769;0.3m in height.

2741 - Boulder Scarp; Bronze Age; 426469,375757;426455,375759;0.3m in height.

2742 - Clearance Stone; Bronze Age; 426474,375887;426474,375883;Distinct sub-rectangular area of cleared stones c.2.5 x 4.0m.

2761 - Hollow Way; Post Medieval; 426400,375665;426435,376000;Band of braided hollow ways, some deeply channelled.

2796 - Hollow Way; Post Medieval; 426340,375865;426332,375957;Multiple narrow and shallow hollow way routes.

Sheet 7

1501 - Bell Pit; Post Medieval; 426998,375515;3.7m in diameter and 0.9m in depth with low crescent-shaped spoil to south-east. A military pit 1502 has been cut into the bottom giving an overall depth of 1.5m.

1502 - Pit; Modern; 426998,375516;Sub-rectangular pit 1.4 x 1.2m maximum and 0.6m in depth cut into the bottom of bell pit 1501. Probably associated with military activity c.1939-45.

2404 - Linear Clearance; Bronze Age; 426848,375799;426842,375793;Irregular curving stone bank c.10m in length, 1.0-2.8m wide and 0.3m in height. South end abuts lynchet 2428.

2405 - Cairn; Bronze Age; 426835,375785;1.7 x 2.3m and 0.3m in height.

2406 - Stony Lynchet; Bronze Age; 426848,375767;426849,375774;0.3m in height.

2407 - Linear Clearance; Bronze Age; 426852,375763;426848,375766;6.0 x 1.1m and 0.4m in height.

2408 - Linear Clearance; Bronze Age; 426849,375775;426846,375783;1.9 x 9.7m and 0.4m in height, masked. North end abuts lynchet 2429.

2409 - Stony Lynchet; Bronze Age; 426831,375754;426835,375757;0.4m in height.

2410 - Cairn; Bronze Age; 426826,375739;1.7 x 3.2m and 0.2m in height.

2411 - Bell Pit; Post Medieval; 426905,375613;Circular pit 3.4m in diameter and 0.7m in depth, with spoil to east.

2412 - Pit; Modern; 426942,375547;0.9m square with stone upcast to north side, associated with military activity c.1939-45.

2413 - Possible Hollow Way; Post Medieval; 426986,375543;426967,375526;Possible slight hollow way - could be a natural feature.

2414 - Possible Causeway; Post Medieval; 426899,375515;426896,375496;Slight bank at base of hollow way c.19m in length and 6.5m wide - could be a built causeway or possibly material washed from the hollow way above.

2415 - Mound; Post Medieval; 426875,375507;426871,375500;Fan of deposited material c.11 x 7m, washed from hollow way above.

2416 - Possible Hollow Way; Post Medieval; 426862,375519;426851,375527;Possible hollow way but with a sharply defined north-west end.

2419 - Possible Cairn; Bronze Age; 426758,375717;Maximum 2.9m in diameter and 0.2m in height. Masked.

2420 - Possible Cairn; Bronze Age; 426817,375735;0.7 x 2.1m and 0.2m in height. Masked.

2421 - Linear Clearance; Bronze Age; 426824,375768,426832,375767;Irregular stone bank c.10m in length, 0.9-3.2m in width and 0.4m in height, masked. Defines possible house site 2422.

2422 - Possible House Site; Bronze Age; 426829,375767;Defined by curving linear clearance 2421, with a diameter of c. 6-8m.

2423 - Linear Clearance; Bronze Age; 426834,375762,426833,375765;3.5m in length, 2.4m wide and 0.3m in height. Masked.

2424 - Linear Clearance; Bronze Age; 426812,375781,426830,375780;18.5m in length, 1.2-3.9m wide and 0.4m in height. Masked.

2425 - Cairn; Bronze Age; 426733,375725;Large and medium-sized stones around an earthfast boulder, maximum 2.2 x 4.0m and 0.2m in height.

2426 - Cairn; Bronze Age; 426810,375801;Small cairn 1.0 x 1.4m and 0.3m in height. Masked.

2427 - Linear Clearance; Bronze Age; 426854,375803;426851,375801;1.0 x 3.7m and 0.1m in height. Masked.

2428 - Lynchet; Bronze Age; 426843,375788;426842,375792;0.1m in height. North end abuts linear clearance 2404.

2429 - Lynchet; Bronze Age; 426844,375787;426846,375784;0.1m in height. South end abuts linear clearance 2408.

2430 - Cairn; Bronze Age; 426858,375759;Maximum 3.4m in diameter, 0.2m in height. Masked.

2431 - Cairn or Burial Cairn; Bronze Age; 426770,375949; Small cairn of large and medium-sized stone c.0.8 x 3.5m and 0.4m in height, not much soil content. Looks to have been extensively disturbed. Contains single cup-marked stone (2433).

2432 - Bullet Scars; Modern; 426740,375842;Associated with military activity c.1939-45.

2433 - Cup and Ring Carving; Bronze Age; 426771,375947;Cup-marked stone on crest of cairn 2431, single cup at centre of visible face measuring 0.05m in diameter and 0.04m in depth.

2434 - Cairn; Bronze Age; 426836,375758;Sub-circular cairn maximum 3.4m in diameter.

2435 - Cairn; Bronze Age; 426682,375705;Maximum 3.3m in diameter and 0.3m in height, of medium-sized stone.

2436 - Cairn; Bronze Age; 426666,375708;1.6 x 3.7m and 0.2m in height, of large and medium-sized stone.

2437 - Cairn; Bronze Age; 426673,375708;Maximum 1.9m in diameter and 0.2m in height. Masked.

2438 - Cairn; Bronze Age; 426648,375711;Maximum 3.0m in diameter and 0.3m in height, of large and medium-sized stone.

- 2439 - Cairn; Bronze Age; 426640,375716;1.8 x maximum 2.8m and 0.2m in height, of large and medium-sized stone.
- 2440 - Cairn; Bronze Age; 426624,375716;2.0 x 3.0m and 0.5m in height, constructed around an earthfast boulder, masked.
- 2441 - Lynchet; Bronze Age; 426618,375713;426623,375715;0.2m in height.
- 2442 - Cairn; Bronze Age; 426614,375718;1.9m in diameter and 0.3m in height. Masked.
- 2443 - Cairn; Bronze Age; 426598,375701;2.1 x 3.2m and 0.5m in height. Masked.
- 2444 - Linear Clearance; Bronze Age; 426632,375675;426645,375671;13m in length, 1.0-3.1m wide and 0.5m in height. Masked.
- 2445 - Possible Lynchet; Bronze Age; 426652,375679;426647,375672;Indistinct feature only 0.1m in height.
- 2446 - Lynchet; Bronze Age; 426648,375668;426649,375670;0.3m in height.
- 2447 - Linear Clearance; Bronze Age; 426662,375663;426649,375670;c.15.6m in length, maximum 3.5m wide and 0.5m in height, comprising both small and much larger stones.
- 2448 - Hollow Way; Post Medieval; 426658,375643;426512,375612;0.2m in depth. Extensive braided route.
- 2449 - Hollow Way; Post Medieval; 426667,375628;426545,375418;0.2m in depth.
- 2451 - Cairn; Bronze Age; 426604,375618;1.2 x 2.1m and 0.2m in height. Masked.
- 2452 - Earthen Bank/Lynchet; Bronze Age; 426599,375644;426498,375633;c.105m in length, 2m wide and 0.2m in height with some limited stone content. Across the natural slope this feature is visible as a lynchet partly cut by hollow way 2448.
- 2453 - Cairn; Bronze Age; 426600,375636;1.2 x 3.3m and 0.3m in height, incorporated within earthen bank 2452.
- 2454 - Linear Clearance; Bronze Age; 426571,375625;1.8 x 15.0m and 0.4m in height, incorporated within earthen bank 2452.
- 2455 - Earthen Bank; Bronze Age; 426507,375592;426606,375603;c.100m in length, 2.5m wide and 0.1m in height.
- 2456 - Animal Disturbance; Natural; 426608,375605;Area of disturbance caused by rabbit burrowing.
- 2457 - Earthen Bank; Bronze Age; 426591,375574;426617,375561;c.30m in length, 3.0m wide and 0.2m in height. Visible beyond either end of linear clearance 2458.
- 2458 - Linear Clearance; Bronze Age; 426609,375564;426596,375573;Irregular stone bank c.15m in length, 3.8m wide and 0.3m in height.
- 2459 - Cairn; Bronze Age; 426634,375594;2.7 x 5.0m and 0.3m in height. Masked.
- 2460 - Earthen Bank/Lynchet; Bronze Age; 426616,375594;426645,375595;c.25m in length, 3.0m

wide and 0.2m in height. Across the natural slope this feature is visible as a lynchet c.7m in length.

2461 - Animal Disturbance; Natural; 426649,375597;Area of disturbance caused by rabbit burrowing.

2462 - Animal Disturbance; Natural; 426693,375551;Area of disturbance caused by rabbit burrowing.

2463 - Earthen Bank; Bronze Age; 426680,375528;426672,375524;2.5 x 8.0m and 0.2m in height.

2464 - Lynchet; Bronze Age; 426681,375523;426701,375511;0.3m in height. Area of disturbance caused by rabbit burrowing at west end.

2465 - Cairn; Bronze Age; 426642,375513;Cairn of large and medium-sized stone, maximum 3.0m in diameter and 0.5m in height, masked. Hollow way divides around cairn.

2467 - Cairn; Bronze Age; 426634,375529;1.1 x 2.7m and 0.2-0.3m in height, masked.

2469 - Hollow Way; Post Medieval; 426669,375524;426550,375421;0.1-0.2m in depth, divides around cairn 2465.

2470 - Animal Disturbance; Natural; 426591,375556;Area of disturbance caused by rabbit burrowing.

2471 - Cairn; Bronze Age; 426591,375527;3.3m in diameter and 0.4m in height. Masked;.

2472 - Cairn; Bronze Age; 426571,375542;3.1m in diameter and 0.5m in height. Some mixed stone visible, recently disturbed at centre.

2473 - Animal Disturbance; Natural; 426553,375510;Area of disturbance c.10m in diameter caused by rabbit burrowing.

2474 - Animal Disturbance; Natural; 426551,375521;Area of disturbance c.4.5m in diameter caused by rabbit burrowing.

2475 - Linear Clearance; Bronze Age; 426521,375535;426529,375530;2.5 x 9.0m and 0.3m in height. Masked.

2476 - Earthen Bank; Bronze Age; 426534,375521;426529,375530;10m in length, 2.2m wide and 0.2m in height.

2477 - Linear Clearance; Bronze Age; 426533,375512;426534,375521;2.0 x 8.7m and 0.3m in height. Masked.

2478 - Slit Trench; Modern; 426518,375514;0.7 x 1.2m and 0.3m in depth, associated with military activity c.1939-45.

2479 - Slit Trench; Modern; 426534,375506;0.7 x 1.8m and 0.3m in depth, associated with military activity c.1939-45.

2480 - Slit Trench; Modern; 426523,375506;0.6 x 0.8m and 0.5m in depth, associated with military activity c.1939-45.

2481 - Probable Lynchet; Bronze Age; 426510,375555;426519,375537;0.3m in height.

- 2482 - Possible Clearance Stone; Bronze Age; 426506,375620; 2.0 x 6.0m and 0.3m in height.
- 2483 - Pit; Modern; 426503,375625; 0.6m square and 0.2m in depth, associated with military activity c.1939-45.
- 2484 - Slit Trench; Modern; 426503,375595; 0.6 x 1.3m and 0.2m in depth, associated with military activity c.1939-45.
- 2485 - Slit Trench; Modern; 426534,375592; 0.5 x 1.7m and 0.2m in depth, associated with military activity c.1939-45.
- 2486 - Slit Trench; Modern; 426555,375592; 0.5 x 1.7m and 0.2m in depth, associated with military activity c.1939-45.
- 2487 - Pit; Modern; 426568,375572; Chevron-shaped pit, overall length 4.0m, 0.6m wide and 0.5m in depth, associated with military activity c.1939-45.
- 2488 - Slit Trench; Modern; 426520,375607; 0.6 x 1.9m and 0.2m in depth, associated with military activity c.1939-45.
- 2489 - Earthen Bank; Bronze Age; 426516,375697; 426512,375681; 16.5m x maximum 1.8m and 0.3m in height. Some stone visible but largely masked.
- 2490 - Cairn; Bronze Age; 426584,375689; 2.4 x 3.3m and 0.4m in height, of medium-sized stone.
- 2491 - Cairn; Bronze Age; 426566,375707; Maximum 2.6m in diameter and 0.5m in height, constructed around an earthfast boulder. Masked.
- 2492 - Probable Cairn; Bronze Age; 426561,375709; Maximum 2.4m in diameter and 0.5m in height, constructed around an earthfast boulder. Masked.
- 2493 - Cairn; Bronze Age; 426551,375714; Maximum 2.5m in diameter and 0.5m in height.
- 2495 - Pile of Stones; Post Medieval; 426532,375756; c.1.0 x 2.0m, of medium-sized stones cleared from adjacent hollow way.
- 2682 - Cairn; Bronze Age; 426560,375594; 2.4m in diameter and 0.4m in height, mostly masked.
- 2683 - Earthen Bank; Bronze Age; 426555,375524; 426590,375526; 35m in length, 2.0m wide and 0.3-0.4m in height.
- 2684 - Cairn; Bronze Age; 426580,375523; 2.7 x 6.0m and 0.6m in height.
- 2685 - Cairn; Bronze Age; 426672,375658; 1.8 x 2.3m and 0.5m in height. Large stones against an earthfast boulder.
- 2687 - Probable Cairn; Bronze Age; 426741,375511; 2.0m in diameter and 0.3m in height, mostly masked.
- 2688 - Linear Clearance; Bronze Age; 426774,375538; 426771,375532; 2.4 x 7.0m and 0.3m in height, mostly masked.
- 2729 - Hollow Way; Post Medieval; 426565,375793; 426555,375772; Isolated section of hollow way.

2730 - Hollow Way; Post Medieval; 426533,375772;426509,375694;Isolated section of hollow way

Sheet 8

412 - Possible Gate; Bronze Age; 427319,375506;This poorly defined gap in earthen bank 411 is c.1.5m wide and may possibly be an original gateway.

413 - Earthen Bank; Bronze Age; 427264,375527;427303,375512;2.0m in length, 1.5-2.0m wide and 0.2m high.

414 - Probable Earthen Mound; Bronze Age; 427268,375553;5.0m in length, 2.0m wide and 0.2m high. This earthen feature's rough alignment with earthen banks 338 and 416 suggest it is prehistoric.

415 - Cairn; Bronze Age; 427295,375558;3.5 x 6.0m and 0.5m in height, of medium-sized stone.

416 - Possible Earthen Bank; Bronze Age; 427298,375559;427315,375562;18.0m in length and 2.0m wide. It has little height and is only seen as a poorly defined vegetation change.

417 - Cairn; Bronze Age; 427318,375563;4.5 x 5.0m and 0.3m in height, masked by turf and soil.

418 - Earthen Bank; Bronze Age; 427319,375572;427338,375603;39.0m in length, 2.0m wide and 0.2m high.

419 - Cairn; Bronze Age; 427328,375548;3.5 x 5.0m and 0.3m in height, of medium-sized stone.

420 - Stone Bank; Bronze Age; 427313,375537;427375,375571;75.0m in length, 1.5-2.5m wide and 0.4m high, of medium-sized stone. Cut in two places by hollow ways.

421 - Cairn; Bronze Age; 427336,375529;3.0m in diameter and 0.3m in height, masked by turf and soil.

429 - Cairn; Bronze Age; 427350,375510;3.0 x 3.5m and 0.3m in height, masked by turf and soil.

430 - Cairn; Bronze Age; 427367,375516;4.0 x 4.5m and 0.4m in height, some medium-sized stone visible.

431 - Cairn; Bronze Age; 427376,375507;2.5 x 3.0m and 0.2m in height (upslope), and 0.3m (downslope), masked by turf and soil.

432 - Cairn; Bronze Age; 427393,375528;3.5 x 4.0m and 0.4m in height (upslope), and 0.5m (downslope), masked by turf and soil.

433 - Cairn; Bronze Age; 427434,375502;2.5m in diameter and 0.2m in height (upslope), and 0.3m (downslope), masked by turf and soil.

434 - Cairn; Bronze Age; 427443,375506;2.5 x 3.0m and 0.3m in height, masked by turf and soil.

474 - Linear Clearance; Bronze Age; 427294,375638;427296,375634;5.0 x 2.0m and 0.3m high, masked by turf and soil.

475 - Earthen Bank; Bronze Age; 427304,375627;427337,375604;3.0m in length, 2.0m wide and up to 0.2m high.

- 476 - Cairn; Bronze Age; 427315,375618;4.0 x 5.5m and 0.4m in height, masked by turf and soil.
- 477 - Cairn; Bronze Age; 427342,375594;2.0m in diameter, masked by turf and soil.
- 478 - Cairn; Bronze Age; 427341,375605;2.5 x 4.5m and 0.3m in height, of medium-sized stone.
- 479 - Pit; Modern; 427341,375604;Associated with military activity c.1939-45.
- 480 - Linear Clearance; Bronze Age; 427343,375604;427348,375606;Curved feature 5.0 x 1.5m and 0.2m high, defining possible house site 630.
- 481 - Cairn; Bronze Age; 427349,375607;4.0 x 7.0m and 0.5m in height, masked by turf and soil.
- 482 - Linear Clearance; Bronze Age; 427355,375598;427350,375609;13.0 x 2.5-3.0m and 0.4m high, of medium-sized stone.
- 483 - Cairn; Bronze Age; 427355,375594;2.0 x 3.5m and 0.3m in height, of medium-sized stone. There is a low orthostat at the south-east side.
- 484 - Linear Clearance; Bronze Age; 427356,375592;427357,375591;2.5 x 1.0m and 0.1m high, masked by turf and soil.
- 485 - Cairn; Bronze Age; 427359,375588;4.0 x 7.0m and 0.4m in height, of medium-sized stone.
- 486 - Linear Clearance; Bronze Age; 427361,375585;427362,375584;2.0 x 2.0m and 0.1m high, masked by turf and soil. One end appears to be truncated by hollow way 570.
- 488 - Cairn; Bronze Age; 427366,375606;3.5 x 5.5m and 0.4m in height, masked by turf and soil. This feature increases in height towards the north-east end.
- 489 - Cairn; Bronze Age; 427374,375611;Amorphous feature 5.0 x 6.5m and 0.5m in height.
- 490 - Earthen Bank; Bronze Age; 427446,375632;427385,375613;3.0m in length, 2.0m wide and up to 0.3m high. The west end is cut by hollow way 570 and may well have originally continued up to cairn 489. The eastern end is bulbous and mound-like in plan.
- 491 - Cairn; Bronze Age; 427396,375619;2.5 x 3.0m and 0.3m in height (upslope), and 0.5m (downslope), masked by turf and soil.
- 492 - Lynchet; Bronze Age; 427368,375617;427372,375613;5.5m in length and 0.3m high. One end is truncated by hollow way 570.
- 493 - Probable Earthen Bank; Bronze Age; 427365,375629;427366,375620;10.0m in length, 1.5m wide and 0.1m high, and is cut by hollow way 570 at both ends. The possibility that this feature is natural cannot be discounted.
- 494 - Earthen Bank; Bronze Age; 427369,375627;427382,375632;Poorly-defined feature 14.0m in length, 2.0m wide and 0.2m high. Both ends are truncated by hollow way 570.
- 495 - Earthen Bank; Bronze Age; 427385,375627;427387,375635;8.0m in length, 2.0m wide and 0.3m high. To the north this feature terminates at linear clearance 496, while to the south it may be truncated by hollow way 570.
- 496 - Linear Clearance; Bronze Age; 427385,375635;427390,375638;5.5 x 2.5m and 0.3m high to the west and 0.2m to the east.

- 497 - Earthen Bank; Bronze Age; 427442,375651;427398,375641;7.0m in length, 2.0m wide and up to 0.2m high. East end is lynchet-like in form.
- 498 - Cairn; Bronze Age; 427396,375640;3.5 x 4.5m and 0.4m in height, of medium-sized stone.
- 499 - Cairn; Bronze Age; 427332,375622;2.5 x 3.5m and 0.3m in height, of medium-sized stone. Overlies the edge of possible pond 502.
- 500 - Cairn; Bronze Age; 427327,375623;2.0 x 3.0m and 0.3m in height, masked by turf and soil. Overlies the edge of possible pond 502.
- 501 - Cairn; Bronze Age; 427328,375630;2.5 x 3.0m and 0.3m in height, masked by turf and soil. Overlies the edge of possible pond 502.
- 502 - Possible Pond or House Site; Bronze Age; 427330,375626;Circular hollow 8.0-8.5m in diameter and 0.1m deep. Cairns 499, 500 and 501 overlie its edge. It is possibly a prehistoric pond, or less likely the site of a timber building.
- 503 - Cairn; Bronze Age; 427333,375635;4.0 x 5.0m and 0.3m in height, of medium-sized stone.
- 504 - Cairn; Bronze Age; 427319,375646;2.0 x 2.5m and 0.4m in height, masked by turf and soil.
- 505 - Earthen Bank; Bronze Age; 427307,375655;427313,375650;8.0m in length, 1.5m wide and 0.2m high.
- 506 - Linear Clearance; Bronze Age; 427314,375651;427330,375655;17.0 x 1.5-2.5m and 0.3m high, masked by turf and soil.
- 507 - Earthen Bank; Bronze Age; 427330,375655;427345,375658;Poorly-defined feature 14.5m in length, 1.5m wide and up to 0.2m high. It may have been disturbed in places.
- 508 - Cairn; Bronze Age; 427346,375662;2.5 x 3.0m and 0.2m in height, masked by turf and soil.
- 509 - Cairn; Bronze Age; 427347,375657;4.5 x 5.0m and 0.4m in height, masked by turf and soil.
- 510 - Earthen Bank; Bronze Age; 427362,375651;427348,375655;14.0m in length, 2.0m wide and 0.2m high.
- 511 - Possible Cairn; Bronze Age; 427351,375654;2.0 x 2.5m and 0.1m in height, masked by turf and soil. This is either a small cairn or a small amount of clearance stone on the crest of earthen bank 510.
- 512 - Cairn; Bronze Age; 427364,375652;4.0 x 5.5m and 0.4m in height, some large and medium-sized stone visible but the feature is mostly masked by turf and soil.
- 513 - Possible Gate; Bronze Age; 427354,375656;This gap between cairns 509 and 511 and earthen bank 510 is 1.5-2.5m wide and c.5.0m in length. It is slightly dished, perhaps from puddling. This may well be an original gateway.
- 514 - Earthen Bank; Bronze Age; 427351,375661;427355,375658;6.0m in length, 2.0m wide and 0.2m high. Of mostly earth with some stones.
- 515 - Linear Clearance; Bronze Age; 427356,375680;427351,375661;20.5 x 1.5-2.5m and 0.3m high, masked by turf and soil.

516 - Cairn; Bronze Age; 427313,375677;2.0 x 4.0m and 0.3m in height, masked by turf and soil.

517 - Cairn or Linear Clearance; Bronze Age; 427342,375686;Two amorphous heaps of stone that are either the remnants of a single robbed cairn c.5.5 x 7.5m and maximum 0.3m in height, or two smaller adjacent area of linear clearance.

518 - Earthen Bank; Bronze Age; 427377,375690;427356,375681;24.0m in length, 2.0m wide and 0.3m high. Cut by hollow way 570 in three places and reduced to a lynchet to the west.

519 - Possible Cairn; Bronze Age; 427366,375668;2.0 x 2.5m and 0.2m in height, masked by turf and soil. Either a small cairn or natural stone that has become cairn-like due to erosion to either side by hollow way 570.

520 - Cairn; Bronze Age; 427373,375677;2.0 x 3.0m and 0.2m in height, masked by turf and soil.

521 - Cairn; Bronze Age; 427374,375665;1.5 x 2.0m and 0.3m in height, masked by turf and soil.

522 - Cairn; Bronze Age; 427379,375691;3.5 x 5.0m and 0.6m in height, masked by turf and soil.

523 - Linear Clearance; Bronze Age; 427376,375696;427378,375693;5.0 x 2.5m and is 0.5m high.

524 - Lynchet; Bronze Age; 427368,375705;427377,375696;12.5m in length and 0.3m high. It is cut by hollow way 570.

526 - Lynchet; Bronze Age; 427374,375716;427382,375722;18.0m in length and 0.3m high. It is cut by hollow way 570.

527 - Linear Clearance; Bronze Age; 427382,375723;427401,375727;Regular bank-like feature 21.0 x 3.0m and 0.4m high.

528 - Probable Earthen Bank; Bronze Age; 427373,375658;427385,375665;15.0m in length, 1.5m wide and 0.2m high. Both ends are truncated by hollow way 570.

529 - Linear Clearance; Bronze Age; 427390,375669;427413,375686;Regular bank-like feature 31.0 x 2.0-3.0m and 0.5m high. Overlies earthen bank 530 and disturbed by hollow way 570.

530 - Earthen Bank; Bronze Age; 427414,375686;427416,375685;4.0m in length, 2.0m wide and 0.3m high, and appears to be the butt end of a bank that protrudes from under linear clearance 529 to the west and continues eastwards in lower form as lynchet 1014.

531 - Cairn; Bronze Age; 427422,375684;Amorphous feature 1.5 x 2.0m and 0.1m in height (upslope) and 0.3m (downslope), masked by turf and soil.

532 - Cairn; Bronze Age; 427433,375681;An amorphous feature comprising only a few stones, 2.0 x 2.5m and 0.1m in height (upslope) and 0.3m (downslope).

533 - Cairn; Bronze Age; 427420,375706;3.5 x 4.5m and 0.5m in height, of medium-sized stone.

534 - Cairn; Bronze Age; 427428,375700;4.5 x 3.5m and maximum 0.4m high downslope, heather covered.

535 - Linear Clearance; Bronze Age; 427375,375570;427380,375570;5.0 x 2.0m and 0.3m high, of large and medium-sized stone.

536 - Linear Clearance; Bronze Age; 427381,375570;427384,375569;3.5 x 1.5m and 0.1m high,

masked by turf and soil.

537 - Linear Clearance; Bronze Age; 427385,375573;427388,375572;4.0 x 1.0m and 0.2m high.

538 - Linear Clearance; Bronze Age; 427389,375568;427398,375567;9.0 x 1.5-2.5m and 0.1m high, masked by turf and soil.

539 - Linear Clearance; Bronze Age; 427404,375563;427397,375565;7.5 x 2.0m and 0.2m high. It lies at the edge of stony ground.

541 - Lynchet; Bronze Age; 427417,375566;427407,375562;12.0m in length and 0.3m high, comprising an enhanced natural feature.

542 - Cairn; Bronze Age; 427399,375567;3.5 x 4.0m and 0.3m in height, of large and medium-sized stone. At the edge of stony ground.

543 - Cairn; Bronze Age; 427428,375701;1.5 x 3.0m and 0.3m in height, of large and medium-sized stone. At the edge of stony ground.

544 - Cairn; Bronze Age; 427401,375577;2.0 x 4.0m and 0.3m in height, masked by turf and soil.

545 - Cairn; Bronze Age; 427415,375575;2.0m in diameter and 0.3m in height. Situated on the edge of an area of stony ground and incorporates a stone slab.

546 - Cairn; Bronze Age; 427428,375567;2.5 x 3.5m and 0.2m in height, masked by turf and soil. On the edge of stony ground.

548 - Cairn; Bronze Age; 427442,375530;3.5 x 4.5m and 0.3m in height, mostly masked by turf and soil.

549 - Possible Cairn; Bronze Age; 427422,375585;1.5 x 2.5m and 0.1m in height, masked by turf and soil. May be a natural grouping of stones.

550 - Cairn; Bronze Age; 427422,375599;2.0m in diameter, 0.1m in height (upslope), 0.3m (downslope), masked by turf and soil.

552 - Lynchet; Bronze Age; 427448,375649;427446,375630;20.0m in length and 0.3m high.

553 - Cairn; Bronze Age; 427440,375658;2.5 x 3.0m and 0.2m in height (upslope), 0.4m (downslope), masked by turf and soil.

554 - Cairn; Bronze Age; 427447,375665;3.5 x 5.0m and 0.2m in height (upslope), 0.4m (downslope), with more stone at the north end.

555 - Cairn; Bronze Age; 427456,375699;2.8m-3.9m in diameter and 0.2m in height, situated above a break of slope.

557 - Cairn; Bronze Age; 427432,375707;2.5 x 3.0m and 0.1m in height (upslope), 0.3m (downslope), mostly masked by turf and soil.

558 - Lynchet; Bronze Age; 427446,375693;427432,375723;36.0m in length and 0.3m high. The middle section is partly natural.

559 - Possible Lynchet; Bronze Age; 427439,375724;427429,375724;5.0m in length and may be a natural feature.

560 - Earthen Bank; Bronze Age; 427419,375720,427428,375725;10.0m in length, 2.5m wide and 0.3m high, truncated to the west by hollow way 570.

562 - Earthen Bank; Bronze Age; 427400,375729;427428,375725;Strongly curving feature c.40.0m in length, maximum 3.0m wide and 0.5m high downslope and 0.2m upslope. West end is overlain by linear clearance 527, to the east it becomes a lynchet.

563 - Cairn; Bronze Age; 427423,375731;2.5 x 3.0m and 0.2m in height (upslope), 0.5m (downslope), masked by turf and soil.

564 - Cairn; Bronze Age; 427437,375740;3.5m in diameter and 0.3m in height, located on the terminal of a lynchet (1001).

568; - Guidestone/Bullet Scars; Post-Medieval/Modern;427379,375761; Well-dressed pillar 1.80m high and 0.35 x 0.35m in plan. Three inscriptions comprising date and initials record visits by Road Commissioners in 1737 and 1775, also on the north-east side "TO SHEFEILD" and on the north-west side "TO TIDSW*LL"; Damaged in 1939-45, top removed and bullet scars elsewhere.

570 - Hollow Way; Post Medieval; 427384,375770;427235,375000;0.6m in depth (upslope), hollow way route braids into two courses.

573 - Guidestone/Bullet and Mortar Scars; Post Medieval/Modern; 427398,375680;Small pillar 1.25m high and 0.25 x 0.37m in plan. West face is inscribed "Bas". East face is bullet scarred, with an embedded fragment of mortar.

621 - Pit; Modern; 427432,375513;Shallow rectangular pit 1.5 x 2.5m with upcast to the north and east. It is probably associated with military activity c.1939-45.

625 - Pit; Post Medieval; 427325,375660;Shallow pit 3.5 x 4.5m with upcast to the east. Uncertain interpretation.

630 - Possible House Site; Bronze Age; 427345,375607;Semi-circular area c.5.0m in diameter defined by linear clearance 480 (with 478 and 481).

1000 - Hollow Way; Post Medieval; 427448,375735,427439,375730;Depth 0.1m, approximately aligned on a guidestone to the south-west.

1001 - Possible Lynchet; Bronze Age; 427427,375745,427437,375741;12.0m in length and 0.3m high, and incorporates an earthfast boulder. It is not clear if this feature has been enhanced or is entirely natural.

1002 - Terrace; Natural; 427442,375699;Terrace c.4.0m wide behind the southern end of lynchet 558. May be a geological feature.

1003 - Quarries; Post Medieval; 427462,375638;Widespread area of quarrying comprising distinct hollows of various sizes c.0.1m-0.3m in depth.

1004 - Bullet Scars; Modern; 427469,375646;Area of boulder field with bullet scarred boulders. Associated with military activity c.1939-45.

1005 - Cairn; Bronze Age; 427498,375619;1.7m x 2.5m and 0.2m in height with a small scarp extending from the north-east margin.

1006 - Cairn; Bronze Age; 427464,375584;An amorphous pile of stone maximum 3.5m in

diameter, situated on a natural rock outcrop or edge of stony ground.

1007 - Linear Clearance; Bronze Age; 427481,375562,427478,375558; 5.5 x 2.5m and 0.3m high, masked by turf and soil. The north-western part is earthen and this may comprise hillwash against a narrow, linear stony feature.

1008 - Cairn; Bronze Age; 427444,375566; 3.0 x 3.5m and 0.2m in height, piled around an earthfast.

1009 - Stony Lynchet; Bronze Age; 427407,375574,427403,375577; 5.0m in length and 0.2m high, somewhat stoney.

1010 - Lynchet; Bronze Age; 427398,375619,427400,375618; 2.5m in length and 0.2m high.

1011 - Possible Cairn; Bronze Age; 427401,375633; 1.0m in diameter and 0.2m in height, of medium-sized stone.

1012 - Possible Cairn; Bronze Age; 427427,375646; A natural earthfast with one small stone at the north that may have been placed here.

1014 - Lynchet; Bronze Age; 427416,375686,427432,375681; 15.5m in length and 0.3m high.

1015 - Pit; Modern; 427387,375695; Small irregular pit, probably associated with military activity c.1939-45.

1016 - Earthen Bank; Bronze Age; 427385,375682,427381,375691; 9.0m in length, 2.0m wide and up to 0.2m high downslope. To the north it terminates at cairn 522.

1017 - Linear Clearance; Bronze Age; 427365,375705,427369,375708; 5.0 x 2.5m and 0.4m high.

1018 - Earthen Bank; Bronze Age; 427369,375708,427372,375710; 5.0m in length, 2.5m wide and 0.3m high. To the north-east it continues in much reduced form as lynchet 526.

1019 - Linear Clearance; Bronze Age; 427390,375638,427394,375640; 4.0 x 1.5m and 0.2m high, masked by turf and soil.

1020 - Pit; Modern; 427372,375607; Shallow oval pit with upcast is probably associated with military activity c.1939-45.

1021 - Lynchet; Bronze Age; 427361,375626,427364,375627; 2.5m in length and 0.2m high. One end is truncated by hollow way 570.

1022 - Linear Clearance; Bronze Age; 427384,375568,427390,375567; 6.0 x 3.0m and 0.3m high, of medium-sized stone.

1023 - Earthen Bank; Bronze Age; 427318,375566,427319,375571; 6.0m in length, 2.0m wide and 0.3m high. Appears to be built mostly of earth but with some stone content.

1024 - Cairn; Bronze Age; 427359,375601; 0.3m in height, masked with a small tail of material to the east.

1025 - Lynchet; Bronze Age; 427365,375601,427366,375604; 3.5m in length and 0.2m high.

1026 - Pit; Modern; 427350,375652; Small, sharp-sided pit 0.3m deep probably associated with military activity c.1939-45.

1027 - Possible Cairn; Bronze Age; 427361,375658;1.5m in diameter and 0.2m in height, comprising some small stones to the east side of an earthfast boulder.

1028 - Pile of Stones; Post Medieval; 427317,375693;1.0 x 2.0m and is probably upcast from hollow way 565.

1029 - Linear Clearance; Bronze Age; 427298,375633,427303,375628;8.0 x 2.0m and 0.3m high, masked by turf and soil.

1030 - Cairn; Bronze Age; 427312,375626;2.0 x 2.5m and 0.3m in height, upright stone at south end.

1031 - Lynchet; Bronze Age; 427318,375588,427323,375592;6.0m in length and 0.2m high.

1032 - Probable Cairn; Bronze Age; 427301,375661;2.4 x 3.0m and 0.3m in height, masked by turf and soil.

1033 - Cairn; Bronze Age; 427264,375539;2.5 x 3.5m and 0.3m in height, masked by turf and soil.

1034 - Linear Clearance; Bronze Age; 427367,375608,427369,375610;3.5 x 1.5m and 0.3m high.

1036 - Possible Lynchet; Bronze Age; 427313,375541,427317,375561;20.0m in length and 0.2m high. This very slight feature may be fortuitous.

1037 - Cairn; Bronze Age; 427329,375504;2.5 x 3.0m and 0.2m in height.

1038 - Probable House Site/Linear Clearance; Bronze Age; 427392,375882;Circular platform cut into natural slope, 8.0 x 10.0m internally, defined at the back by scarp 0.3m high, and at the front by a lynchet 0.3m high. There is linear clearance to either side: north 9.5 x 2.0m and south 2.0 x 5.0m.

1039 - Cairn; Bronze Age; 427413,375891;3.0 x 3.5m and 0.4m in height, of medium-sized stone.

1040 - Linear Clearance; Bronze Age; 427417,375902,427406,375906;1.5 x 2.5m and 0.3m high.

1041 - Cairns; Bronze Age; 427400,375909;Three small exposures of stone on the line of a boundary, 1.0 x 2.0m, 0.5m in diameter, and 0.5 x 1.0m respectively.

1042 - Linear Clearance; Bronze Age; 427388,375914,427396,375911;8.0 x 1.5-3.5m and 0.4m high, largely masked by turf and soil but some medium-sized stone is visible.

1043 - Cairn; Bronze Age; 427386,375901;3.5m in diameter and 0.3m in height, of large and medium-sized stone.

1044 - Linear Clearance; Bronze Age; 427393,375867,427388,375870;5.5 x 1.5m and 0.1m high, masked by turf and soil.

1045 - Linear Clearance; Bronze Age; 427428,375898,427422,375901;6.0 x 1.5m and 0.1m high, masked by turf and soil.

1046 - Cairn; Bronze Age; 427435,375863;1.5 x 2.5m and 0.2m in height (upslope), 0.4m (downslope), disturbed at the west by hollow ways.

1047 - Cairn; Bronze Age; 427435,375858;2.5 x 3.5m and 0.1m in height (upslope), 0.3m

(downslope), disturbed at west end by hollow ways.

1048 - Cairn; Bronze Age; 427422,375865;1.0 x 1.5m and 0.2m in height, masked by turf and soil, disturbed by hollow ways to west.

1049 - Bell Pit; Post Medieval; 427272,375950;Single pit 2.5m in diameter that may be a run-in shaft with a high spoil-heap on the downslope side, 6.5 x 11.0m.

1050 - Bell Pit; Post Medieval; 427286,375938;Single pit 3.0 x 3.5m that may be a run-in shaft with a 1.0m high spoil-heap on the downslope side, 7.0 x 9.0m.

1051 - Building; Post Medieval; 427284,375935;The footings of a drystone structure 2.5 x 3.5m externally and c.0.5m high. It had a door at the north-east corner, possibly a toolshed associated with mine 1050.

1052 - Mine Pits; Post Medieval; 427280,375942;Two conjoined pits, each 3.0-5.0m in diameter. There is no associated upcast.

1053 - Mine; Post Medieval; 427313,375913;Shaft pit 2.5 x 3.0m with spoil-heap downslope 10.0 x 13.0m and 1.2m in height. 3-4 shallow pits upslope. Narrow channel to the south-east, c.50m in length and 1.0m deep, is flanked by upcast banks.

1054 - Mine Pit; Post Medieval; 427294,375930;1.5 x 2.5m in which there is a deposit of bright orange-brown ochre exposed in the side.

1055 - Mine; Post Medieval; 427245,375930;Single pit 4.5 x 6.0m that may be a run-in shaft, with a small spoil-heap on the downslope side, 5.5 x 7.5m. Narrow channel to the south-east, c.70m in length and 0.8m deep, is flanked by upcast banks.

1056 - Cairn; Bronze Age; 427349,375837;1.0 x 1.5m and 0.3m in height, masked by turf and soil.

1057 - Shooting Butt or Military Fieldwork; Post Medieval or Modern; 427473,375966;Hollow cut into the hillside 5.0m across with upcast on the upslope side and an entrance downslope. May have military origins or associations.

1058 - Cairn; Bronze Age; 427474,375959;2.0 x 2.5m and 0.4m in height, flanked by hollow way to north. Some loose stone may be upcast from the hollow way.

1059 - Cairn; Bronze Age; 427405,375976;1.5 x 2.5m and 0.2m in height, some medium-sized stone visible.

1068 - Possible Gate; Bronze Age; 427345,375500;Poorly defined gap in earthen bank. May be original. Utilised by an outlying hollow way.

1169 - Shooting Butt or Military Fieldwork; Post Medieval or Modern; 427463,375909;Cut into slope with upcast on all sides except the east which appears to be an entrance. May have military origins or associations.

1170 - Linear Clearance; Bronze Age; 427455,375887;427451,375888;0.3m in height to the north, 0.1m to the south, some small stones visible but mostly masked.

1171 - Linear Clearance; Bronze Age; 427461,375922;427459,375916;0.5m in height (downslope), 0.3m (upslope), of large and medium-sized stone.

- 1172 - Hollow; Modern; 427461,375900;Scoop dug into the natural slope.
- 1173 - Lynchet; Bronze Age; 427426,375918;427422,375901;0.2m in height, situated within an area of hollow ways, but appears to be a genuine lynchet.
- 1174 - Cairn; Bronze Age; 427425,375911;0.2m in height, masked.
- 1175 - Probable Lynchet; Bronze Age; 427445,375945;427436,375918;0.4m in height, situated within an area of hollow ways, but appears to be a genuine lynchet.
- 1176 - Cairn; Bronze Age; 427441,375992;Large amount of stone of mixed sizes, with a small heap of three stones to the south-east.
- 1177 - Linear Clearance; Bronze Age; 427399,375965;427402,375972;0.3m in height, with hollow ways to both sides.
- 1178 - Pile of Stones; Post Medieval; 427407,375998;Two heaps of stone alongside hollow ways, probably track clearance rather than cairns.
- 1200 - Bell Pit; Post Medieval; 427218,375967;Sub-circular pit c1.5m in diameter with earthen spoil heap to south-east, 0.2m in height (upslope) and 2.5m in height (downslope).
- 1201 - Bell Pit; Post Medieval; 427245,375956;Sub-circular pit 1.3m in diameter with earthen spoil heap to the south and east, 0.2m in height (upslope) and 1.0m in height (downslope).
- 1202 - Bell Pit; Post Medieval; 427205,375943;Sub-circular pit 2.2m in diameter with slumped earthen spoil heap to south-east 2.5m in height (downslope).
- 1203 - Mine Pit; Post Medieval; 427202,375969;Sub-circular pit c.3.0m in diameter and 1.0m in depth, of a type normally associated with bell pits. No visible spoil.
- 1204 - Mine Pit; Post Medieval; 427188,375988;Square pit 2.4m x 2.4m and 0.5m in depth, of a type normally associated with bell pits. There is a low area of spoil to the south-east of the pit.
- 1205 - Bell Pit; Post Medieval; 427192,375956;Circular pit 2.3m in diameter with earthen spoil heap to and east, 0.4m in height (upslope) and 1.0m (downslope). Spoil from this pit is merged with that of the adjacent pit 1206.
- 1206 - Bell Pit; Post Medieval; 427191,375959;Small pit 1.5m in diameter with area of spoil to east, indistinguishable from the spoil associated with pit 1205.
- 1207 - Bell Pit; Post Medieval; 427182,375957;Circular pit 2.2m in diameter situated at the foot of the natural slope. There is a small amount of spoil to the south-east of the pit, 0.3m in height, suggesting that this pit is relatively shallow.
- 1208 - Possible Pit; Modern; 427171,375958;Small rectangular pit 1.2m x 1.0m and 0.1m in depth. Associated with military activity c.1939-45.
- 1210 - Pit; Modern; 427117,375991;Square, sharply defined pit 1.2m x 1.2m and 0.2m in depth. Associated with military activity c.1939-45.
- 1211 - Bullet Scars; Modern; 427125,375943;Single bullet scarred boulder associated with military activity c.1939-45.

1212 - Bullet Scars; Modern; 427144,375959;Single bullet scarred boulder associated with military activity c.1939-45.

1213 - Bullet Scars; Modern; 427133,375976;Single bullet scarred boulder associated with military activity c.1939-45.

1214 - Mound; Natural; 427157,375955;Earthen mound 2.8m in diameter and 0.3m in height, probably natural.

1217 - Bell Pit; Post Medieval; 427142,375891;Sub-circular pit c.4m in diameter with a substantial spoil heap to the south-east, 0.3m in height (upslope) and 1.6m (downslope).

1218 - Mound; Natural; 427127,375883;Predominantly earthen mound with some buried stone content, 2.3m in diameter and 0.2m in height. May well be natural.

1220 - Cairn; Bronze Age; 427030,375894;Triangular cairn of large stones maximum diameter 1.9m and 0.6m in height, possibly situated at the edge of a cultivated area.

1221 - Possible Clearance Stone; Bronze Age; 427030,375906;Two large stones, possibly at the edge of a cultivated area.

1222 - Possible Clearance Stone; Bronze Age; 427033,375914; An area of large, densely-scattered surface stone, possibly the result of clearance for cultivation.

1223 - Bullet Scars; Modern; 427078,375928;Single bullet scarred boulder associated with military activity c.1939-45.

1224 - Probable Cairn or Burial Cairn; Bronze Age; 427045,375942; A substantial heather-covered mound of medium-sized stones, 3.1m maximum diameter and 0.4m in height. Its location on stoney ground suggests it may be a funerary feature.

1228 - Track; Post Medieval; 427182,375973;427187,375985;Terraced trackway 1.8m wide and c.14m in length is visible cut into the natural slope. It appears to terminate to the north at pit 1204.

1229 - Track; Post Medieval; 427177,375944;427178,375952;Short section of terraced trackway at the base of the natural slope, 1.8m wide and c.5m in length. Probably a continuation of trackway 1228.

1481 - Pit; Modern; 427264,375670;1.2 x 0.8m and 0.5m in depth. Associated with military activity c.1939-45.

1482 - Pit; Modern; 427260,375678;1.2 x 0.9m and 0.6m in depth. Associated with military activity c.1939-45.

1484 - Pit; Modern; 427234,375627;1.2 x 0.8m and 0.5m in depth. Associated with military activity c.1939-45.

1485 - Pit; Modern; 427163,375576;Sub-circular pit maximum 2.7m in diameter and 0.6m deep, significantly larger than other pits. Possibly associated with military activity c.1939-45.

1486 - Pit; Modern; 427169,375579;2.2 x 0.6m and 0.6m in depth. Associated with military activity c.1939-45.

1487 - Pit; Modern; 427166,375605;2.1 x 1.3m and 0.3m deep. Associated with military activity

c.1939-45.

1488 - Mine or Drain; Post Medieval; 427151,375586;427176,375619;Narrow ditch, 0.3m wide and 0.4m in depth, could be either a Post Medieval industrial feature similar to 1491 or a drain.

1489 - Cairn; Bronze Age; 427172,375511;3.0m in diameter and 0.5m in height. Adjacent hollow ways divert around this cairn.

1491 - Mine; Post Medieval; 427102,375556;Double banked linear ditch, banks are flat topped and 2.4m in width. Stone lined drain visible at east end. Slight widening at west end may be a concealed shaft. Similar in form to features 1053 and 1055.

1492 - Possible Drain; Post Medieval; 427119,375551;427096,375528;Wide, irregular channel with straight-edged sections and water draining down middle. Could be natural in origin but artificially altered, possibly associated with nearby industrial activity 1491.

1493 - Pit; Modern; 427076,375510;1.4 x 0.9m and 0.2m in depth, probably associated with military activity c.1939-45.

1494 - Pile of Stones; Post Medieval; 427078,375513;Stone cairn maximum 5.8 x 3.0m and 0.4m in height. Not prehistoric in appearance, possibly associated with nearby Post Medieval industrial activity 1491, 1492.

1495 - Pit; Modern; 427068,375505;1.5 x 1.0m and 0.5m in depth, associated with military activity c.1939-45.

1496 - Pit; Modern; 427074,375506;1.4 x 1.0m and 0.3m in depth, associated with military activity c.1939-45.

1497 - Paired Pits; Modern; 427009,375501;Pair of pits each measuring 1.3 x 0.9m and 0.4m in depth, associated with military activity c.1939-45.

1498 - Pit; Modern; 427041,375539;0.6 x 0.6m and 0.2m in depth, associated with military activity c.1939-45.

1499 - Possible Clearance Stone; Bronze Age; 427049,375535;Linear area of medium-sized stone. Possibly an area of clearance stone or a fortuitous natural feature.

1500 - Possible Bell Pit; Post Medieval; 427066,375526;Small mound 1.2m x 2.9m and 0.2m in height with small pit upslope. If this is a bell pit it may well be unfinished - possibly due to flooding from adjacent flush.

1503 - Possible Pit; Modern; 427022,375546;Irregular pit maximum 2.8m in diameter and 0.3m in depth, cut into the bottom of bell pit 1504, possibly associated with military activity c.1939-45.

1504 - Bell Pit; Post Medieval; 427025,375548;Shallow hollow 0.2-0.3m in depth with spoil to north-east. Possible military pit 1503 has been cut into the bottom.

1505 - Possible Linear Clearance; Bronze Age or Post Medieval; 427045,375561;427044,375556;Linear pile of medium-sized stones 4.8m x maximum 2.0m and 0.3m in height, grass and heather-covered. Pit 1506 either cuts into south-east side of this bank or is the source of the material and thus 1505 is part of the upcast of probable bell pit 1506.

1506 - Probable Bell Pit; Post Medieval; 427046,375558;0.9 x 1.3m and 0.1m in depth with spoil to south-east side, cuts into stone bank 1505. Not military in appearance, could be an

exploratory excavation associated with nearby industrial activity.

1507 - Pit; Modern; 427004,375554;1.2 x 0.8m and 0.2m in depth, associated with military activity c.1939-45.

1508 - Pit; Modern; 427202,375891;0.7 x 0.6m and 0.2m in depth, associated with military activity c.1939-45.

1509 - Pit; Modern; 427193,375873;1.3 x 0.9m and 0.2m in depth, associated with military activity c.1939-45.

1510 - Pit; Modern; 427192,375869;0.6 x 0.8m and 0.2m in depth, associated with military activity c.1939-45.

1537 - Bell Pit; Post Medieval; 427110,375508;2.2m square pit with spoil to north side.

2149 - Pits/Slit Trenches; Modern; 427486,375649;Group of three foxholes and two slit trenches averaging 0.5m x 1.1m and 0.1m in depth. Associated with military activity c.1939-45.

2150 - Slit Trench; Modern; 427467,375628;Two shallow slit trenches 0.4m x 1.1m. Associated with military activity c.1939-45.

2153 - Bullet Scars; Modern; 427440,375792;Area of heavily bullet-scarred rocks. Associated with military activity c.1939-45.

2154 - Bullet Scars; Modern; 427481,375797;Large bullet-scarred boulder in stream. Associated with military activity c.1939-45.

2212 - Possible Paving Stone; Post Medieval; 427451,375802;Worn slab in hollow way 2213, 0.5m x 0.8m. Not certainly placed but wear caused by use of 2213.

2213 - Hollow Way; Post Medieval; 427412,375781;427454,375803;0.4m in depth where it cuts into natural slope.

2214 - Pit; Modern; 427424,375757;1.0m x 0.8m, and 0.1m in depth. Associated with military activity c.1939-45.

2215 - Slit Trench; Modern; 427432,375768;2.2m x 0.5m and 0.2m in depth with an area of spoil downslope from the trench. Associated with military activity c.1939-45.

2216 - Pit; Modern; 427412,375756;0.6m x 0.9m and 0.1m in depth. Associated with military activity c.1939-45.

2217 - Slit Trench; Modern; 427411,375743;1.1m x 0.5m and 0.1m in depth. Associated with military activity c.1939-45.

2218 - Conduit; Post Medieval; 427385,375787;427419,375819;Terrace cut into the natural slope at a width of 0.6m, partly overlain by spoil from pipeline 2219, which may be the original continuation of the conduit to Little Barbrook reservoir (2239).

2219 - Pipeline; Modern; 427390,375797;427418,375820;Pipeline to carry water from the natural stream west of this feature via a conduit to the Little Barbrook reservoir. The pipeline has been sunk into, and caused disturbance to, adjacent hollow ways.

2220 - Shooting Butt or Military Fieldwork; Post Medieval or Modern; 427454,375846;

Embanked hollow 4.4m square, part of a line of features running NNE (1057, 1169, 2239), possibly a practice-work associated with military activity c.1939-45.

2221 - Linear Clearance; Bronze Age; 427460,375856;427457,375853;Medium-sized stone piled along the crest of a steep valley slope, 4.8m x 1.3m and 0.5m in height (downslope).

2222 - Bullet Scars; Modern; 427498,375952;Single large boulder with bullet scars on north face. Associated with military activity c.1939-45.

2223 - Possible Bridge; Post Medieval; 427369,375772;Large flat natural stone slab close to the stream may have formed a bridging point (hollow ways on both sides approach and bend towards this slab).

2224 - Cairn; Bronze Age; 427354,375783;Pile of heather and bracken covered stones 3.4m in diameter, 0.2m in height (upslope) and 1.0m in height (downslope).

2239 - Conduit; Modern; 427419,375820;427560,376122;Narrow water channel 0.8m wide and c.0.6m in depth. Conduit supplies water for Little Barbrook reservoir from stream to west of channel via pipeline (feature 2219). The channel is dug (at least in part) along the line of a former hollow way (565).

2726 - Hollow Way; Post Medieval; 427400,375739;427373,375717;Narrow curvilinear route departs from line of main swathe of hollow ways.

2727 - Cairn; Bronze Age; 427370,375611;Small distinct feature amongst linear clearance and other cairns.

2728 - Cairn; Bronze Age; 427299,375547;Maximum 3.0m in diameter.

2766 - Hollow Way; Post Medieval; 427056,375735;427272,375746;Braided hollow way

2775 - Cairn; Bronze Age; 427460,375584;Amorphous pile of stones c.3m in diameter on a natural rock outcrop at the edge of stony ground.

2776 - Hollow Way; Post Medieval; 427388,375890;427395,375905;Short c.20m stretch of hollow way.

2777 - Hollow Way; Post Medieval; 427345,375759;427365,375830;Braided hollow ways.

2797 - Possible Hollow Way; Post Medieval; 427494,375803;427503,375814;Slight terracing traversing steep slope but may be fortuitous.

2798 - Possible House Site; Bronze Age; 427370,375607;Possible site of timber house marked by curve in bounding features, 1034, 2727, 489, with a diameter of at least 6m.

Sheet 9

1423 - Possible Clearance Stone; Bronze Age; 427812,375565;Break of slope which may contain field clearance debris.

1424 - Cairn; Bronze Age; 427801,375574;Stone cairn maximum 5.0m in diameter with part showing evidence of subsequent stone robbing on west side.

1425 - Scarp; Post Medieval; 427801,375563;427763,375578;Stony scarp, 0.5m in height, representing a negative lynchet cut when the terraced trackway was built.

1426 - Possible Cairn; Bronze Age; 427765,375575; Maximum 2.6m in diameter, of medium-sized stone, disturbed by scarp 1425.

1427 - Possible Cairn; Bronze Age; 427797,375583; Medium-sized stones piled against an earthfast boulder, maximum 1.2m in diameter.

1428 - Bank; Modern; 427765,375581,427704,375607; Large and medium-sized stones upcast to a height of 0.5m at the edge of a bulldozed fire break.

1429 - Probable Cairn; Bronze Age; 427748,375591; 1.9m x 3.0m and 0.3m in height, of medium-sized stone. The eastern half may consist of a buried earthfast stone, the western edge has been robbed.

1430 - Cairn; Bronze Age; 427771,375598; Cairn of medium-sized stone 7.0m in diameter, steep-sided to base, central antiquarian excavation trench with upcast spoil heaps at both ends.

1431 - Stony Lynchet; Bronze Age; 427743,375606,427734,375602; Lynchet 0.5m in height with medium-sized (?clearance) stone.

1432 - Probable Cairn; Bronze Age; 427835,375630; 1.8m x 3.1m and 0.3m high, little visible stone, possible a natural outcrop.

1433 - Stone; Natural; 427888,375632; Vertical stone slab, 0.5 x 1.0m in plan and 0.6m high, probably natural.

1434 - Cairn; Bronze Age; 427930,375624; 1.9m in diameter and 0.3m high, masked.

1435 - Pit; Modern; 427874,375694; Rectangular pit 0.2m deep, may be associated with military activity c.1939-45.

1436 - Cairn; Bronze Age; 427874,375692; 4.6m in diameter and 0.3m high of large stones, two further stones lie beyond the eastern edge of the cairn.

1437 - Cairn; Bronze Age; 427841,375651; Area of medium-sized stone 1.0m x 1.4m.

1438 - Cairn; Bronze Age; 427832,375675; 2.3m in diameter and 0.3m in height, masked.

1439 - Cairn; Bronze Age; 427827,375664; 2.0m x 4.4m and 0.3m in height, indistinct edges, masked.

1440 - Probable Cairn; Bronze Age; 427823,375653; 1.4m in diameter and 0.2m in height, masked.

1441 - Cairn; Bronze Age; 427806,375671; Of large and medium-sized stone, maximum 5.7m in diameter and 0.4m in height. There is a pit cut into the centre which is surrounded by scattered upcast.

1442 - Cairn; Bronze Age; 427778,375656; Maximum 6.4m in diameter and 0.5m in height of medium-sized stone.

1443 - Possible Cairn; Bronze Age; 427744,375645; 1.2m x 2.2m and 0.3m in height, masked.

1444 - Cairn; Bronze Age; 427717,375629; 3.0m in diameter and 0.2m in height (upslope) and 0.5m in height (downslope), masked.

1445 - Stony Lynchet; Bronze Age; 427747,375610;427743,375612;Low stony lynchet c.5m in length.

1446 - Cairn; Bronze Age; 427725,375612;0.2m in height, of medium-sized stone.

1447 - Scarp; Post Medieval; 427678,375620;427704,375603;A negative lynchet created to form the edge of a levelled platform presumably a passing place or vehicular turning point associated with the track. Same context as line of stones on other edge of platform (2123).

1448 - Quarries; Post Medieval; 427672,375632;Two stone quarries, possibly created during trackway construction.

1449 - Linear Clearance; Bronze Age; 427693,375635;427681,375646;Linear clearance at the break in the natural slope, 3.0m x 11.5m, comprising a bank of large and medium-sized stones, overlain by cairn 1450.

1450 - Cairn; Bronze Age; 427690,375640;Small cairn of medium-sized stone overlying linear clearance 1449.

1451 - Lynchet; Bronze Age; 427694,375629;427691,375633;Small lynchet with medium-sized stone, extending from a natural outcrop of earthfast boulders.

1452 - Clearance Stone; Bronze Age; 427689,375637;Area of chunked medium-sized stone associated with an adjacent cleared area above.

1453 - Possible House Site; Bronze Age; 427689,375661;Possible platform, 4.0m x 6.0m, with earth and stone lynchet downslope, possible cut upslope.

1454 - Burial Cairn/Platform; Bronze Age; 427741,375681;Large circular cairn of medium-sized stone c.11m in diameter and just under 1m in height. There is a robber trench at the centre and a raised platform of medium-sized stones to the south-west which appears to extend under the main cairn while still being visible on the south side. There is a small quarry pit to the north.

1458 - Drain; Post Medieval; 427855,375521;427817,375563;Flanking upslope of track, depth 0.5m. SE end stops at slight flush running upslope.

1459 - Cairn; Bronze Age; 427868,375507;3.0m x 4.4m and 0.3m high of medium-sized stone.

1460 - Probable Cairn; Bronze Age; 427872,375510;slight mounding 0.2m high, probably buried cairn.

1462 - Mound; Natural; 427926,375510;Earthen mound 3.4m in diameter with one earthfast boulder, possible upcast from animal action.

1463 - Burial Cairn/Platform/Excavation Trench/Spoil Mounds; Bronze Age/Modern; 427909,375607;Re-constructed excavated cairn c.8m in diameter with platform extending to the east. An excavation trench can be seen around the cairn with evidence of three baulks. There are relic spoil heaps to the south and east of the excavation trench.

1464 - Headstone; Modern; 427870,375579;Turf-covered dog's grave marked by a small raised headstone.

1465 - Stone Circle/Excavation Trench; Bronze Age/Modern; 427857,375582;Barbrook I stone circle, an embanked stone circle with levelled interior. Former excavation trenches in evidence. One of the 13 regularly spaced orthostats appears to be missing with corresponding disturbance

of inner part of ring bank (NE of circle) 12 stones still stand. There has been a small excavation in front of the largest orthostat to the south-west, and two trenches across the interior.

1466 - Stone; Natural; 427817,375593; Small vertically-set slab probably a natural feature in a prominent position.

1467 - Quarry; Post Medieval; 427821,375563; Small rectangular quarry with no associated spoil.

1468 - Quarry; Post Medieval; 427802,375565; Small ovoid quarry.

1471 - Excavation Trench or Pit; Post Medieval; 427603,375892; A pit, possibly an excavation trench, lies to the south-east of cairn 1605. The relationship between these two features is not clear. A small mound of stones to the south-east of the pit is probably associated spoil.

1555 - Cairn; Bronze Age; 427835,375711; Cairn of medium-sized stone 4.6m x 6.0m and 0.8m in height.

1556 - Cairn; Bronze Age; 427842,375717; Cairn of medium-sized stone 5.0m x 8.5m. Several large stones around the south edge may form a curb, or may just represent clearance.

1557 - Cairn; Bronze Age; 427852,375697; Partially masked cairn with at least some large stone content, maximum 4.0m in diameter. There is a large earthfast boulder at one end.

1558 - Mound/Pit; Post Medieval; 427830,375807; Earthen mound 0.2m in height with an ill-defined pit, 0.1m in depth, at one side. Does not appear to be a military feature.

1559 - Cairn; Bronze Age; 427798,375755; 3.8m in diameter and 0.5m in height, comprising large stones round the southern edge with medium-sized stone in the centre and earth at the east end. This cairn was excavated and re-built in 1960.

1560 - Spoil Mound; Modern; 427791,375756; Earthen spoil mound 3.3m x 4.6m and 0.5m in height, by-product of excavation of cairn 1561.

1561 - Cairn/Excavation Trench; Bronze Age/Modern; 427790,375762; Restored Bronze Age cairn 2.7m in diameter and 0.3m in height with a centre of small and medium-sized stones and a curb of large stones around three sides of the cairn. The curb is a spurious product of restoration. The whole lies within a modern excavation trench.

1562 - Cairn; Bronze Age; 427801,375773; 2.5m in diameter and 0.3m in height, masked.

1563 - Cairn; Bronze Age; 427789,375780; Grass-covered cairn of medium-sized stone maximum 4.4m in diameter and 0.4m in height. There are voids between some stones suggesting that the cairn has been re-built but there is no documented excavation.

1564 - Cairn; Bronze Age; 427786,375786; 2.6m x 4.0m and 0.3m in height.

1565 - Cairn; Bronze Age; 427794,375742; 4.5m in diameter and 0.3m in height of large and medium-sized stone. One side of the cairn is poorly defined and it has a flat top, suggesting that material has been removed from the top.

1566 - Lynchet/Earthen Bank; Bronze Age; 427772,375756; 427788,375746; Earthen bank/lynchet 0.2m in height with some stone content.

1567 - Cairn; Bronze Age; 427743,375736; 5.4m in diameter and 0.3m in height of medium-sized

stone.

1568 - Possible Hollow Way; Post Medieval; 427725,375721;427720,375705;May represent no more than a well-defined sheep track.

1569 - Possible Platform; Bronze Age; 427723,375691;427728,375682;Two curvilinear scarps (possibly lynchets), upslope scarp is 0.2m in height, downslope scarp is 0.6m in height. Together they define a D-shaped platform-like level area in the natural slope.

1570 - Cairn; Bronze Age; 427705,375700;Maximum 6.9m in diameter and 0.4m in height, masked.

1571 - Stony Lynchet; Bronze Age; 427706,375696;427699,375699;Comprising low stony spread 0.2m in height.

1572 - Dressed Stone; Post Medieval; 427713,375685;Lintel-type gritstone block partly finished with two roughly-dressed faces.

1573 - Clearance Stone; Bronze Age; 427710,375686;Irregular low cairn of large and medium-sized stones, c.3.6m x 4.0m.

1574 - Possible Lynchet; Bronze Age; 427720,375677;427715,375676;0.2m maximum height and c.5m in length, with a poorly defined platform below.

1575 - Cairn/Possible Platform or Cairn; Bronze Age; 427697,375705;Irregular cairn of large and medium-sized stone, 0.5m in height (downslope). There is an off-centre pit with associated upcast in the south-west quadrant of the cairn. To the south-east the cairn merges with stony lynchet 1571. A platform or second cairn of equal height is attached to the WNW.

1576 - Cairn/Platform; Bronze Age; 427690,375693;5.0m in diameter and 0.4m in height, of medium-sized stone with two large stone slabs at the edge. There is a flat-topped lobate platform 0.3m in height to the west.

1577 - Possible Linear Clearance; Bronze Age; 427687,375689;427684,375685;Indistinct area of medium-sized stone 1.1m x 5.0m and 0.2m in height.

1578 - Possible Linear Clearance; Bronze Age; 427681,375686;427678,375682;Indistinct area of large and medium-sized stone 1.0m x 4.5m and 0.2m in height.

1579 - Quarry; Post Medieval; 427633,375672;0.6m in depth, the result of quarrying for road-building material.

1580 - Quarry; Post Medieval; 427648,375651;0.6m in depth, the result of quarrying for road-building material.

1581 - Possible House Site; Bronze Age; 427624,375705;4.0m x 7.0m platform, with possible stoney revetment downslope.

1582 - Probable Pit/Mound; Post Medieval; 427609,375728;Earthen mound 3.2m in diameter with adjacent pit or depression.

1583 - Cairn; Bronze Age; 427602,375745;The centre of the cairn has been robbed and consists of large and medium-sized stone debris. There are discreet piles of upcast medium-sized stones to the north and south of the cairn.

1584 - Quarry; Post Medieval; 427560,375752;Small stone quarry perhaps created by quarrying for track metalling.

1585 - Cairn; Bronze Age; 427571,375800;Restored cairn 6.7m x 11.7. The centre of the cairn was robbed in 1992 and later replaced by PJPB Archaeology Service.

1586 - Possible Quarries; Post Medieval; 427562,375812;Two small pits, possibly quarries, with stone debris between them.

1587 - Possible House Site; Bronze Age; 427571,375810;427570,375815;Curvilinear stoney lynchet c.6m in length defining a possible house platform upslope of c. 4.5m diameter.

1588 - Cairn; Bronze Age; 427546,375833;Maximum c.8m in diameter, of medium-sized stone, partly robbed.

1589 - Linear Clearance; Bronze Age; 427557,375830;427553,375827;1.0m x 4.0m. May represent an area of linear clearance.

1590 - Cairn; Bronze Age; 427551,375827;3.8m in diameter, of medium-sized stone.

1591 - Possible Lynchet; Bronze Age; 427563,375858;427561,375847;Possible lynchet with angle change at north end.

1592 - Hollow Way; Post Medieval; 427626,375978;427562,375901;Broad area of hollow ways.

1593 - Probable Cairn; Bronze Age; 427639,375967;2.5m in diameter and 0.3m in height, masked but at least some stone content.

1594 - Cairn; Bronze Age; 427645,375950;Maximum 4.2m in diameter and 0.3m in height, masked.

1595 - Probable Cairn; Bronze Age; 427637,375935;2.5m in diameter and 0.3m in height (downslope), masked.

1596 - Stony Lynchet; Bronze Age; 427633,375934;427630,375929;0.3m in height and c.5m in length.

1597 - Probable Cairn; Bronze Age; 427628,375927;Maximum 3.0m in diameter and 0.3m in height (downslope), masked.

1598 - Cairn; Bronze Age; 427637,375911;3.0m in diameter and 0.3m in height, masked.

1599 - Slit Trenches; Modern; 427637,375905;Three trenches with average dimensions 0.7m x 1.3m and 0.2m in depth, associated with military activity c.1939-45.

1600 - Cairn; Bronze Age; 427644,375890;Maximum 3.8m in diameter and 0.5m in height, masked.

1601 - Cairn; Bronze Age; 427644,375897;1.5m x 3.0m and 0.3m in height, masked.

1602 - Possible Cairn; Bronze Age; 427637,375901;1.6m in diameter and 0.1m in height, masked.

1603 - Cairn; Bronze Age; 427628,375897;4.2m in diameter and 0.4m in height, masked.

1604 - Cairn; Bronze Age; 427619,375894;Maximum 3.0m in diameter and 0.3m in height, masked.

1605 - Probable Cairn; Bronze Age; 427601,375892;Probable cairn which appears to be Bronze Age. There is a pit or possible excavation trench (1471) to the south-east of the cairn with a possible associated stony spoil mound (1472). The exact relationship between the cairn and pit is not clear.

1606 - Probable Cairn; Bronze Age; 427577,375896;4.5m in diameter and 0.3m in height, masked but with at least some stone content.

1607 - Cairn; Bronze Age; 427592,375893;1.7m in diameter and 0.2m in height, masked.

1608 - Cairn; Bronze Age; 427624,375857;3.8m in diameter and 0.4m in height, of medium-sized stone. There is an oval sharp-sided internal robber pit with associated upcast to the south-east.

1609 - Cairn; Bronze Age; 427623,375842;3.8m in diameter and 0.6m in height of large and medium-sized stone.

1610 - Pit; Modern; 427615,375849;0.7m x 1.7m and 0.2m in depth, associated with military activity c.1939-45.

1611 - Cairn; Bronze Age; 427592,375797;4.0m x 5.6m and 0.4m in height of medium-sized stone.

1612 - Cairn/Possible Cist; Bronze Age; 427603,375775;Maximum 7.0m in diameter and 0.7m in height of medium-sized stone. The centre of the cairn has been disturbed and two sides of a possible cist have been revealed, at least one of which comprises a natural earthfast stone. There is upcast downslope of the central disturbance comprising loose stones.

1613 - Cairn; Bronze Age; 427588,375780;Maximum 7.0m in diameter and 0.3m in height of medium-sized stone, only the original rim of the cairn remains, the centre having been removed. There is a small upcast heap to the north-west of the cairn but it does not contain enough material to account for the disturbance as a whole.

1614 - Cairn; Bronze Age; 427625,375764;Maximum 9.8m in diameter and 0.5m in height of large and medium-sized stone. A large central robber pit has exposed natural stone slabs at ground level. There are two upcast heaps and isolated stones scattered nearby to east and west.

1615 - Cairn; Bronze Age; 427645,375740;Maximum 9.0m in diameter and 0.6m in height of medium-sized stones. There is a large area of disturbance in the centre of the cairn with upcast thrown onto the original rim of the cairn, possibly obscuring the true shape and size of the mound.

1616 - Cairn; Bronze Age; 427652,375729;2.9m in diameter and 0.3m in height of medium-sized stone.

1617 - Cairn/Possible Cairn; Bronze Age; 427637,375718;Irregular cairn of medium-sized stone, 5.0m x 9.2m and 0.6m in height. Oval cairn with probable addition to the south-west. However, since both stone accumulations are of the same height it is difficult to determine whether or not this is a single feature.

1618 - Cairn; Bronze Age; 427662,375707;3.0m x 6.0m and 0.4m in height of medium-sized stone.

1619 - Cairn; Bronze Age; 427684,375713;Maximum 6.4m in diameter and 0.6m in height of medium-sized stone.

1620 - Cairn; Bronze Age; 427689,375723;Maximum 3.0m in diameter and 0.4m in height of medium-sized stone. There is a small central pit containing a metal spade blade and broken wooden-handled trowel apparently no more than approximately 20 years in situ. The small hole that contains these has now been backfilled with the loose upcast comprising 4 stones.

1621 - Linear Clearance; Bronze Age; 427674,375749;427669,375743;Area of medium-sized clearance stone 3.2m x 8.3m and 0.3m in height, with a military pit (2706) at one end.

1622 - Cairn; Bronze Age; 427659,375740;0.3m in height of large and medium-sized stone.

1623 - Cairn; Bronze Age; 427722,375795;2.2m in diameter and 0.2m in height of medium-sized stone, masked.

1624 - Cairn; Bronze Age; 427716,375800;Maximum 4.0m in diameter and 0.4m in height of medium-sized stone, masked.

1625 - Possible Cairn; Bronze Age; 427738,375799;2.6m in diameter and 0.2m in height, with minimal stone content.

1626 - Stone Circle/Excavation Trench; Bronze Age/Modern; 427749,375821;Barbrook II stone circle. A heavily restored embanked stone circle, the bank of which is 0.4m in height, the inner face of which is a vertical-sided drystone wall. The circle consists of ten irregularly spaced orthostats with an entrance to the north-east 1.0-1.5m in width. In the interior is a small cairn with kerb (1627) and nearby a ruined cist (1628). The whole lies within a modern excavation trench which has now been backfilled.

1627 - Cairn; Bronze Age; 427746,375819;Restored cairn of 1.9m in diameter and 0.2m in height of small and medium-sized stone within Barbrook II stone circle (1626).

1628 - Cist/Cup and Ring Carving; Bronze Age; 427748,375818;Four stones define the approximately rectangular area of the cist within Barbrook II stone circle (1626). Another stone - the displaced capstone - is carved with rock art.

1629 - Spoil Mound; Modern; 427762,375824;Low excavation spoil mound partly removed during the reconstruction of the Barbrook II stone circle (1626).

1630 - Spoil Mound; Modern; 427758,375833;Low excavation spoil mound associated with the Barbrook II stone circle (1626).

1631 - Cairn; Bronze Age; 427721,375849;Irregular cairn of medium-sized stone, 5.0m in diameter and 0.2m in height. The centre of the cairn has been disturbed and material extending to the east of the cairn may be explained as upcast from this disturbance.

1632 - Cairn; Bronze Age; 427716,375809;1.0m x 2.5m and 0.2m in height, of large stones.

1633 - Cairn; Bronze Age; 427698,375832;Maximum 2.8m in diameter and 0.2m in height, of large stones.

1634 - Cairn; Bronze Age; 427689,375828;Maximum 4.3m in diameter and 0.4m in height, of large stones.

1635 - Cairn; Bronze Age; 427684,375819;Maximum 3.3m in diameter and 0.5m in height, of

large stones.

1636 - Cairn; Bronze Age; 427681,375811;2.0m x 2.9m and 0.5m in height, of large stones.

1637 - Pit; Modern; 427683,375811;1.1m x 1.4m and 0.2m in depth, associated with military activity c.1939-45.

1638 - Cairn; Bronze Age; 427674,375795;Maximum 3.0m in diameter and 0.3m in height, of large stones.

1639 - Cairn; Bronze Age; 427647,375768;2.8m in diameter and 0.3m in height of large and medium- sized stones. The southern half of the cairn has been largely removed.

1640 - Quarry; Post Medieval; 427656,375765;0.2m in depth.

1641 - Cairn; Bronze Age; 427654,375759;Maximum 7.1m in diameter and 0.8m in height of large and medium-sized stones. The centre of the cairn has been robbed/disturbed.

1642 - Pit; Modern; 427657,375757;1.0m x 2.2m, with material banked-up against the adjacent cairn, possibly associated with military activity c.1939-45.

1643 - Cairn; Bronze Age; 427638,375779;7.5m in diameter and 0.3m in height of large and medium- sized stone. The centre of the cairn has been disturbed and it is difficult to distinguish between the remains of the original cairn and stony upcast deposited around the central disturbance.

1644 - Cairn; Bronze Age; 427661,375859;3.5m in diameter and 0.4m in height of large and medium- sized stone.

1645 - Pit; Modern; 427651,375869;0.5m x 0.6m and 0.1m in depth and backfilled with stone. Associated with military activity c.1939-45.

1646 - Cairn; Bronze Age; 427657,375870;3.0m x 4.9m and 0.5m in height of large and medium-sized stone.

1647 - Cairn; Bronze Age; 427656,375902;2.0m in diameter and 0.1m in height with some stone content beneath the soil. The cairn is only visible because it is situated within an area of burnt heather.

1648 - Cairn; Bronze Age; 427691,375889;4.9m in diameter and 0.4m in height of large stone.

1649 - Possible Cairn; Bronze Age; 427699,375865;3.3m in diameter and 0.1m in height, of large stone, possibly chucked stone around an area of natural outcrop.

1650 - Possible Earthen Bank; Bronze Age; 427702,375873;427700,375870;1.6m x 3.9m and 0.3m in height, apparently earthen in content.

1651 - Possible Cairn; Bronze Age; 427712,375861;A large pit surrounded in upcast 0.2m in height - probably the remains of a disturbed cairn although none of the original structure appears to survive.

1652 - Pit; Modern; 427701,375938;Pit with a small adjacent mound 0.3m in height, probably associated with military activity c.1939-45.

1653 - Mound; Natural; 427694,375980;Earthen mound maximum 4.0m in diameter and 0.2m

in height, possibly natural.

1654 - Possible Cairn; Bronze Age; 427688,375986;2.0m x 4.2m.

1655 - Mound; Natural; 427729,375927;Earth mound 2.2m x 4.6m and 0.1m in height, unknown date or function - possibly natural.

1656 - Lynchet; Bronze Age; 427548,375530;427545,375540;Heather-covered lynchet, 0.3-0.4m in height and c.10m in length, stony at south-east end with cairn 1657 at north end and cairn 1659 at south end.

1657 - Cairn; Bronze Age; 427545,375538;1.0m x 1.8m and 0.1-0.2m in height at north end of lynchet 1656.

1658 - Pit; Modern; 427547,375541;0.6m square and 0.1m in depth. Associated with military activity c.1939-45.

1659 - Cairn; Bronze Age; 427548,375529;1.6m x 2.6m and 0.1m in height at south end of lynchet 1656.

1660 - Lynchet; Bronze Age; 427548,375520;427548,375525;Stony lynchet 0.3m in height and c.4.5m in length.

1661 - Possible Mound; Post Medieval; 427520,375543;U-shaped earthen platform, 2.0m x 2.2m and 0.1m in height. Not Bronze Age in appearance, possibly natural.

1724 - Possible Lynchet; Bronze Age; 427515,375509;427510,375500;0.2m in height and c.10m in length.

2095 - Cairn; Bronze Age; 427821,375507;Cairn of medium-sized stones 0.9m x 1.8m and 0.3m in height.

2115 - Possible Hollow Way; Post Medieval; 427700,375510;427695,375511;Slight parallel scarps at the head of a natural flush.

2117 - Bank; Modern; 427675,375550;427712,375590;Substantial irregular bank of earth and stones c.54m in length, maximum 2.8m wide and c.1m in height. Similar to bank 2118. Associated with recent Water Board activity.

2118 - Bank; Modern; 427668,375558;427705,375595;Substantial bank of earth and stones c.54m in length, maximum 5.0m wide and c.1m in height. Similar to bank 2117. Associated with recent Water Board activity.

2119 - Bullet Scars; Modern; 427648,375589;Single large boulder with a few clear bullet scars on its south-east face.

2120 - Slit Trenches; Modern; 427625,375642;Loose group of thirteen slit trenches, some with spoil, averaging 0.5m x 1.2m and 0.2m in depth. Associated with military activity c.1939-45.

2121 - Track; Post Medieval; 427673,375618;427701,375507;Terraced trackway maximum 2.0m in width and 0.4m in height (downslope). Overlain by Modern banks 2117 and 2118, and by an area of disturbance 2143. No evidence of a buried hardcore surface.

2122 - Quarry; Post Medieval; 427691,375596;Depth 1.0m.

2144 - Quarry; Post Medieval; 427716,375548;5.5m square and 0.5m in depth.

2145 - Earthen Bank; Post Medieval or Modern; 427750,375571;427733,375556;Very low scarp or earthen bank 0.7m wide and 0.06m in height, traceable for a distance of 22m. May be associated with the adjacent fire break (2126).

2146 - Bullet Scars; Modern; 427582,375605;Single bullet scarred boulder. Associated with military activity c.1939-45.

2147 - Bullet Scars; Modern; 427593,375563;Single bullet scarred boulder. Associated with military activity c.1939-45.

2148 - Bullet Scars; Modern; 427551,375583;Single bullet scarred boulder. Associated with military activity c.1939-45.

2237 - Bank; Modern; 427737,375550;427696,375497;Bank of earth and stone c.22m in length, 3.0m wide and 0.4m in height. Similar to bank 2128. Perpetuates line of scarp 2126, and may continue further downslope. Associated with recent Water Board activity.

2700 - Possible Earthen Bank; Bronze Age; 427581,375508;427574,375507;2.8 x 7.2m and 0.3m in height, predominantly earthen with some stone content. May be natural.

2706 - Pit; Modern; 427670,375743;Small pit 0.1m in depth associated with military activity, cut into linear clearance 1621

Sheet 10

2760 - Hollow Way; Post Medieval; 426590,376195;426285, 375927; Wide band of braided hollow ways, in part appear to pre-date 2761. Continues outside survey area.

Sheet 11

1511 - Cairn; Bronze Age; 426600,376139;Maximum 2.8m in diameter and 0.2m in height, of medium-sized stone. Adjacent hollow way diverts around to north of cairn.

1512 - Cairn; Bronze Age; 426591,376133;Maximum 1.9m in diameter and 0.2m in height, of medium-sized stone dumped on edge of area of stony ground.

1513 - Cairn; Bronze Age; 426594,376125;Pile of medium-sized stones, 1.4 x 2.3m.

1514 - Clearance Stone; Bronze Age; 426603,376148;Area of naturally stony ground with cleared stone dumped on it and concentrations of stone around edge.

1515 - Cultivation Edge; Bronze Age; 426570,376127;426577,376158;Significant change in height with some clearance stone along it. Broken by hollow ways.

1516 - Linear Clearance; Bronze Age; 426572,376141;3.7 x 1.2m and 0.2m in height of medium-sized stone with an upright slab at west side.

1517 - Cairn; Bronze Age; 426580,376148;Irregular in shape, 2.8m x maximum 1.3m and 0.2m in height with an area of clear ground to the east.

1518 - Cairn; Bronze Age; 426577,376151;Maximum 1.8m in diameter and 0.2m in height, of medium-sized stone. Situated on edge of stony ground.

2144 - Quarry; Post Medieval; 427716,375548;5.5m square and 0.5m in depth.

2145 - Scarp or Bank; Post Medieval or Modern; 427750,375571,427733,375556;Very low scarp or earthen bank 0.7m wide and 0.06m in height, traceable for a distance of 22m. May be associated with the adjacent fire break (2126).

2146 - Bullet Scars; Modern; 427582,375605;Single bullet scarred boulder. Associated with military activity c.1939-45.

2147 - Bullet Scars; Modern; 427593,375563;Single bullet scarred boulder. Associated with military activity c.1939-45.

2148 - Bullet Scars; Modern; 427551,375583;Single bullet scarred boulder. Associated with military activity c.1939-45.

2237 - Bank; Modern; 427737,375550,427696,375497;Bank of earth and stone c.22m in length, 3.0m wide and 0.4m in height. Similar to bank 2128. Perpetuates line of scarp 2126, and may continue further downslope. Associated with recent Water Board activity.

2700 - Possible Earthen Bank; Bronze Age; 427581,375508,427574,375507;2.8 x 7.2m and 0.3m in height, predominantly earthen with some stone content. May be natural.

2706 - Pit; Modern; 427670,375743;Small pit 0.1m in depth associated with military activity, cut into linear clearance 1621

Sheet 10

2760 - Hollow Way; Post Medieval; 426590,376195,426285, 375927; Wide band of braided hollow ways, in part appear to pre-date 2761. Continues outside survey area.

Sheet 11

1511 - Cairn; Bronze Age; 426600,376139;Maximum 2.8m in diameter and 0.2m in height, of medium-sized stone. Adjacent hollow way diverts around to north of cairn.

1512 - Cairn; Bronze Age; 426591,376133;Maximum 1.9m in diameter and 0.2m in height, of medium-sized stone dumped on edge of area of stony ground.

1513 - Cairn; Bronze Age; 426594,376125;Pile of medium-sized stones, 1.4 x 2.3m.

1514 - Clearance Stone; Bronze Age; 426603,376148;Area of naturally stony ground with cleared stone dumped on it and concentrations of stone around edge.

1515 - Cultivation Edge; Bronze Age; 426570,376127,426577,376158;Significant change in height with some clearance stone along it. Broken by hollow ways.

1516 - Linear Clearance; Bronze Age; 426572,376141;3.7 x 1.2m and 0.2m in height of medium-sized stone with an upright slab at west side.

1517 - Cairn; Bronze Age; 426580,376148;Irregular in shape, 2.8m x maximum 1.3m and 0.2m in height with an area of clear ground to the east.

1518 - Cairn; Bronze Age; 426577,376151;Maximum 1.8m in diameter and 0.2m in height, of medium-sized stone. Situated on edge of stony ground.

1519 - Linear Clearance; Bronze Age; 426576,376160; Well-formed crescent-shaped cairn c.4.1 x 1.6m and 0.3m in height, of medium-sized stone. Not masked.

1520 - Cairn; Bronze Age; 426588,376158; Maximum 2.9m in diameter and 0.2m in height, of small and medium-sized stone. Cut by adjacent hollow way.

1521 - Possible Bell Pit; Post Medieval; 426620,376190; Pit 1.7m square and 0.3m in depth with low mound of spoil on east side.

1522 - Linear Clearance; Bronze Age; 426598,376174; Linear in form, 4.9m x maximum 2.0m and 0.3m in height, of mostly small stone. May alternatively be two conjoined cairns.

1523 - Cairn; Bronze Age; 426596,376177; Maximum 2.2m in diameter and 0.2m in height, of medium-sized stone.

1524 - Clearance Stone/Possible House Site; Bronze Age; 426597,376183; Curvilinear area of clearance stone, c.15m in length and 1.2m wide, with discrete area of stone at north end, 1.2 x 3.8m, may suggest a house site but more likely a plot edge. Disturbed by slight hollow ways.

1525 - Cairn; Bronze Age; 426561,376141; Maximum 2.8m in diameter and 0.2m in height, of medium-sized stone.

1526 - Cairn; Bronze Age; 426562,376136; 1.1 x 3.2m and 0.2m in height, of medium-sized stone.

1527 - Linear Clearance; Bronze Age; 426561,376129; 4.0 x 1.6m and 0.3m in height, of medium-sized stone.

1528 - Linear Clearance; Bronze Age; 426554,376124; 5.0 x 1.5m and 0.2m in height, turf covered.

1529 - Possible Linear Clearance; Bronze Age; 426548,376114; 5.2 x 1.5m small depression on west side may indicate it is simply spoil from a pit.

1530 - Cairn; Bronze Age; 426561,376110; Sub-circular cairn maximum 3.5m in diameter and 0.3m in height, of medium-sized stone.

1531 - Cairn; Bronze Age; 426565,376112; Sub-circular cairn maximum 3.1m in diameter and 0.3m in height, of medium-sized stone.

1532 - Cairn; Bronze Age; 426571,376115; Low triangular cairn of small stones, 4.0m x maximum 2.5m and 0.1m in height. Cut by hollow way to south.

1533 - Cairn; Bronze Age; 426557,376103; 1.5 x 3.0m and 0.2m in height. Mostly small stone.

1534 - Possible Cairn; Bronze Age; 426570,376126; Low concentration of a few medium-sized stones c.1.6m in diameter.

1535 - Mound; Natural; 426551,376098; Hemi-spherical mound 0.9 x 2.4m and 0.3m in height of mixed earth and small stones, possibly natural. Cut by hollow way to south.

1536 - Mound; Natural; 426526,376052; Low mound 1.8 x 2.9m and 0.2m in height of mixed earth and small stones - similar to mound 1535. Possibly natural.

1538 - Mound; Natural; 426579,376085; Low irregular mound of earth and small stones 0.9 x 4.1m, exposed by adjacent hollow way, similar to mound 1535, could be natural.

1539 - Linear Clearance; Bronze Age; 426584,376118;426587,376121;1.7 x 4.9m and 0.1-0.2m in height, of medium-sized stone.

1540 - Clearance Stone; Bronze Age; 426589,376121;Small pile of small and medium-sized stone 0.6m in diameter.

2743 - Hollow Way; Post Medieval; 426618,376068;426636,376070;Slight hollow way crosses (and post-dates) adjacent routes. May be heading in the direction of the main swathe of hollow ways to the west.

2744 - Hollow Way; Post Medieval; 426639,376074;426659,376117;Narrow route runs at an angle from main swathe of hollow ways.

2745 - Hollow Way; Post Medieval; 426630,376063;426673,376146;Narrow route runs at an angle from main swathe of hollow ways, and is cut by hollow way 2743 to the south.

2759 - Hollow Way; Post Medieval; 426694,376151;426500,376029;Broad swathe of hollow ways. Appears to pre-date adjacent band of hollow ways (2758).

Sheet 12

2229 - Possible Shooting Butt or Military Fieldwork; Post Medieval or Modern; 427480,376016; Circular depression with a narrow channel leading off it, post-dates adjacent hollow ways. A line of features to SSW (1057, 1169, 2220), some more obviously shooting butts. However, they could have military origins or associations.

2230 - Mine; Post Medieval; 427422,376091;Regular rectangular channel cut into the natural slope to a depth of 0.6m, with a spoil bank (0.1m in height) along the north side.

2231 - Stony Spread; Natural; 427439,376039;427449,376048;Irregular spread of stones, c.15.0m in length and average 2.0m wide exposed by hollow ways. Not artificial.

2386 - Cairn; Bronze Age; 427374,376064;Maximum 4.9m in diameter and 0.3m in height, of medium-sized stone.

2387 - Pit; Modern; 427351,376054;1.3 x 1.4m and 0.3m in depth, associated with military activity c.1939-45.

2388 - Cairn; Bronze Age; 427396,376057;Sub-circular cairn c.5.0m in diameter and 0.5m in height, of medium-sized stone. Robbed in centre and on south-east side.

2389 - Lynchet; Bronze Age; 427394,376053;427394,376054;0.2m in height.

2390 - Cairn; Bronze Age; 427393,376051;Amorphous cairn maximum 3.0m in diameter and 0.2m in height.

2391 - Cairn; Bronze Age; 427381,376046;Sub-circular cairn c.3.1m in diameter and 0.2m in height, of medium-sized stone.

2392 - Possible Cairn; Bronze Age; 427378,376040;Low amorphous feature, possibly a cairn, maximum 1.7m in diameter and 0.1m in height, of medium-sized stone.

2393 - Possible Cairn; Bronze Age; 427378,376038;1.2m in diameter and 0.1m in height, of medium-sized stone.

2394 - Possible Hollow; Bronze Age; 427384,376037; Horseshoe-shaped depression c.5.0m wide and 0.1-0.3m in depth.

2395 - Cairn; Bronze Age; 427382,376033; Amorphous cairn of mostly medium-sized stone around one earthfast boulder, maximum 3.8m in diameter and 0.3m in height.

2396 - Cairn; Bronze Age; 427386,376025; Discrete flat-topped cairn of medium-sized stone, maximum 2.5m in diameter and 0.2m in height.

2397 - Cairn or Pile of Stones; Bronze Age/Modern; 427432,376034; Discrete cluster of stones 0.2m high visible between hollow ways. This is either a prehistoric feature or has been cleared from the hollow way.

2398 - Pit; Post Medieval; 427203,376020; Sub-circular pit maximum 5.0m in diameter and 0.6m in depth, cuts feature 2399.

2399 - Hollow; Post Medieval; 427200,376019; Linear-like hollow 0.4m in depth, cut by pit 2398.

2400 - Pit; Post Medieval; 427198,376015; 1.7 x 2.2m and 0.4m in depth.

2401 - Sheep Lea; Post Medieval; 427184,376041; 427170,376038; Stone shelter wall 0.3m in height.

2402 - Linear Clearance or Shelter; Bronze Age or Post Medieval; 427108,376027; Linear stone feature 4.9 x 0.9m and 0.6m in height. Could be Bronze Age linear clearance or a Post Medieval shelter wall.

2403 - Mound; Natural; 427158,376074; Large peat mound c.5.6m in diameter and 0.8m in height, may be natural.

2799 - Cairn or Pile of Stones; Bronze Age/Post Medieval; 427428,376029; 2.3m x 1.2m and 0.2m high. May be no more than a small collection of stones from hollow way clearance but it is on a line between 2800 and 2397.

2800 - Linear Clearance; Bronze Age; 427416,376012; 427423,376022; 0.3m high, slightly disjointed and disturbed by hollow way to east.

Sheet 13

565 - Hollow Way; Post Medieval; 427542,376129; 427500,376095; Multiple braided routes.

1226 - Quarry; Modern; 427563,376149; Substantial area quarried for the reservoir embankment to a depth of 1.5m-2.5m (upslope).

1279 - Possible Cairn, Burial Cairn or Pile of Stones; Bronze Age/Modern; 427579,376168; Could alternatively be stony upcast associated with the adjacent pit (see 1283). If Bronze Age in date, its isolated location may suggest it is a funerary structure.

1281 - Possible Cairn or Burial Cairn; Bronze Age; 427542,376194; Sub-circular cairn 3.5m in diameter and 0.2m in height. Its isolated location may suggest it is a funerary structure. May be fortuitous.

1282 - Burial Cairn or Cairn; Bronze Age; 427565,376194; Cairn, 6.0m x 5.0m across and 0.2m in height with a disturbance at east side. Its isolated position may suggest it is a funerary structure rather than a clearance feature.

1283 - Pits; Modern; 427584,376171;Three rectangular pits c.0.8m x 0.7m and 0.2m in depth. To the north of the south-westernmost pit is a small stony mound which could be an adjacent Bronze Age cairn (see 1279) or upcast associated with the pit.

1284 - Hollow Way; Post Medieval; 427585,376155;427713,376254;0.5m deep with stony sides. Contains paved path 1289.

1285 - Hollow Way; Post Medieval; 427698,376285;427500,376174;Braided hollow way survives in places to a maximum depth of 0.5m but elsewhere is less well-defined.

1287 - Piles of Stone; Post Medieval; 427675,376232;Small cairn of medium-sized to large stone, 1.3m in diameter and 0.2m in height. No soil in interstices. Associated with hollow way 1284.

1288 - Hollow Way; Post Medieval; 427689,376275;427641,376216;Discontinuous hollow way, 0.4m in depth.

1289 - Paved Path; Post Medieval; 427625,376186;427600,376169;Single line of gritstone slabs, mostly buried, within hollow way 1284.

1290 - Pit; Modern; 427616,376189;Rectangular pit 0.8m x 1.1m and 0.2m in depth with stony upcast to side, 0.2m in height.

1291 - Hollow Way; Post Medieval; 427703,376281;427699,376275;0.4m in depth.

1292 - Hollow Way; Post Medieval; 427706,376275;427699,376272;0.4m in depth.

1293 - Hollow Way; Post Medieval; 427710,376264;427703,376261;0.4m in depth.

1294 - Burial Cairn, Cairn or Pile of Stones; Bronze Age/Post Medieval; 427701,376265; Sub-circular cairn with maximum diameters of 0.9m and 1.8,0.1m in height. This feature lies at a distance from other agricultural features, hence Bronze Age funerary or later period interpretations should also be considered.

1662 - Possible Slit Trench; Modern; 427910,376024;0.5m x 1.8m and 0.2m in depth, may be associated with military activity c.1939-45.

1663 - Slit Trench; Modern; 427914,376019;1.1m x 2.0m and 0.3m in depth. Associated with military activity c.1939-45.

1664 - Pit; Modern; 427922,376019;Irregular pit 0.2m in depth, associated with military activity c.1939-45.

1665 - Pit; Modern; 427946,376019;0.9m x 1.2m and 0.2m in depth. Associated with military activity c.1939-45.

1666 - Pit; Modern; 427944,376024;1.4m x 2.2m and 0.4m in depth. Associated with military activity c.1939-45.

1667 - Pit; Modern; 427947,376042;1.1m x 1.9m and 0.4m in depth. Associated with military activity c.1939-45.

1668 - Pit; Modern; 427951,376007;T-shaped pit 0.4m in depth. Associated with military activity c.1939-45.

1669 - Pit; Modern; 427956,376012;1.2m x 2.2m and 0.3m in depth. Associated with military

activity c.1939-45.

1670 - Pit; Modern; 427960,376013;0.9m x 1.4m and 0.3m in depth. Associated with military activity c.1939-45.

1671 - Pit; Modern; 427921,376024;L-shaped pit 0.4m in depth. Associated with military activity c.1939-45.

1672 - Pit; Modern; 427921,376030;1.0m x 1.4m and 0.5m in depth. Associated with military activity c.1939-45.

1673 - Pit; Modern; 427918,376033;0.9m x 1.9m and 0.2m in depth. Associated with military activity c.1939-45.

1674 - Pit; Modern; 427982,376027;0.4m x 1.2m and 0.4m in depth. Associated with military activity c.1939-45.

1675 - Pit; Modern; 427982,376023;0.6m x 1.5m and 0.4m in depth. Associated with military activity c.1939-45.

1676 - Pit; Modern; 427978,376023;L-shaped pit 0.3m in depth. Associated with military activity c.1939-45.

1677 - Pit; Modern; 427971,376025;0.6m x 1.7m and 0.4m in depth. Associated with military activity c.1939-45.

1678 - Pit; Modern; 427958,376032;0.9m x 2.2m and 0.6m in depth. Associated with military activity c.1939-45.

1679 - Pit; Modern; 427959,376025;0.4m x 1.2m and 0.3m in depth. Associated with military activity c.1939-45.

1680 - Pit; Modern; 427965,376012;1.1m x 2.0m and 0.4m in depth. Associated with military activity c.1939-45.

1681 - Pit; Modern; 427997,376002;Foxhole 0.6m square and 0.2m in depth. Associated with military activity c.1939-45.

1682 - Pit; Modern; 427991,376026;0.4m x 1.0m. Associated with military activity c.1939-45.

1683 - Pit; Modern; 427979,376011;1.5m x 1.8m and 0.5m in depth. Associated with military activity c.1939-45.

1684 - Pit; Modern; 427970,376011;0.5m x 0.6m and 0.2m in depth. Associated with military activity c.1939-45.

1685 - Bullet Scars; Modern; 427939,376088;Area of bullet scarred rocks. Associated with military activity c.1939-45.

1686 - Hollow Way; Post Medieval; 427924,376096;427924,376105;0.2m in depth.

1687 - Pit; Modern; 427918,376054;0.9m x 1.1m and 0.2-0.3m in depth. Associated with military activity c.1939-45.

1688 - Hollow Way; Post Medieval; 427890,376120;427908,376132;0.3m in depth.

1689 - Pile of Stones; Post Medieval; 427903,376136;Pile of large and medium-sized stones, 2.3m x 4.0m and 0.5-0.6m in height with no accumulated earth content. Clearly not a Bronze Age feature, possibly clearance from- or marker for adjacent hollow ways.

1690 - Hollow Way; Post Medieval; 427836,376127;427904,376139;0.3-0.4m in depth.

1691 - Stone Bank or Shelter; Post Medieval; 427884,376120;Large and medium-sized stones piled in linear fashion 1.0m x 3.0m and 0.5-0.6m in height, may represent waste stone from adjacent quarry deliberately stacked to create a wind break.

1692 - Hollow Way; Post Medieval; 427855,376115;427837,376115;0.3m in depth.

1693 - Posthole; Modern; 427826,376061;Modern post hole 0.4m in diameter and 0.7m in depth. A large wooden stake was noted lying on the ground nearby.

1694 - Cairn or Burial Cairn; Bronze Age; 427835,376019;Cairn of small and medium-sized stones, maximum 1.0m in diameter and 0.2-0.3m in height. The isolated location may suggest this is a funerary structure.

1695 - Hollow Way; Post Medieval; 427669,376028;427597,376026;Braided hollow ways 0.2m in depth. Appears to have been mechanically altered or widened.

1696 - Quarry; Post Medieval; 427593,376026;0.5m in depth. Probably dug to provide material for adjacent track.

1697 - Military Fieldwork; Modern; 427589,376015;Platform 0.9m x 3.0m terraced into the natural slope to a depth of 0.3m (to upslope). Associated with military activity c.1939-45.

1698 - Quarry; Post Medieval; 427623,376082;4.0m in depth. Probably dug in association with adjacent reservoir embankment.

1699 - Pit; Modern; 427803,376113;1.8m square and 0.2m in depth. Associated with military activity c.1939-45.

1700 - Pile of Stones; Post Medieval; 427822,376152;Linear pile of stones with no apparent form, 0.7m x 3.6m and 0.2m in height. Probably associated with pipeline 1711.

1701 - Pile of Stones; Post Medieval; 427828,376164;Pile of stones 1.2m x 1.8 and 0.3m in height at south end of pipeline 1711, does not appear to be a Bronze Age cairn and may well be associated with the construction of the pipeline.

1703 - Hollow Way; Post Medieval; 427814,376231;427647,376127;Braided hollow way 0.2m in depth.

1704 - Possible Cairn; Bronze Age; 427768,376147;Pile of three small stones 0.6m in diameter and 0.1m in height.

1705 - Cairn or Burial Cairn; Bronze Age; 427689,376093;Heather-covered cairn 2.5m in diameter and 0.3m in height. The isolated location of cairns 1705/1706 may suggest they are funerary structures.

1706 - Cairn or Burial Cairn; Bronze Age; 427697,376096;Maximum 3.0m in diameter and 0.3m in height, heather-covered. The isolated location of cairns 1705/1706 may suggest they are funerary structures.

1707 - Hollow Way; Post Medieval; 427653,376094;427644,376100;0.3m in depth, joins main swathe of hollow ways (1703).

1708 - Hollow Way; Post Medieval; 427673,376082;427640,376099;0.5m maximum depth, joins main swathe of hollow ways (1703).

1709 - Bridge; Post Medieval; 427880,376327;The bridge has a simple parapet of gritstone blocks 0.2m in height and a single arch. The stream to either side of the bridge is retained by drystone walling which post-dates the bridge.

1710 - Quarry; Post Medieval; 427883,376311;3.0m in depth (upslope), cut into natural slope to obtain building material for the trackway.

1711 - Pipeline; Post Medieval; 427828,376166;427908,376276;Slight terracing 2.1m in width indicates the position of a buried pipeline.

1712 - Vent Pipe; Post Medieval; 427881,376243;Cast iron vent pipe 0.19m in diameter and standing 0.36m above ground level.

1713 - Pit; Modern; 427896,376230;1.3m x 1.7m and 0.3m in depth with associated upcast 0.3m in height, may be associated with military activity c.1939-45.

1714 - Slit Trench; Modern; 427871,376209;Two slit trenches 0.7m 1.7m and 0.3m maximum depth.

1715 - Pit; Modern; 427867,376212;1.8m x 2.0m and 0.2m in depth, probably associated with military activity c.1939-45.

1716 - Slit Trench; Modern; 427853,376138;0.5m x 1.9m and 0.2m in depth, associated with military activity c.1939-45.

1717 - Bridge; Post Medieval; 427706,376190;Bridge with a single arch.

1718 - Pile of Stones; Post Medieval; 427705,376246;1.1m x 3.1m and 0.2m in height, clearance from adjacent hollow way (1284).

1719 - Bridge; Post Medieval; 427720,376255;Site of former clapper bridge. On either side of the stream the path ends in stone supports although the clapper stone is now missing.

1720 - Reservoir Earthwork; Post Medieval; 427671,376194;427651,376182;Regular bank c.5m wide, c.25m in length, 0.3m in height (upslope) and 1.8m in height (downslope), contemporary with or later than the Barbrook reservoir.

1721 - Sluice; Post Medieval; 427615,376091;Concrete-lined sluice associated with the Barbrook reservoir.

2225 - Drain; Post Medieval; 427511,376036;427517,376033;Overflow from reservoir conduit above has eroded the natural slope at this point.

2226 - Drain; Post Medieval; 427517,376032;427540,375999;0.5m wide and 0.6m in depth.

2228 - Possible Hollow Way; Post Medieval; 427576,376026;427569,376025;Depth 0.1m.

2232 - Drain; Post Medieval; 427546,376096;427553,376090;Associated with reservoir conduit above.

2233 - Drain; Post Medieval; 427544,376131;427548,376116;Stream course, artificially deepened or possibly diverted to feed reservoir conduit.

2235 - Pit; Modern; 427537,376112;1.0m x 1.5m and 0.4m in depth. Associated with military activity c.1939-45.

2236 - Hollow Way; Post Medieval; 427587,376041;427572,376030;Terraced into the natural slope at a width of 0.9m.

2701 - Quarry; Post Medieval; 427720,376180;Scoop into hillside for hardcore for the adjacent track - not a stone quarry.

2707 - Slit Trench; Modern; 427934,376023;Slit trench 0.6 x 1.0m and 0.5m in depth, associated with military activity c.1939-45.

2718 - Hollow Way; Post Medieval; 427621,376012;427586,376008;Narrow route 0.2m in depth.

2719 - Hollow Way; Post Medieval; 427860,376165;427849,376159;Short section of hollow way diagonally crossing crest of natural slope.

2720 - Hollow Way; Post Medieval; 427905,376150;427892,376142;Short section of hollow way above natural slope, branches off from hollow way 1690.

2721 - Hollow Way; Post Medieval; 427921,376118;427905,376103;Section of narrow hollow way 0.2m in depth.

2722 - Hollow Way or Reservoir Earthwork; Post Medieval; 427632,376176;427583,376142;Scarp terraces into base of natural slope, could be side of former hollow way or created when the reservoir was built.

2723 - Hollow Way; Post Medieval; 427645,376012;427596,376000;Narrow sinuous route 0.2m in depth.

2801 - Reservoir; Post Medieval; 427630,376140;Little Barbrook Reservoir, of 19th century date.

2802 - Dam; Post Medieval; 427570,376123;427605,376080;Earthen dam with stepped overflow at centre retained by stone walls. Retains Little Barbrook Reservoir. Of 19th century date.

2805 - Quarries; Post Medieval; 427900,376100;The scarp slope and land below has a large number of small quarry pits (also see 1722 (Sheet15)).

Sheet 15

1461 - Hollow Way; Post Medieval; 428059,375551;427830,375442;Very slight, braided, hollow way, 0.2m deep max.

1722 - Stone Bank or Shelter; Post Medieval; 428037,375978;428032,375978;Irregular rubble bank c.5.5m in length and 0.5m maximum height, built between two earthfast boulders incorporating a distinct angle change. Some of the component stone is angular and quarried in appearance and there are signs of crude coursing within the bank. Adjacent quarry to north-west side. It is unclear if this is stacked quarry waste or a ruined quarrymans shelter.

1723 - Pipeline; Post Medieval; 428216,375776;428134,375820;Visible as a bank, c.52m in length and 0.2m maximum height, and a slight ditch. Large fragments of pipe were noted on the ground surface nearby.

2713 - Hollow Way; Post Medieval; 428053,375959,428068,375972; Hollow way divides into two routes down natural slope.

2714 - Hollow Way; Post Medieval; 428049,375964,428053,375977; Section of narrow hollow way visible on natural scarp.

2715 - Possible Hollow Way; Post Medieval; 428259,375726,428227,375697; Slight feature, may be a section of hollow way or is fortuitous.

2716 - Hollow; Natural; 428004,375563; Shallow sub-circular hollow, maximum 5.3m in diameter, appears to be a natural feature - probably a former pond which has now dried-up.

Sheet 16

1476 - Hollow Way; Post Medieval; 428027,375136,428022,375110; Narrow route leading to area of stone getting on natural slope.

2347 - Possible Slit Trench; Modern; 428080,375163; Linear hollow 0.8m x 3.8m and 0.2m in depth, could be a double slit trench or less probably created by stone removal.

2348 - Quarry; Post Medieval; 428083,375175; 0.3m in depth at the east end and 1.0m in depth at the west end.

2350 - Possible Cairn; Bronze Age; 428093,375225; Low sub-circular mound of large stone slabs and medium-sized stones, 3.1m x 4.4m and 0.1-0.3m in height, grass-covered and robbed at south-east end.

2351 - Possible Clearance Stone; Bronze Age; 428059,375307; Two small areas of large and medium-sized stones, could represent clearance stone and may be associated with possible clearance stone 2352.

2352 - Possible Clearance Stone; Bronze Age; 428056,375313; Single large earthfast stone with a few adjacent scattered medium-sized stones, 1.2m x 4.0m. Could represent clearance stone with a natural element, and may be associated with possible clearance stone 2351.

2353 - Possible Cairn; Bronze Age; 428023,375341; Maximum 3.0m in diameter and 0.4m in height, group of stones against an earthfast boulder - may be natural.

2354 - Cairn; Bronze Age; 428029,375343; Maximum 2.4m in diameter and 0.3m in height, comprising a group of three large stones with smaller turf-covered stones in between.

2355 - Cairn; Bronze Age; 428010,375354; 3.5m in diameter and 0.4m in height, large stones grouped around a single large earthfast stone slab.

2356 - Cairn; Bronze Age; 428029,375382; c.6.5m x 3.0m and 0.4m in height, discrete concentration of smaller stones at north - rest is irregular.

2357 - Cairn; Bronze Age; 428005,375404; 3.8m in diameter and 0.4m in height, comprising large stones against a large earthfast boulder.

2358 - Possible Linear Clearance; Bronze Age; 428015,375452,428004,375462; 16m in length and averaging 2-3m in width and 0.4m in height. Overlain by drystone wall/sheep lea 2359.

2359 - Sheep Lea; Post Medieval; 428013,375450;427998,375470;Partially collapsed drystone walling c.28m in length and maximum 0.5m high, possibly built as a sheep lea. Increased tumble or stone heap at west end may overlie a possible cairn (2792 (Sheet 5)) although this is far from certain (see also 2697 (sheet 5)).

2360 - Pile of Stones; Modern; 428006,375463;Group of stones probably collected together from wall tumble.

2361 - Probable Burial Cairn; Bronze Age; 428001,375481;Stone built and heavily robbed, with numerous digging scarps and islands of residual stone, survives to a maximum height of 0.5m and appears to have had a former diameter of c.12m. May have been quarried for material for the adjacent for sheep lea 2359.

2362 - Possible Cairn; Bronze Age; 428039,375484;Maximum 4.5m in diameter and 0.2m in height, heavily robbed.

2363 - Cairn; Bronze Age; 428060,375456;4.4m in diameter and 0.3m in height. Some large stones are visible.

2364 - Cairn; Bronze Age; 428061,375447;Maximum 4.7m in diameter and 0.4m in height of large stones

2365 - Possible Cairn; Bronze Age; 428063,375435;3.0m in diameter and 0.3m in height, turf and heather covered.

2366 - Cairn; Bronze Age; 428061,375414;3.0m in diameter and 0.5m in height. Large (moved) stone slabs with medium-sized stones around.

2367 - Cairn; Bronze Age; 428037,375419;2.9m in diameter and 0.3m in height, of large and medium-sized stones.

2368 - Linear Clearance; Bronze Age; 428059,375374;Irregular cairn c.9m x 3m and 0.4m in height comprising large and medium-sized stones around earthfast boulders.

2369 - Cairn; Bronze Age; 428066,375376;2.7m x 4.5m and 0.4m in height, of large and medium-sized stones.

2370 - Cairn; Bronze Age; 428063,375405;1.8m x 3.0m and 0.3m in height. Turf-covered stones around an earthfast boulder.

2371 - Cairn; Bronze Age; 428064,375400;Maximum 4.8m in diameter and 0.3m in height, of large stones.

2372 - Cairn; Bronze Age; 428078,375405;Cairn of large and medium-sized stones, 2.3m x 3.7m and 0.2m in height.

2373 - Cairn; Bronze Age; 428086,375408;Some cleared stone placed among earthfast boulders, 2.5m x 3.5m and 0.2m in height.

2374 - Cairn; Bronze Age; 428075,375421;1.7m x 2.8m and 0.3m in height, of large stones.

2375 - Clearance Stone; Bronze Age; 428078,375417;Clearance stone discernable within natural scattered surface stone.

2376 - Cairn; Bronze Age; 428071,375444;Heather-covered cairn of large stones, 3.0m x 4.2m

and 0.2m in height.

2377 - Cairn; Bronze Age; 428084,375422; Grass-covered cairn of large and medium-sized stones, maximum 3.5m in diameter and 0.2m in height.

2795 - Track; Post Medieval; 428106,375144; 427881,376325; Contour-following track with mostly sandstone brash surface. Principally associated with access to Little Barbrook and Barbrook Reservoirs. Inspection covers along its course indicate a pipe-line runs underneath. Of probable 19th century date.

Sheet 17

2341 - Pit; Modern; 427540,374956; 1.3m x 1.0m. Associated with military activity c.1939-45.

2342 - Bullet Scars; Modern; 427607,374906; Area of rocks which are bullet scarred on south-west face. Associated with military activity c.1939-45.

2343 - Pit; Modern; 427644,374975; 0.5m x 0.6m. Associated with military activity c.1939-45.

2344 - Pit; Modern; 427595,374979; 0.9m x 0.7m. North side formed by earthfast boulder. Associated with military activity c.1939-45.

Sheet 18

2531 - Pile of Stones; Modern; 426486,375495; Consolidated pile of stones, probably a hikers' cairn, 2.0 x 4.0m.

2532 - Quarry; Post Medieval; 426492,375489; Walling stone quarry.

CONCORDANCE

PREHISTORIC FEATURES

AGRICULTURAL

Cairn

Sheet 2 - 1469, 2171, 2176, 2177, 2284, 2285, 2308, 2314, 2315, 2780, 2782.

Sheet 3 - 2, 4, 566, 1355, 1364, 1371, 1372, 1379, 1383, 1387, 1389, 1393, 1407, 1409, 1410, 1411, 1728, 2595, 2600, 2602, 2609, 2612, 2616, 2620, 2621, 2630, 2637, 2639, 2641, 2642, 2643, 2650, 2651, 2652, 2658, 2659, 2662, 2663, 2664, 2667, 2670, 2671, 2672, 2673, 2686.

Sheet 4 - 15, 17, 25, 29, 35, 37, 42, 46, 93, 104, 105, 106, 107, 108, 110, 111, 112, 113, 114, 116, 118, 120, 121, 125, 127, 130, 133, 134, 135, 136, 138, 139, 142, 144, 150, 160, 172, 175, 176, 177, 204, 206, 209, 210, 214, 215, 216, 217, 219, 221, 222, 223, 227, 241, 242, 243, 246, 247, 248, 252, 253, 255, 256, 257, 259, 261, 281, 283, 284, 285, 289, 293, 295, 297, 298, 299, 300, 303, 306, 312, 315, 316, 317, 322, 327, 330, 333, 334, 349, 350, 355, 356, 357, 360, 361, 362, 365, 366, 367, 370, 371, 372, 373, 374, 378, 381, 382, 384, 388, 389, 390, 394, 397, 400, 401, 403, 405, 422, 424, 425, 427, 437, 438, 466, 467, 469, 1077, 1079, 1080, 1091, 1101, 1113, 1137, 1140, 1141, 1250, 1255, 1259, 1263, 1264, 1269, 1274, 1276, 1278, 1296, 1309, 1311, 1319, 1325, 1330, 1340, 1341, 1342, 1345, 1349, 1350, 1412, 1421, 2286, 2287, 2545, 2571, 2574, 2577, 2689, 2693, 2747, 2748, 2749.

Sheet 5 - 472, 2000, 2002, 2003, 2011, 2025, 2027, 2029, 2031, 2037, 2038, 2039, 2040, 2044, 2053, 2054, 2064, 2066, 2069, 2071, 2251, 2256, 2257, 2264, 2271, 2272, 2281.

Sheet 6 - 1554, 2496, 2498, 2501, 2502, 2503, 2504, 2514, 2518, 2520.

Sheet 7 - 2405, 2410, 2425, 2426, 2430, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2442, 2443, 2451, 2453, 2459, 2465, 2467, 2471, 2472, 2490, 2491, 2493, 2682, 2684, 2685.

Sheet 8 - 415, 417, 419, 421, 429, 430, 431, 432, 433, 434, 476, 477, 478, 481, 483, 485, 488, 489, 491, 498, 499, 500, 501, 503, 504, 508, 509, 512, 516, 520, 521, 522, 531, 532, 533, 534, 542, 543, 544, 545, 546, 548, 550, 553, 554, 555, 557, 563, 564, 1005, 1006, 1008, 1024, 1030, 1033, 1037, 1039, 1041, 1043, 1046, 1047, 1048, 1056, 1058, 1059, 1174, 1176, 1220, 1489, 2224, 2727, 2728, 2775.

Sheet 9 - 1424, 1430, 1434, 1436, 1437, 1438, 1439, 1441, 1442, 1444, 1446, 1450, 1459, 1555, 1556, 1557, 1559, 1561, 1562, 1563, 1564, 1565, 1567, 1570, 1575, 1576, 1583, 1585, 1588, 1590, 1594, 1598, 1600, 1601, 1603, 1604, 1607, 1608, 1609, 1611, 1612, 1613, 1614, 1615, 1616, 1617, 1618, 1619, 1620, 1622, 1623, 1624, 1627, 1631, 1632, 1633, 1634, 1635, 1636, 1638,

1639, 1641, 1643, 1644, 1646, 1647, 1648, 1657, 1659, 2095, 2137.

Sheet 11 - 1511, 1512, 1513, 1517, 1518, 1520, 1523, 1525, 1526, 1530, 1531, 1532, 1533.

Sheet 12 - 2386, 2388, 2390, 2391, 2395, 2396.

Sheet 16 - 2354, 2355, 2356, 2357, 2363, 2364, 2366, 2367, 2369, 2370, 2371, 2372, 2373, 2374, 2376, 2377.

Probable Cairn

Sheet 2 - 2161.

Sheet 3 - 1386, 2624, 2625, 2648.

Sheet 4 - 2579.

Sheet 5 - 2280.

Sheet 7 - 2492, 2687.

Sheet 8 - 1032.

Sheet 9 - 1429, 1432, 1440, 1460, 1593, 1595, 1597, 1605, 1606.

Possible Cairn

Sheet 2 - 2196, 2318, 2319, 2320, 2324, 2325.

Sheet 3 - 1369, 2618, 2627, 2649, 2653, 2665, 2669, 2731.

Sheet 4 - 31, 40, 123, 155, 201, 205, 212, 274, 342, 359, 368, 595, 597, 1104, 1116, 1134, 1240, 1266, 1419, 2588.

Sheet 5 - 2009, 2026, 2030, 2072, 2094, 2096, 2269, 2792.

Sheet 6 - 2516.

Sheet 7 - 2419, 2420, 2431.

Sheet 8 - 511, 517, 519, 549, 1011, 1012, 1027, 1224.

Sheet 9 - 1426, 1427, 1443, 1575, 1602, 1617, 1625, 1649, 1651, 1654, 2135, 2136.

Sheet 11 - 1534.

Sheet 12 - 2392, 2393, 2397, 2799.

Sheet 13 - 1279, 1281, 1282, 1294, 1694, 1704, 1705, 1706.

Sheet 16 - 2350, 2353, 2362, 2365.

Linear Clearance

Sheet 2 - 2162, 2163, 2164, 2165, 2172, 2238, 2313, 2689.

Sheet 3 - 14, 1352, 1357, 1726, 1727, 1729, 2534, 2599, 2608, 2613, 2626, 2646, 2647, 2668.

Sheet 4 - 16, 26, 32, 38, 109, 117, 119, 128, 132, 137, 147, 149, 164, 166, 173, 181, 182, 208, 226, 229, 231, 234, 235, 237, 244, 245, 249, 270, 275, 278, 280, 287, 288, 290, 292, 294, 301, 305, 314, 323, 325, 351, 354, 376, 395, 398, 471, 1087, 1088, 1142, 1253, 1257, 1267, 1271, 1273, 1275, 1317, 1324, 1328, 1332, 1346, 1415, 1417, 1422, 2570, 2694.

Sheet 5 - 2001, 2019, 2041, 2045, 2052, 2061, 2070, 2073, 2255, 2262, 2263, 2273, 2274, 2276, 2278, 2279.

Sheet 6 - 2499, 2524, 2525.

Sheet 7 - 2404, 2407, 2408, 2421, 2423, 2424, 2427, 2444, 2447, 2454, 2458, 2475, 2477, 2688.

Sheet 8 - 474, 480, 482, 484, 486, 496, 506, 515, 523, 527, 529, 535, 536, 537, 538, 539, 1007, 1017, 1019, 1022, 1029, 1034, 1038, 1040, 1042, 1044, 1045, 1170, 1171, 1177, 2221.

Sheet 9 - 1449, 1589, 1621.

Sheet 11 - 1516, 1519, 1522, 1527, 1528, 1539.

Sheet 12 - 2800.

Sheet 16 - 2368.

Probable Linear Clearance

Sheet 2 - 2166.

Possible Linear Clearance

Sheet 2 - 2178.

Sheet 3 - 1381.

Sheet 4 - 240, 286, 386, 597.

Sheet 5 - 2015, 2093, 2697.

Sheet 8 - 517, 1505.

Sheet 9 - 1577, 1578.

Sheet 11 - 1529.

Sheet 12 - 2402.

Sheet 16 - 2358.

Stone Bank

Sheet 2 - 2169, 2691.

Sheet 3 - 2418.

Sheet 4 - 36, 143, 151, 154, 178, 179, 265, 268, 1315, 1318, 2783.

Sheet 5 - 2023, 2028.

Sheet 8 - 420.

Possible Stone Bank

Sheet 4 - 153.

Bank

Sheet 4 - 1280.

Earthen Bank

Sheet 3 - 2468, 2598, 2601, 2610, 2611, 2614.

Sheet 4 - 122, 169, 203, 207, 211, 220, 251, 282, 296, 331, 332, 335, 336, 337,
338, 343, 344, 347, 358, 363, 410, 411, 428, 1156, 1351.

Sheet 6 - 2526.

Sheet 7 - 2452, 2455, 2457, 2460, 2463, 2476, 2489, 2683.

Sheet 8 - 413, 418, 475, 490, 494, 495, 497, 505, 507, 510, 514, 518, 530, 560,
562, 1016, 1018, 1023.

Sheet 9 - 1566.

Probable Earthen Bank

Sheet 8 - 493, 528.

Possible Earthen Bank

Sheet 4 - 1070, 1148.

Sheet 8 - 416.

Sheet 9 - 1650, 2700.

Probable Earthen Mound

Sheet 4 - 126, 129, 202.

Sheet 8 - 414.

Possible Earthen Mound

Sheet 4 - 380, 399, 402, 423.

Lynchet

Sheet 2 - 2173, 2175, 2179, 2289, 2781.

Sheet 3 - 1354, 1356, 1358, 1385, 1408, 2591, 2592, 2596, 2597, 2605.

Sheet 4 - 41, 94, 115, 145, 148, 165, 168, 174, 180, 198, 213, 225, 239, 260, 267,
277, 302, 304, 318, 325, 383, 385, 392, 393, 404, 435, 436, 470, 1062,
1072, 1075, 1076, 1081, 1128, 1145, 1149, 1152, 1153, 1157, 1159, 1160,
1181, 1235, 1236, 1260, 1261, 1295, 1297, 1300, 1301, 1306, 1307, 1310,
1327, 1347, 1414, 2535, 2565, 2575, 2578, 2681, 2695, 2768, 2769, 2772,
2789.

Sheet 5 - 2007, 2010, 2017, 2018, 2020, 2021, 2043, 2065, 2699.

Sheet 6 - 2500, 2527, 2529.

Sheet 7 - 2428, 2429, 2441, 2446, 2452, 2460, 2464.

Sheet 8 - 492, 524, 526, 541, 552, 558, 1010, 1014, 1021, 1025, 1031, 1173.

Sheet 9 - 1451, 1566, 1656, 1660.

Sheet 12 - 2389.

Probable Lynchet

Sheet 4 - 218, 1272.

Sheet 7 - 2481.

Sheet 8 - 1175.

Possible Lynchet

Sheet 4 - 324, 1126, 1139, 1242, 1413, 2750, 2787, 2790.

Sheet 5 - 1232, 2022, 2024, 2252, 2253, 2270.

Sheet 7 - 2445.

Sheet 8 - 559, 1001, 1036.

Sheet 9 - 1574, 1591, 1724.

Stoney Lynchet

Sheet 3 - 2606, 2615, 2784.

Sheet 4 - 33, 1225, 1308, 1312, 1343, 1416, 1418, 1470, 2570.

Sheet 7 - 2406, 2409.

Sheet 8 - 1009.

Sheet 9 - 1431, 1445, 1571, 1596.

Possible Stoney Lynchet

Sheet 4 - 1136.

Boulder Scarp

Sheet 2 - 1329.

Sheet 3 - 1353, 1388, 1390, 1398, 1402.

Sheet 4 - 199, 200, 396, 1227, 1252, 1326, 1331, 1333, 1344.

Sheet 5 - 2012, 2013, 2051, 2097, 2100, 2282.

Sheet 6 - 2494, 2521, 2740, 2741.

Probable Boulder Scarp

Sheet 6 - 1553.

Possible Boulder Scarp

Sheet 4 - 34, 1321.

Sheet 5 - 1230, 1231, 2098.

Cultivation Edge

Sheet 3 - 2590, 2593, 2629.

Sheet 4 - 1265.

Sheet 6 - 2517, 2519.

Sheet 11 - 1515.

Possible Cultivation Edge

Sheet 4 - 1242.

Sheet 5 - 1457.

Clearance Stone

Sheet 2 - 2312.

Sheet 3 - 2607.

Sheet 4 - 308, 375, 1184, 2576.

Sheet 5 - 2275, 2277, 2717.

Sheet 6 - 2497, 2515, 2742.

Sheet 9 - 1452, 1573.

Sheet 11 - 1514, 1524, 1540.

Sheet 16 - 2375.

Possible Clearance Stone

Sheet 2 - 2331.

Sheet 4 - 1251, 1268.

Sheet 7 - 2482.

Sheet 8 - 1221, 1222, 1499.

Sheet 9 - 1423.

Sheet 16 - 2351, 2352.

Possible Gate

Sheet 4 - 230, 232, 345, 626, 1089, 1114, 1154, 2566.

Sheet 8 - 412, 513, 1068.

Possible Track

Sheet 4 - 2573.

Possible Hollow Way

Sheet 4 - 580.

Possible Animal Pen

Sheet 4 - 352, 2564.

Possible Pond

Sheet 8 - 502.

Possible Hollow

Sheet 12 - 2394.

Possible Tree Ring

Sheet 4 - 31.

DOMESTIC

House Site

Sheet 4 - 1305.

Probable House Site

Sheet 3 - 2640.

Sheet 4 - 236, 266, 468, 627, 1067, 2572.

Sheet 5 - 2042.

Sheet 8 - 1038.

Possible House Site

Sheet 4 - 161, 276, 310, 622, 631, 1078, 1082, 1143, 1147, 1243, 1316, 1322, 2569.

Sheet 5 - 2063.

Sheet 7 - 2422.

Sheet 8 - 502, 630, 2798.

Sheet 9 - 1453, 1581, 1587.

Sheet 11 - 1524.

Possible Shieling

Sheet 4 - 31.

Platform

Sheet 3 - 2647.

Possible Platform

Sheet 3 - 1353.

Sheet 4 - 439.

Sheet 9 - 1569.

RITUAL

Ring Cairn/Stone Circle

Sheet 3 - 1392.

Sheet 9 - 1465, 1626.

Burial Cairn

Sheet 4 - 326.

Sheet 5 - 473.

Sheet 9 - 1454, 1463.

Probable Burial Cairn

Sheet 4 - 369, 387.

Sheet 16 - 2361.

Possible Burial Cairn

Sheet 2 - 2318

Sheet 3 - 1381, 2618.

Sheet 4 - 201, 1419.

Sheet 7 - 2431.

Sheet 8 - 1224.

Sheet 13 - 1279, 1281, 1282, 1294, 1694, 1705, 1706.

Possible Kerb Cairn

Sheet 3 - 2644.

Platform

Sheet 4 - 369.

Sheet 9 - 1454, 1463, 1576.

Possible Platform

Sheet 5 - 473.

Sheet 9 - 1575.

Cist

Sheet 4 - 1135.

Sheet 9 - 1628.

Possible Cist

Sheet 9 - 1612

Cup and Ring Carving

Sheet 7 - 2433.

Sheet 9 - 1628.

HISTORIC FEATURES

STONE QUARRIES

Quarry

Sheet 2 - 2183, 2184, 2187.

Sheet 3 - 2533.

Sheet 4 - 1338, 2803, 2804.

Sheet 5 - 2014, 2036, 2084, 2240, 2242, 2243, 2254, 2266, 2774, 2793, 2794.

Sheet 6 - 2530.

Sheet 8 - 1003.

Sheet 9 - 1448, 1467, 1468, 1579, 1580, 1584, 2122, 2129, 2144.

Sheet 13 - 1226, 1696, 1698, 1710, 2701, 2805.

Sheet 16 - 2348.

Sheet 18 - 2532.

Possible Quarry

Sheet 3 - 1382.

Sheet 4 - 2584.

Sheet 9 - 1586.

Dressed Stone

Sheet 4 - 1335, 1336.

Sheet 6 - 1541.

Sheet 9 - 1572.

Stone Bank

Sheet 3 - 2589.

Stone Bank or Shelter

Sheet 13 - 1691.

Sheet 15 - 1722.

Wall or Shelter

Sheet 4 - 1338.

Mound

Sheet 3 - 2589.

Building

Sheet 4 - 1334.

Pile of Stones

Sheet 4 - 1339.

Sheet 6 - 1551.

Possible Pile of Stones

Sheet 5 - 2096.

MINING

Mine

Sheet 8 - 1053, 1055, 1491.

Sheet 12 - 2230.

Possible Mine

Sheet 8 - 1488.

Bell Pit

Sheet 4 - 2556

Sheet 7 - 1501, 2411.

Sheet 8 - 1049, 1050, 1200, 1201, 1202, 1205, 1206, 1207, 1217, 1504, 1537.

Probable Bell Pit

Sheet 8 - 1506.

Possible Bell Pit

Sheet 8 - 1500.

Sheet 11 - 1521.

Mine Pits

Sheet 8 - 1052, 1054, 1203, 1204.

Pile of Stones

Sheet 8 - 1494.

Building

Sheet 8 - 1051.

Possible Shelter

Sheet 4 - 2680.

HOLLOW WAYS, TRACKS, PATHS AND GUIDESTONES

Hollow Way

Sheet 1 - 2710, 2711, 2712.

Sheet 2 - 2174, 2310, 2311, 2317.

Sheet 3 - 1348, 1391, 2417, 2594, 2636, 2733, 2735, 2762, 2763, 2764, 2765, 2778, 2779.

Sheet 4 - 309, 321, 583, 1071, 1084, 1237, 1249, 1258, 2734, 2746.

Sheet 5 - 574, 586, 1479, 2035, 2048, 2056, 2057, 2058, 2060, 2068, 2074, 2075, 2077, 2083, 2086, 2092, 2101, 2103, 2106, 2107, 2108, 2109, 2110, 2112, 2113, 2114, 2752, 2753, 2754, 2755, 2756, 2757, 2773.

Sheet 6 - 2522, 2523, 2738, 2761, 2796.

Sheet 7 - 2448, 2449, 2469, 2729, 2730.

Sheet 8 - 570, 1000, 2213, 2726, 2766, 2776, 2777.

Sheet 9 - 1592, 2130, 2133.

Sheet 10 - 2760.

Sheet 11 - 2743, 2744, 2745, 2759.

Sheet 13 - 565, 1284, 1285, 1288, 1291, 1292, 1293, 1686, 1688, 1690, 1692, 1695, 1703, 1707, 1708, 2236, 2718, 2719, 2720, 2721, 2723.

Sheet 15 - 1461, 2713, 1714.

Sheet 16 - 1476.

Probable Hollow Way

Sheet 6 - 2739.

Possible Hollow Way

Sheet 2 - 2157, 2323.

Sheet 4 - 2750.

Sheet 5 - 1455, 1478, 2089.

Sheet 7 - 2413, 2416.

Sheet 8 - 2797.

Sheet 9 - 1568, 2115.

Sheet 12 - 2399.

Sheet 13 - 2228, 2722.

Sheet 15 - 2715.

Causeway

Sheet 3 - 2677, 2678.

Possible Causeway

Sheet 7 - 2414.

Mound

Sheet 7 - 2415.

Pile of Stones

Sheet 2 - 2692.

Sheet 3 - 1373.

Sheet 6 - 2511.

Sheet 7 - 2495.

Sheet 8 - 1028, 1178.

Sheet 13 - 1287, 1689, 1718.

Possible Pile of Stones

Sheet 3 - 1369.

Sheet 4 - 386, 567.

Sheet 12 - 2397, 2799.

Track

Sheet 4 - 582, 1073.

Sheet 5 - 574, 2048, 2081, 2082.

Sheet 8 - 1228, 1229.

Sheet 9 - 2121.

Sheet 16 - 2795.

Drain

Sheet 5 - 2085, 2087, 2089, 2265, 2267.

Sheet 9 - 1458.

Probable Drain

Sheet 9 - 2134.

Paved Path

Sheet 2 - 2309.

Sheet 3 - 1378.

Sheet 13 - 1289.

Possible Paving Stone

Sheet 8 - 2212.

Guidestone

Sheet 2 - 2316.

Sheet 4 - 2791.

Sheet 8 - 568, 573.

Possible Guidestone

Sheet 3 - 566

Sheet 4 - 1063.

Bridge/Bridge Abutment

Sheet 5 - 2047.

Sheet 13 - 1709, 1717, 1719.

Possible Bridge

Sheet 8 - 2223.

GROUSE SHOOTING BUTTS AND ASSOCIATED STRUCTURES

Shooting Butt

Sheet 3 - 1370.

Sheet 4 - 224, 587, 588, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602.

Sheet 5 - 603, 604.

Possible Shooting Butt

Sheet 3 - 1384.

Sheet 8 - 1057, 1169, 2220.

Sheet 12 - 2229.

Stone Structure

Sheet 5 - 2046.

Possible Water Tank

Sheet 4 - 611.

Drain

Sheet 4 - 612.

RESERVOIRS AND ASSOCIATED STRUCTURES

Reservoir

Sheet 13 - 2801.

Dam

Sheet 13 - 2802.

Reservoir Earthwork

Sheet 13 - 1720

Possible Reservoir Earthwork

Sheet 13 - 2722

Sluice

Sheet 13 - 1721.

Conduit

Sheet 8 - 2218, 2239.

Drain

Sheet 13 - 2225, 2226, 2232, 2233.

Pump

Sheet 5 - 2806.

Pipeline/Vent Pipe

Sheet 8 - 2219.

Sheet 13 - 1711, 1712.

Sheet 15 - 1723.

Pile of Stones

Sheet 9 - 2127.

Sheet 13 - 1700, 1701.

Bank

Sheet 9 - 1428, 2117, 2118, 2128, 2237.

Scarp

Sheet 5 - 2090.

Sheet 9 - 1425, 1447, 2126.

Possible Scarp or Bank

Sheet 9 - 2145.

Disturbance

Sheet 9 - 2143.

Platform

Sheet 9 - 2125.

Stone Setting

Sheet 9 - 2123.

WORLD WAR II MILITARY FIELDWORKS

Slit Trench

Sheet 1 - 2378, 2379, 2380, 2383, 2384.

Sheet 2 - 2204.

Sheet 3 - 1361, 1362, 1363, 1366, 1374, 2604, 2617, 2619, 2623, 2631, 2632, 2634, 2638, 2645, 2654, 2655, 2656, 2657, 2660, 2661, 2666, 2674, 2675.

Sheet 4 - 1064, 1065, 1069, 1083, 1086, 1099, 1108, 1110, 1111, 1112, 1117, 1118, 1119, 1120, 1121, 1122, 1123, 1124, 1129, 1132, 1138, 1150, 1151, 1158, 1233, 1234, 1239, 1244, 1420, 1702, 1725, 2294, 2297, 2299, 2300, 2302, 2304, 2551, 2552, 2553, 2563, 2567, 2587, 2703, 2704, 2705.

Sheet 5 - 2078, 2079, 2259, 2261.

Sheet 6 - 1546, 1547, 2512, 2528.

Sheet 7 - 2478, 2497, 2480, 2484, 2485, 2486, 2488.

Sheet 8 - 2149, 2150, 2215, 2217.

Sheet 9 - 1599, 2120.

Sheet 13 - 1663, 1714, 1716, 2707.

Possible Slit Trench

Sheet 13 - 1662.

Sheet 16 - 2347.

Pit/Paired Pits

Sheet 1 - 2385.

Sheet 2 - 2158, 2159, 2167, 2180, 2205, 2208, 2211, 2322, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340.

Sheet 3 - 1359, 1360, 1365, 1367, 1368, 1375, 1394, 1395, 1396, 1397, 1399, 1400, 1401, 1403, 1404, 1405, 1406, 2622, 2628, 2633, 2635, 2676.

Sheet 4 - 605, 606, 610, 613, 614, 615, 616, 617, 1060, 1061, 1066, 1085, 1090, 1092, 1093, 1094, 1095, 1096, 1097, 1100, 1102, 1103, 1105, 1106, 1107, 1109, 1115, 1125, 1127, 1130, 1131, 1133, 1238, 1241, 1246, 1247, 1254, 1256, 1270, 2283, 2293, 2295, 2296, 2298, 2301, 2303, 2305, 2306, 2307, 2536, 2537, 2538, 2539, 2540, 2543, 2544, 2546, 2547, 2548, 2549, 2550,

2554, 2557, 2558, 2559, 2560, 2561, 2562, 2568, 2580, 2581, 2582, 2583,
2585, 2586, 2702, 2751, 2767.

Sheet 5 - 1474, 1475, 1477, 2005, 2006, 2008, 2059, 2062, 2067, 2080, 2245, 2248,
2249, 2250, 2258, 2260, 2268, 2345.

Sheet 6 - 1548, 1549, 2505, 2506, 2507, 2508, 2509, 2510.

Sheet 7 - 1502, 2412, 2483, 2487.

Sheet 8 - 479, 621, 1015, 1020, 1026, 1210, 1481, 1482, 1484, 1485, 1486, 1487,
1493, 1495, 1496, 1497, 1498, 1507, 1508, 1509, 1510, 2149, 2214, 2216.

Sheet 9 - 1435, 1610, 1637, 1642, 1645, 1652, 1658, 2138, 2139, 2706.

Sheet 12 - 2387.

Sheet 13 - 1283, 1290, 1664, 1665, 1666, 1667, 1668, 1669, 1670, 1671, 1672,
1673, 1674, 1675, 1676, 1677, 1678, 1679, 1680, 1681, 1682, 1683, 1684,
1687, 1699, 1713, 1715, 2235.

Sheet 17 - 2341, 2343, 2344.

Probable Pit

Sheet 4 - 2541.

Possible Pit/Possible Paired Pits

Sheet 2 - 2321, 2326, 2327, 2328.

Sheet 3 - 1364

Sheet 4 - 2542, 2584, 2679.

Sheet 5 - 1480.

Sheet 8 - 1208, 1503.

Military Fieldwork

Sheet 4 - 1345, 2555.

Sheet 13 - 1697.

Possible Military Fieldwork

Sheet 4 - 2680, 2770, 2788.

Sheet 8 - 1057, 1169, 2220.

Sheet 12 - 2229.

Mound

Sheet 4 - 1098.

Possible Mound

Sheet 4 - 126, 129, 202, 380, 399, 402, 423, 620.

Pile of Stones

Sheet 6 - 1545.

Possible Pile of Stones

Sheet 13- 1279.

Disturbance

Sheet 5 - 2246, 2247.

Bullet Scars/Bullet and Mortar Scars

Sheet 1 - 2381, 2382.

Sheet 2 - 2156, 2160, 2181, 2182, 2185, 2194, 2201, 2206, 2207, 2210, 2284, 2329, 2330.

Sheet 3 - 1377, 1379.

Sheet 4 - 317, 375, 1135, 1245, 1248, 1334, 1345, 2786, 2791.

Sheet 5 - 2004, 2016, 2032, 2033, 2034, 2039, 2049, 2076.

Sheet 6 - 2513.

Sheet 7 - 2432.

Sheet 8 - 573, 568, 1004, 1211, 1212, 1213, 1223, 2153, 2154, 2222.

Sheet 9 - 2119, 2146, 2147, 2148.

Sheet 13 - 1685.

Sheet 17 - 2342.

ARCHAEOLOGICAL EXCAVATIONS

Excavation Trench

Sheet 2 - 2288.

Sheet 4 - 619, 1277, 1299, 1302, 1304, 1313, 1320, 2696.

Sheet 9 - 1463, 1465, 1561, 1626.

Possible Excavation Trench

Sheet 4 - 576, 1321.

Sheet 9 - 1471.

Spoil Mound

Sheet 2 - 2168, 2170.

Sheet 4 - 1278, 1298, 1303, 1314, 1323, 2785.

Sheet 9 - 1463, 1560, 1629, 1630.

Bank

Sheet 4 - 1280.

OTHER FEATURES

Sheep Lea

Sheet 12 - 2401.

Sheet 16 - 2359.

Possible Sheep Lea

Sheet 5 - 2697.

Pile of Stones

Sheet 16 - 2360.

Shelter

Sheet 4 - 1337.

Possible Shelter

Sheet 4 - 2770, 2788.

Sheet 12 - 2402.

Ditch

Sheet 3 - 1376.

Headstone

Sheet 9 - 1464.

Posthole

Sheet 13 - 1693.

Possible Robber Trench

Sheet 3 - 1382.

Foundation Trench

Sheet 3 - 1380.

Stone Setting

Sheet 9 - 2132.

Drain

Sheet 5 - 1456.

Possible Drain

Sheet 8 - 1488, 1492.

Stone Bank
Sheet 5 - 2698.

Pile of Stones
Sheet 18 - 2531.

Possible Pile of Stones
Sheet 5 - 2055.

Sheet 13 - 1294.

Pit
Sheet 5 - 624.

Sheet 8 - 625.

Sheet 9 - 1558

Sheet 12 - 2398, 2400.

Probable Pit
Sheet 9 - 1582.

Possible Pit
Sheet 9 - 1471.

Mound
Sheet 9 - 1558, 1582.

Possible Mound
Sheet 9 - 1661.

Possible Scarp or Bank
Sheet 9 - 2145.

Hollow
Sheet 8 - 1172.

Sheet 12 - 2399.

NATURAL

Stoney Spread
Sheet 12 - 2231.

Stone
Sheet 6 - 1550.

Sheet 9 - 1433, 1466.

Hollow

Sheet 15 - 2716.

Drainage Gully

Sheet 2 - 2209.

Terrace

Sheet 8 - 1002.

Mound

Sheet 4 - 618.

Sheet 5 - 2111, 2186.

Sheet 8 - 1214, 1218.

Sheet 9 - 1462, 1653, 1655.

Sheet 11 - 1535, 1536, 1538.

Sheet 12 - 2403.


Animal Disturbance

Sheet 3 - 2732.

Sheet 4 - 623.

Sheet 7 - 2456, 2461, 2462, 2470, 2473, 2474.

INDEX DIAGRAM FOR SHEET NUMBERS



2

Sheet number. Each sheet covers an area 500m square. Sheet edges marked by bold lines.